


Post bolt slots
3/4" x 2 1/2"

Splice bolt slots
3/4" x 1 1/8"



SPECIFICATIONS

Rub rails shall conform to A.S.T.M. A36 and shall be galvanized in accordance with A.S.T.M. A123 except when corrosion resistant rails are requested, in which case rub rails shall conform to A.S.T.M. A588 and shall not be painted nor galvanized.

No punching, drilling, or cutting will be permitted after galvanizing.

Dimensional tolerances not shown or implied are intended to be those consistent with the proper functioning of the part, including its appearance and accepted manufacturing practices.

INTENDED USE

This channel is used as a rub rail in the standard 'W' Beam Guard-rail and 'W' Beam Median Barrier designs G4, MB4, and MB4B.

Note: This rail may be used as an alternate to RE-9[]-73.
For splice bolts see F-9[1 1/2"]-73.

BENT PLATE RUB RAIL

HM-TF-13

STANDARD

RE-72-76