



**Test Report No. 609591-03**  
**Test Report Date: September 2018**

## ***MASH TL-5 Evaluation of PennDOT PA Bridge Barrier***

by

D. Lance Bullard, Jr., P.E.  
Senior Research Engineer

Bill Griffith  
Research Specialist

and

Darrell L. Kuhn, P.E.  
Research Specialist



Contract No.: PDT-E03657  
Test No.: 609591-03-1, -2, -3  
Test Date: July 2018

Sponsored by  
**Pennsylvania Department of Transportation**

---

### **TEXAS A&M TRANSPORTATION INSTITUTE PROVING GROUND**

Mailing Address:  
Roadside Safety & Physical Security  
Texas A&M University System  
3135 TAMU  
College Station, TX 77843-3135

Located at:  
Texas A&M University RELLIS Campus  
Building 7091  
3100 State Highway 47  
Bryan, TX 77807



## DISCLAIMER

The contents of this report reflect the views of the authors, who are solely responsible for the facts and accuracy of the data, and the opinions, findings, and conclusions presented herein. The contents do not necessarily reflect the official views or policies of the Pennsylvania Department of Transportation, The Texas A&M University System, or Texas A&M Transportation Institute. This report does not constitute a standard, specification, or regulation. In addition, the above listed agencies/ companies assume no liability for its contents or use thereof. The names of specific products or manufacturers listed herein do not imply endorsement of those products or manufacturers.

The results reported herein apply only to the article being tested. The full-scale crash tests were performed according to TTI Proving Ground quality procedures and according to the *MASH* guidelines and standards.

The Proving Ground Laboratory within the Texas A&M Transportation Institute's Roadside Safety and Physical Security Division ("TTI Lab" or "TTI LAB") strives for accuracy and completeness in its crash test reports. On rare occasions, unintentional or inadvertent clerical errors, technical errors, omissions, oversights, or misunderstandings (collectively referred to as "errors") may occur and may not be identified for corrective action prior to the final report being published and issued. When the TTI Lab discovers an error in a published and issued final report, the TTI Lab shall promptly disclose such error to Gannet Fleming, Inc and the Pennsylvania Department of Transportation, and both parties shall endeavor in good faith to resolve this situation. The TTI Lab will be responsible for correcting the error that occurred in the report, which may be in form of errata, amendment, replacement sections, or up to and including full reissuance of the report. The cost of correcting an error in the report shall be borne by TTI Lab. Any such errors or inadvertent delays that occur in connection with the performance of the related testing contract shall not constitute a breach of the testing contract.

**THE TTI LAB SHALL NOT BE LIABLE FOR ANY INDIRECT, CONSEQUENTIAL, PUNITIVE, OR OTHER DAMAGES SUFFERED BY GANNET FLEMING, INC. AND THE PENNSYLVANIA DEPARTMENT OF TRANSPORTATION OR ANY OTHER PERSON OR ENTITY, WHETHER SUCH LIABILITY IS BASED, OR CLAIMED TO BE BASED, UPON ANY NEGLIGENT ACT, OMISSION, ERROR, CORRECTION OF ERROR, DELAY, OR BREACH OF AN OBLIGATION BY THE TTI LAB.**

1. Report No.		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle <b>MASH TL-5 Evaluation of PennDOT PA Bridge Barrier</b>				5. Report Date <b>September 2018</b>	
				6. Performing Organization Code	
7. Author(s) <b>D. Lance Bullard, Jr., Bill Griffith, and Darrell L. Kuhn</b>				8. Performing Organization Report No. <b>Test Report No. 609591-03</b>	
9. Performing Organization Name and Address <b>Texas A&amp;M Transportation Institute Proving Ground 3135 TAMU College Station, Texas 77843-3135</b>				10. Work Unit No. (TRAIS)	
				11. Contract or Grant No. <b>PDT-E03657</b>	
12. Sponsoring Agency Name and Address <b>Gannett Fleming, Inc PO Box 67100 Harrisburg, PA 17106-7100</b>  <b>Pennsylvania Department of Transportation Bureau of Project Delivery Bridge Design and Technology Division 400 North Street, 7th Floor Harrisburg, PA 17120</b>				13. Type of Report and Period Covered <b>Technical Report: October 2017 – September 2018</b>	
				14. Sponsoring Agency Code	
15. Supplementary Notes <b>Project Title: MASH test 5-10, 5-11, 5-12</b> <b>Name of Contacting Representative: Travis C. Arentz, P.E. (Gannett Fleming, Inc.) and Tom Macioce, P.E. (PennDOT)</b>					
16. Abstract  <p>TTI evaluated the performance of the PennDOT PA Bridge Barrier in accordance with criteria specified in the American Association of State Highway and Transportation Officials (AASHTO), <i>Manual for Assessing Safety Hardware (MASH, Second Edition, 2016)</i>. MASH Tests 5-10, 5-11, and 5-12 were performed on the bridge rail. The tests involved an 1100C and a 2270P vehicle, each impacting the PennDOT PA Bridge Barrier at a target impact speed and impact angle of 62 mi/h and 25°, respectively, and a 36000V vehicle impacting the PennDOT PA Bridge Barrier at a target impact speed and impact angle of 50 mi/h and 15°, respectively.</p> <p>Assessment of the tests based on the applicable safety evaluation criteria for longitudinal barriers showed that the PennDOT PA Bridge Barrier performed acceptably for MASH Tests 5-10, 5-11, and 5-12.</p>					
17. Key Words <b>Longitudinal Barrier, Concrete Barrier, Bridge Barrier, Crash Testing, Roadside Safety</b>			18. Distribution Statement <b>Copyrighted. Not to be copied or reprinted without consent from Pennsylvania Department of Transportation</b>		
19. Security Classif.(of this report) <b>Unclassified</b>		20. Security Classif.(of this page) <b>Unclassified</b>		21. No. of Pages <b>166</b>	22. Price

*This page intentionally left blank.*

## REPORT AUTHORIZATION

---

### REPORT REVIEWED BY:

DocuSigned by:

*Glenn Schroeder*

F092F9C85047487...

Glenn Schroeder, Research Specialist  
Drafting & Reporting

DocuSigned by:

*Ken Reeves*

60D556035506468...

Ken Reeves, Research Specialist  
Electronics Instrumentation

DocuSigned by:

*Gary Gerke*

FDA2101E3F6B487...

Gary Gerke, Research Specialist  
Construction

DocuSigned by:

*Richard Badillo*

0F31DA00A6144F9...

Richard Badillo, Research Specialist  
Photographic Instrumentation

DocuSigned by:

*Scott Dobrovolny*

1C013885787C44C...

Scott Dobrovolny, Research Specialist  
Mechanical Instrumentation

DocuSigned by:

*Wanda L. Menges*

B92179022AF24FE...

Wanda L. Menges, Research Specialist  
Reporting & Deputy QM



Crash testing performed at:  
TTI Proving Ground  
3100 SH 47, Building 7091  
Bryan, TX 77807

DocuSigned by:

*Darrell L. Kuhn*

D4CC23E85D5B4E7...

Darrell L. Kuhn, P.E., Research Specialist  
Quality Manager

DocuSigned by:

*Matthew Robinson*

EAA20DFA5BFD447...

Matthew N. Robinson, Research Specialist  
Test Facility Manager & Technical Manager

DocuSigned by:

*D. Lance Bullard, Jr., P.E.*

1968DD6587A049C...

D. Lance Bullard, Jr., P.E.  
Senior Research Engineer

*This page intentionally left blank.*

# TABLE OF CONTENTS

	Page
<b>Disclaimer</b> .....	ii
<b>Table of Contents</b> .....	vii
<b>List of Figures</b> .....	ix
<b>List of Tables</b> .....	xi
<b>Chapter 1. Introduction</b> .....	1
<b>Chapter 2. System Details</b> .....	3
2.1. Test Article and Installation Details .....	3
2.2. Material Specifications .....	6
<b>Chapter 3. Test Requirements and Evaluation Criteria</b> .....	7
3.1. Crash Test Performed / Matrix .....	7
3.2. Evaluation Criteria.....	7
<b>Chapter 4. Test Conditions</b> .....	9
4.1. Test Facility .....	9
4.2. Vehicle Tow and Guidance System.....	9
4.3. Data Acquisition Systems .....	10
4.3.1. Vehicle Instrumentation and Data Processing .....	10
4.3.2. Anthropomorphic Dummy Instrumentation .....	11
4.3.3. Photographic Instrumentation Data Processing.....	11
<b>Chapter 5. MASH Test 5-11 (Crash Test No. 609591-03-1)</b> .....	13
5.1. Test Designation and Actual Impact Conditions .....	13
5.2. Weather Conditions .....	13
5.3. Test Vehicle .....	13
5.4. Test Description .....	14
5.5. Damage to Test Installation .....	14
5.6. Vehicle Damage.....	15
5.7. Occupant Risk Factors .....	16
<b>Chapter 6. MASH Test 5-10 (Crash Test No. 609591-03-2)</b> .....	19
6.1. Test Designation and Actual Impact Conditions .....	19
6.2. Weather Conditions .....	19
6.3. Test Vehicle .....	19
6.4. Test Description.....	20
6.5. Damage to Test Installation .....	21
6.6. Vehicle Damage.....	22
6.7. Occupant Risk Factors .....	23
<b>Chapter 7. MASH Test 5-12 (Crash Test No. 609591-03-3)</b> .....	27
7.1. Test Designation and Actual Impact Conditions .....	27
7.2. Weather Conditions .....	27
7.3. Test Vehicle .....	27
7.4. Test Description.....	28
7.5. Damage to Test Installation .....	29
7.6. Vehicle Damage.....	30
7.7. Occupant Risk Factors .....	30
<b>Chapter 8. Summary and Conclusions</b> .....	33

8.1	Assessment of Test Results.....	33
8.2	Conclusions.....	33
	<b>References.....</b>	<b>38</b>
	<b>Appendix A. Details of the Bridge Rail.....</b>	<b>41</b>
	<b>Appendix B. Supporting Certification Documents.....</b>	<b>51</b>
	<b>Appendix C. MASH Test 5-11 (Crash Test No. 609591-03-1).....</b>	<b>107</b>
C1	Vehicle Properties and Information.....	107
C2	Sequential Photographs.....	111
C3	Vehicle Angular Displacements .....	114
C4	Vehicle Accelerations .....	115
	<b>Appendix D. MASH Test 5-10 (Crash Test No. 609591-03-2).....</b>	<b>121</b>
D1	Vehicle Properties and Information.....	121
D2	Sequential Photographs.....	124
D3	Vehicle Angular Displacements .....	127
D4	Vehicle Accelerations .....	128
	<b>Appendix E. MASH Test 5-12 (Crash Test No. 609591-03-3).....</b>	<b>135</b>
E1	Vehicle Properties and Information.....	135
E2	Sequential Photographs.....	137
E3	Vehicle Angular Displacements .....	140
E4	Vehicle Accelerations .....	141



## LIST OF FIGURES

	<b>Page</b>
Figure 2.1. Details of the PennDOT PA Bridge Barrier.....	4
Figure 2.2. PennDOT PA Bridge Barrier prior to Testing.....	5
Figure 2.3. Concrete Map Overview of the of the PennDOT PA Bridge Barrier.....	6
Figure 5.1. PennDOT PA Bridge Barrier/Test Vehicle Geometrics for Test No. 609591-03-1.....	13
Figure 5.2. Test Vehicle before Test No. 609591-03-1.....	14
Figure 5.3. PennDOT PA Bridge Barrier after Test No. 609591-03-1.....	15
Figure 5.4. Test Vehicle after Test No. 609591-03-1.....	16
Figure 5.5. Interior of Test Vehicle for Test No. 609591-03-1.....	16
Figure 5.6. Summary of Results for <i>MASH</i> Test 5-11 on PennDOT PA Bridge Barrier.....	18
Figure 6.1. PennDOT PA Bridge Barrier/Test Vehicle Geometrics for Test No. 609591-03-2.....	20
Figure 6.2. Test Vehicle before Test No. 609591-03-2.....	20
Figure 6.3. PennDOT PA Bridge Barrier after Test No. 609591-03-2.....	22
Figure 6.4. Test Vehicle after Test No. 609591-03-2.....	23
Figure 6.5. Interior of Test Vehicle for Test No. 609591-03-2.....	23
Figure 6.6. Summary of Results for <i>MASH</i> Test 5-10 on PennDOT PA Bridge Barrier.....	25
Figure 7.1. PennDOT PA Bridge Barrier/Test Vehicle Geometrics for Test No. 609591-03-3.....	27
Figure 7.2. Test Vehicle before Test No. 609591-03-3.....	28
Figure 7.3. PennDOT PA Bridge Barrier after Test No. 609591-03-3.....	29
Figure 7.4. Test Vehicle after Test No. 609591-03-3.....	30
Figure 7.5. Interior of Test Vehicle for Test No. 609591-03-3.....	30
Figure 7.6. Summary of Results for <i>MASH</i> Test 5-12 on PennDOT PA Bridge Barrier.....	32
Figure C.1. Sequential Photographs for Test No. 609591-03-1 (Overhead and Gut Views).....	111
Figure C.2. Sequential Photographs for Test No. 609591-03-1 (Rear View).....	113
Figure C.3. Vehicle Angular Displacements for Test No. 609591-03-1.....	114
Figure C.4. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-1 (Accelerometer Located at Center of Gravity).....	115
Figure C.5. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-1 (Accelerometer Located at Center of Gravity).....	116
Figure C.6. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-1 (Accelerometer Located at Center of Gravity).....	117
Figure C.7. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-1 (Accelerometer Located Rear of Center of Gravity).....	118
Figure C.8. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-1 (Accelerometer Located Rear of Center of Gravity).....	120
Figure C.9. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-1 (Accelerometer Located Rear of Center of Gravity).....	120
Figure D.1. Sequential Photographs for Test No. 609591-03-2 (Overhead and Gut Views).....	124
Figure D.2. Sequential Photographs for Test No. 609591-03-2 (Rear View).....	126

Figure D.3. Vehicle Angular Displacements for Test No. 609591-03-2.....	127
Figure D.4. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-2 (Accelerometer Located at Center of Gravity).....	128
Figure D.5. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-2 (Accelerometer Located at Center of Gravity).....	129
Figure D.6. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-2 (Accelerometer Located at Center of Gravity).....	130
Figure D.7. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-2 (Accelerometer Located Rear of Center of Gravity).....	131
Figure D.8. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-2 (Accelerometer Located Rear of Center of Gravity).....	132
Figure D.9. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-2 (Accelerometer Located Rear of Center of Gravity).....	133
Figure E.1. Location of Accelerometers and Rate Transducers. ....	136
Figure E.2. Sequential Photographs for Test No. 609591-03-3 (Overhead and Gut Views). ....	137
Figure E.3. Sequential Photographs for Test No. 609591-03-3 (Rear View).....	139
Figure E.4. Vehicle Angular Displacements for Test No. 609591-03-3. (Accelerometer Located at Fifth Wheel).....	140
Figure E.5. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located at Fifth Wheel).....	141
Figure E.6. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located at Fifth Wheel).....	142
Figure E.7. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located at Fifth Wheel).....	143
Figure E.8. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located Rear of Trailer). ....	144
Figure E.9. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located Rear of Trailer). ....	145
Figure E.10. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located Rear of Trailer) ....	146
Figure E.11. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located at Tractor). ....	147
Figure E.12. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located at Tractor). ....	148
Figure E.13. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located at Tractor) .....	149

## LIST OF TABLES

	<b>Page</b>
Table 3.1. Test Conditions and Evaluation Criteria Specified for <i>MASH</i> TL-5 Longitudinal Barriers. ....	7
Table 3.2. Evaluation Criteria Required for <i>MASH</i> TL-5 Longitudinal Barriers. ....	8
Table 5.1. Events during Test No. 609591-03-1. ....	14
Table 5.2. Occupant Risk Factors for Test No. 609591-03-1. ....	17
Table 6.1. Events during Test No. 609591-03-2. ....	20
Table 6.2. Occupant Risk Factors for Test No. 609591-03-2. ....	24
Table 7.1. Events during Test No. 609591-03-3. ....	28
Table 7.2. Occupant Risk Factors for Test No. 609591-03-3. Measure from 5 <sup>th</sup> wheel Accelerometers .....	31
Table 8.1. Performance Evaluation Summary for <i>MASH</i> Test 5-11 on PennDOT PA Bridge Barrier. ....	34
Table 8.2. Performance Evaluation Summary for <i>MASH</i> Test 5-10 on PennDOT PA Bridge Barrier. ....	35
Table 8.3. Performance Evaluation Summary for <i>MASH</i> Test 5-12 on PennDOT PA Bridge Barrier. ....	36
Table 8.4. Assessment Summary for <i>MASH</i> TL-5 Tests on PennDOT PA Bridge Barrier. ....	37
Table C.1. Vehicle Properties for Test No. 609591-03-1. ....	107
Table C.2. Measurements of Vehicle Vertical CG for Test No. 609591-03-1. ....	108
Table C.3. Exterior Crush Measurements for Test No. 609591-03-1. ....	109
Table C.4. Occupant Compartment Measurements for Test No. 609591-03-1. ....	110
Table D.1. Vehicle Properties for Test No. 609591-03-2. ....	121
Table D.2. Exterior Crush Measurements for Test No. 609591-03-2. ....	122
Table D.3. Occupant Compartment Measurements for Test No. 609591-03-2. ....	123
Table E.1. Vehicle Properties for Test No. 609591-03-3. ....	135

*This page intentionally left blank.*

## Chapter 1. INTRODUCTION

The purpose of the tests reported herein was to assess the performance of the PennDOT PA Bridge Barrier according to the safety-performance evaluation guidelines included in the American Association of State Highway and Transportation Officials (AASHTO), *Manual for Assessing Safety Hardware (MASH) (1)*. The crash testing was performed in accordance with *MASH* Tests 5-10, 5-11, and 5-12, which involve an 1100C and a 2270P vehicle impacting the PennDOT PA Bridge Barrier at a target impact speed and impact angle of 62 mi/h and 25°, respectively, and a 36000V vehicle impacting the PennDOT PA Bridge Barrier at a target impact speed and impact angle of 50 mi/h and 15°, respectively.

This report provides details of the PennDOT PA Bridge Barrier, detailed documentation of the crash test results, and an assessment of the performance of the PennDOT PA Bridge Barrier for *MASH* Tests 5-10, 5-11, and 5-12 evaluation criteria.

*This page intentionally left blank.*

## Chapter 2. SYSTEM DETAILS

### 2.1. TEST ARTICLE AND INSTALLATION DETAILS

The test installation was comprised of a steel reinforced cantilevered concrete bridge deck, 11 inches thick, supporting a 24-inch tall × 18-inch thick steel reinforced concrete barrier. The test installation was constructed with three ½-inch wide joints, two extended through the parapet wall only, and the third through the wall and deck.

There were 20 posts attached to the top of the parapet using cast in place anchor bolts. The posts were spaced on 90-inch centers, beginning 44-inches from each end of the concrete deck and parapet, for a total installation length of 149 ft-10 inches. Two rectangular HSS 5×4×<sup>3</sup>/<sub>8</sub> rails were attached to each post, with the tops of the rails located 37 inches and 50 inches above grade, respectively.

Figure 2. presents overall information on the PennDOT PA Bridge Barrier, and Figure 2.2 provides photographs of the installation. Appendix A provides further details of the PennDOT PA Bridge Barrier.




Figure 2.1. Details of the PennDOT PA Bridge Barrier.






**Figure 2.2. PennDOT PA Bridge Barrier prior to Testing.**

## 2.2. MATERIAL SPECIFICATIONS

Appendix B provides material certification documents for the materials used to install/construct the PennDOT PA Bridge Barrier.

The specified minimum unconfined compressive strength of the concrete for the support wall, bridge deck and moment slab (moment slab was poured along with bridge deck batches) was 4,000 psi, the working slab was 3,000 psi, and the barrier was 3,500 psi. The average unconfined compressive strengths of the batches of concrete used in the construction of the test installation were as follows with locations of the different batches shown in the following illustration Figure 2.3



**Figure 2.3. Concrete Map Overview of the of the PennDOT PA Bridge Barrier**

Working Slab: 3,895 psi (over 5 batches) on 2018-05-19, 37 days from pour date.

Wall: 6,225 psi (over 3 batches) on 2018-05-31, 26 days from pour date.

Deck (moment slab): 5,815 psi (over 6 batches) on 2018-05-31, 26 days from pour date.

Barrier: 4,981 psi (over 2 batches) on 2018-06-05, 20 days from pour date.

Steel reinforcement of the bridge deck and wall was comprised of epoxy coated ASTM A615 Grade 60 rebar with specified minimum yield strength of 60 ksi.

## Chapter 3. TEST REQUIREMENTS AND EVALUATION CRITERIA

### 3.1. CRASH TEST PERFORMED / MATRIX

Table 3.1 shows the test conditions and evaluation criteria for *MASH* TL-5 for longitudinal barriers. *MASH* Test 5-10 involves an 1100C vehicle, weighing 2420 lb  $\pm$ 55 lb, impacting the critical impact point (CIP) of the barrier at an impact speed of 62 mi/h  $\pm$ 2.5 mi/h and an angle of 25°  $\pm$ 1.5°. *MASH* Test 5-11 involves a 2270P vehicle, weighing 5000 lb  $\pm$ 110 lb, impacting the CIP of the barrier at an impact speed of 62 mi/h  $\pm$ 2.5 mi/h and an angle of 25°  $\pm$ 1.5°. *MASH* Test 5-12 involves a 36000V vehicle weighing 79,300 lb  $\pm$ 1100 lb, impacting the CIP of the barrier at an impact speed of 50 mi/h  $\pm$ 2.5 mi/h and an angle of 15°  $\pm$ 1.5°.

The target CIPs were determined using the information provided in *MASH* Section 2.2.1 and Section 2.3.2, and Tables 2-7 and 2-8. The target CIP for *MASH* Test 5-11 on the PennDOT PA Bridge Barrier was 4.3 ft  $\pm$ 1 ft upstream of post 9 edge with lower rail splice. The target CIP for *MASH* Test 5-10 was 3.6 ft  $\pm$ 1 ft upstream of post 13 edge with lower rail splice. The target CIP for *MASH* Test 5-12 was 1 ft  $\pm$ 1 ft, downstream of post 5 edge with lower rail splice.

**Table 3.1. Test Conditions and Evaluation Criteria Specified for *MASH* TL-5 Longitudinal Barriers.**

Test Article	Test Designation	Test Vehicle	Impact Conditions		Evaluation Criteria
			Speed	Angle	
Longitudinal Barrier	5-10	1100C	62 mi/h	25°	A, D, F, H, I
	5-11	2270P	62 mi/h	25°	A, D, F, H, I
	5-12	36000V	50 mi/h	15°	A, D,G

The crash tests and data analysis procedures were in accordance with guidelines presented in *MASH*. Chapter 4 presents brief descriptions of these procedures.

### 3.2. EVALUATION CRITERIA

The appropriate safety evaluation criteria from Tables 2-2A and 5-1 of *MASH* were used to evaluate the crash tests reported herein. The test conditions and evaluation criteria required for *MASH* Tests 5-10, 5-11, and 5-12 are listed in Table 3.1, and the substance of the evaluation criteria in Table 3.2. An evaluation of the crash test results is presented in detail under the section Assessment of Test Results.

**Table 3.2. Evaluation Criteria Required for MASH TL-5 Longitudinal Barriers.**

Evaluation Factors	Evaluation Criteria	MASH Test
<b>Structural Adequacy</b>	A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	5-10, 5-11, 5-12
<b>Occupant Risk</b>	D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>  <i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	5-10, 5-11, 5-12
	F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	5-10, 5-11
	G. <i>It is preferable, although not essential, that the vehicle remain upright during and after the collision.</i>	5-12
	H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	5-10, 5-11
	I. <i>The occupant ridedown accelerations should satisfy the following: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	5-10, 5-11

## Chapter 4. TEST CONDITIONS

### 4.1. TEST FACILITY

The full-scale crash tests reported herein were performed at Texas A&M Transportation Institute (TTI) Proving Ground, an International Standards Organization (ISO)/International Electrotechnical Commission (IEC) 17025-accredited laboratory with American Association for Laboratory Accreditation (A2LA) Mechanical Testing Certificate 2821.01. The full-scale crash tests were performed according to TTI Proving Ground quality procedures, and according to the *MASH* guidelines and standards.

The test facilities of the TTI Proving Ground are located on the Texas A&M University RELLIS Campus, which consists of a 2000-acre complex of research and training facilities situated 10 miles northwest of the flagship campus of Texas A&M University. The site, formerly a United States Army Air Corps base, has large expanses of concrete runways and parking aprons well suited for experimental research and testing in the areas of vehicle performance and handling, vehicle-roadway interaction, durability and efficacy of highway pavements, and evaluation of roadside safety hardware and perimeter protective devices. The site selected for construction and testing of the PennDOT PA Bridge Barrier was at the end of an out-of-service runway. The runway consists of an unreinforced jointed-concrete pavement in 12.5-ft × 15-ft blocks nominally 6 inches deep. The runway was built in 1942, and the joints have some displacement, but are otherwise flat and level.

### 4.2 VEHICLE TOW AND GUIDANCE SYSTEM

For the 5-10 and 5-11 tests, the vehicle was towed into the test installation using a steel cable guidance and reverse tow system. A steel cable for guiding the test vehicle was tensioned along the path, anchored at each end, and threaded through an attachment to the front wheel of the test vehicle. An additional steel cable was connected to the test vehicle, passed around a pulley near the impact point, through a pulley on the tow vehicle, and then anchored to the ground such that the tow vehicle moved away from the test site. A 2:1 speed ratio between the test and tow vehicle existed with this system. Just prior to impact with the installation, the test vehicle was released and ran unrestrained. The vehicle remained freewheeling (i.e., no steering or braking inputs) until it cleared the immediate area of the test site (no sooner than 2 s after impact), after which the brakes were activated, if needed, to bring the test vehicle to a safe and controlled stop.

For the 5-12 test the vehicle was placed in 9<sup>th</sup> gear for the 5-12 test. With the vehicle idling the clutch was remotely engaged, to allow the truck to be pushed to speed. Once at speed, within the power band of the gear, the clutch was remotely released.. The accelerator was then remotely depressed and the vehicle accelerated under its own power to the required speed. A steel cable for guiding the test vehicle was tensioned along the path, anchored at each end, and threaded through an attachment to the front wheel of the test vehicle. The vehicle was released and ran unrestrained just prior to impact with the installation. The vehicle remained freewheeling (i.e., no steering or braking inputs) until it cleared the immediate area of the test site (no sooner than 2 s after impact), after which the brakes were activated, if needed, to bring the test vehicle to a safe and controlled stop.

## 4.3 DATA ACQUISITION SYSTEMS

### 4.3.1 Vehicle Instrumentation and Data Processing

Each test vehicle was instrumented with a self-contained, on-board data acquisition system. The signal conditioning and acquisition system is a 16-channel, Tiny Data Acquisition System (TDAS) Pro produced by Diversified Technical Systems, Inc. The accelerometers, which measure the x, y, and z axis of vehicle acceleration, are strain gauge type with linear millivolt output proportional to acceleration. Angular rate sensors, measuring vehicle roll, pitch, and yaw rates, are ultra-small, solid state units designed for crash test service. The TDAS Pro hardware and software conform to the latest SAE J211, Instrumentation for Impact Test. Each of the 16 channels is capable of providing precision amplification, scaling, and filtering based on transducer specifications and calibrations. During the test, data are recorded from each channel at a rate of 10,000 values per second with a resolution of one part in 65,536. Once data are recorded, internal batteries back these up inside the unit should the primary battery cable be severed. Initial contact of the pressure switch on the vehicle bumper provides a time zero mark as well as initiates the recording process. After each test, the data are downloaded from the TDAS Pro unit into a laptop computer at the test site. The Test Risk Assessment Program (TRAP) software then processes the raw data to produce detailed reports of the test results.

Each of the TDAS Pro units is returned to the factory annually for complete recalibration and all instrumentation used in the vehicle conforms to all specifications outlined by SAE J211. All accelerometers are calibrated annually by means of an ENDEVCO® 2901, precision primary vibration standard. This standard and its support instruments are checked annually and receive a National Institute of Standards Technology (NIST) traceable calibration. The rate transducers used in the data acquisition system receive a calibration via a Genisco Rate-of-Turn table. The subsystems of each data channel are also evaluated annually, using instruments with current NIST traceability, and the results are factored into the accuracy of the total data channel, per SAE J211. Calibrations and evaluations are also made any time data are suspect. Acceleration data is measured with an expanded uncertainty of  $\pm 1.7$  percent at a confidence factor of 95 percent ( $k=2$ ).

TRAP uses the data from the TDAS Pro to compute occupant/compartiment impact velocities, time of occupant/compartiment impact after vehicle impact, and the highest 10-millisecond (ms) average ridedown acceleration. TRAP calculates change in vehicle velocity at the end of a given impulse period. In addition, maximum average accelerations over 50-ms intervals in each of the three directions are computed. For reporting purposes, the data from the vehicle-mounted accelerometers are filtered with a 60-Hz low-pass digital filter, and acceleration versus time curves for the longitudinal, lateral, and vertical directions are plotted using TRAP.

TRAP uses the data from the yaw, pitch, and roll rate transducers to compute angular displacement in degrees at 0.0001-s intervals, then plots yaw, pitch, and roll versus time. These displacements are in reference to the vehicle-fixed coordinate system with the initial position and orientation of the vehicle-fixed coordinate systems being initial impact. Rate of rotation data is measured with an expanded uncertainty of  $\pm 0.7$  percent at a confidence factor of 95 percent ( $k=2$ ).

Placement of the electronic instrumentation in the *MASH* Test 5-12 is shown in Appendix E1, Figure E.1 and described below.

- (A) The front accelerometers were placed on the tractor frame rail 14.0 inches forward of the front axle, 20.0 inches left of the longitudinal centerline, and at height of 33.0 inches above ground surface.
- (B) Accelerometers and rate transducers were placed on the tractor frame just ahead of the fifth wheel, 105 inches rearward of the front axle, at the longitudinal centerline, and at a height of 32 inches above ground surface.
- (C) The rear accelerometers were placed on the trailer frame, between the two rear trailer axles, 677 inches rearward of the front axle, at the longitudinal centerline, and 49.5 inches above ground surface.

#### **4.3.2 Anthropomorphic Dummy Instrumentation**

An Alderson Research Laboratories Hybrid II, 50th percentile male anthropomorphic dummy, restrained with lap and shoulder belts, was placed in the front seat on the impact side of the 1100C vehicle. The dummy was not instrumented.

According to *MASH*, use of a dummy in the 2270P vehicle is optional, however, it is recommended a dummy be used when testing “any longitudinal barrier with a height greater than or equal to 33 inches.” Use of the dummy in the 2270P vehicle is recommended for tall rails to evaluate the “potential for an occupant to extend out of the vehicle and come into direct contact with the test article.” Although this information is reported, it is not part of the impact performance evaluation. Since the rail height of the PennDOT PA Bridge Barrier was 50 inches above grade, a dummy was placed in the front seat of the 2270P vehicle on the impact side and restrained with lap and shoulder belts.

*MASH* does not recommend or require use of a dummy in the 36000V vehicle.

#### **4.3.3 Photographic Instrumentation Data Processing**

Photographic coverage of each test included three digital high-speed cameras:

- One overhead with a field of view perpendicular to the ground and directly over the impact point;
- One placed upstream of the impact point on the traffic side of the barrier; and
- A third placed to have a field of view parallel to and aligned with the installation at the downstream end.

A flashbulb on the impacting vehicle was activated by a pressure-sensitive tape switch to indicate the instant of contact with the PennDOT PA Bridge Barrier. The flashbulb was visible from each camera. The video files from these digital high-speed cameras were analyzed to observe phenomena occurring during the collision and to obtain time-event, displacement, and angular data. A digital camera recorded and documented conditions of each test vehicle and the installation before and after the test.

*This page intentionally left blank.*



## Chapter 5. MASH TEST 5-11 (CRASH TEST NO. 609591-03-1)

### 5.1 TEST DESIGNATION AND ACTUAL IMPACT CONDITIONS

MASH Test 5-11 involves a 2270P vehicle, weighing 5000 lb  $\pm$ 110 lb, impacting the CIP of the bridge rail at an impact speed of 62 mi/h  $\pm$ 2.5 mi/h and an angle of 25°  $\pm$ 1.5°. The target CIP for MASH Test 5-11 on the PennDOT PA Bridge Barrier was 4.3 ft  $\pm$ 1 ft upstream of post 9 edge with lower rail splice. The 2013 RAM 1500 pickup used in the test weighed 5004 lb, and the actual impact speed and angle were 63.2 mi/h and 24.8°, respectively. The actual impact point was 4.3 ft upstream of the upstream edge of post 9. Minimum target impact severity (IS) was 106 kip-ft, and actual IS was 121 kip-ft.

### 5.2 WEATHER CONDITIONS

The test was performed on the morning of June 28, 2018. Weather conditions at the time of testing were as follows: wind speed: 8 mi/h; wind direction: 228° (vehicle was traveling in a southerly direction); temperature: 86°F; relative humidity: 73 percent.

### 5.3 TEST VEHICLE

Figures 5.1 and 5.2 show the 2013 RAM 1500 pickup used for the crash test. The vehicle's test inertia weight was 5004 lb, and its gross static weight was 5169 lb. The height to the lower edge of the vehicle bumper was 11.8 inches, and height to the upper edge of the bumper was 27.0 inches. The height to the vehicle's center of gravity was 29.0 inches. Tables C.1 and C.2 in Appendix C1 give additional dimensions and information on the vehicle. The vehicle was directed into the installation using the cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.



Figure 5.1. PennDOT PA Bridge Barrier/Test Vehicle Geometrics for Test No. 609591-03-1.



**Figure 5.2. Test Vehicle before Test No. 609591-03-1.**

#### **5.4 TEST DESCRIPTION**

The 2013 RAM 1500 was traveling at an impact speed of 61.7 mi/h when it contacted the PennDOT PA Bridge Barrier 4.3 ft upstream of post 9 at an impact angle of 24.825.3°. Table 5.1 lists events that occurred during Test No. 609591-03-1. Figures C.1 and C.2 in Appendix C2 present sequential photographs during the test.

**Table 5.1. Events during Test No. 609591-03-1.**


<b>TIME (s)</b>	<b>EVENTS</b>
0.000	Vehicle makes contact with bridge rail
0.023	Vehicle begins to redirect
0.051	Right front bumper shears off of vehicle when contacting post 9
0.082	Dummy head begins to break through passenger side window
0.182	Vehicle becomes parallel with bridge rail
0.188	Rear right side of truck contacts bridge rail
0.192	Left front tire lifts off of pavement
0.214	Left rear tire lands back on pavement
0.255	Left front tire lands back on pavement
0.299	Vehicle loses contact with bridge rail while traveling at 50.8 mi/h

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. After loss of contact with the barrier, the vehicle came to rest 212 ft downstream of the impact and 12 ft toward traffic lanes.

#### **5.5 DAMAGE TO TEST INSTALLATION**

Figure 5.3 shows the damage to the PennDOT PA Bridge Barrier. There was slight concrete damage to the concrete barrier edges near impact and at joint, along with some surface

scuffing of the traffic face of the rail and concrete wall. Working width was 18.0 inches at a height of 24.0 inches. Maximum dynamic deflection during the test was 0.7 inches, and there was no measureable permanent deformation.



**Figure 5.3. PennDOT PA Bridge Barrier after Test No. 609591-03-1.**

## **5.6 VEHICLE DAMAGE**

Figure 5.4 shows the damage sustained by the vehicle. The front bumper, hood, grill, radiator and support, right front fender, right head light, right A-post, right front tire and rim,

right front corner of roof, right front and rear doors and glass, right rear fender, right rear tail light, rear bumper and tailgate were damaged. The windshield sustained a crack starting at the bottom and radiating upward. Maximum exterior crush to the vehicle was 11.0 inches in the side plane at the right corner at bumper height. Maximum occupant compartment deformation was 3.0 inches on the right side from the firewall to the passenger seat, and vertically on the passenger side from the floorboard to the roof at the passenger seat location. Figure 5.5 shows the interior of the vehicle. Tables C.3 and C.4 in Appendix C1 provide exterior crush and occupant compartment measurements.



**Figure 5.4. Test Vehicle after Test No. 609591-03-1.**




**Figure 5.5. Interior of Test Vehicle for Test No. 609591-03-1.**

## **5.7 OCCUPANT RISK FACTORS**

Data from the accelerometer, located at the vehicle center of gravity, were digitized for evaluation of occupant risk and are shown in Table 5.2. Figure 5.6 summarizes these data and other pertinent information from the test. Figure C.3 in Appendix C3 shows the vehicle angular displacements, and Figures C.4 through C.9 in Appendix C4 show accelerations versus time traces.

**Table 5.2. Occupant Risk Factors for Test No. 609591-03-1.**

<b>Occupant Risk Factor</b>	<b>Value</b>	<b>Time</b>
<b>Occupant Impact Velocity (OIV)</b> Longitudinal Lateral	ft/s	at 0.0918 seconds on right side of interior
	<b>19.4</b>	
	<b>28.2</b>	
<b>Occupant Ridedown Accelerations (G's)</b> Longitudinal Lateral		
	<b>-3.2</b>	(0.1038 - 0.1138 seconds)
	<b>-6.7</b>	(0.2152 - 0.2252 seconds)
<b>Theoretical Head Impact Velocity (THIV)</b>	km/h	at 0.0895 seconds on right side of interior
	<b>38.1</b>	
	m/s	
	<b>10.6</b>	
<b>Post Head Deceleration (PHD) (G's)</b>	<b>7.1</b>	(0.2152 - 0.2252 seconds)
<b>Acceleration Severity Index (ASI)</b>	<b>2.06</b>	(0.0574 - 0.1074 seconds)
<b>Maximum 50-ms Moving Average (G's)</b> Longitudinal Lateral Vertical		
	<b>-9.4</b>	(0.0318 - 0.0818 seconds)
	<b>-15.9</b>	(0.0328 - 0.0828 seconds)
	<b>-2.3</b>	(0.0013 - 0.0513 seconds)
<b>Maximum Roll, Pitch, and Yaw Angles</b> Roll Pitch Yaw	<b>Degrees</b>	
	<b>4</b>	(0.4838 seconds)
	<b>4</b>	(0.0623 seconds)
	<b>34</b>	(0.5737 seconds)



**General Information**

Test Agency ..... Texas A&M Transportation Institute (TTI)  
 Test Standard Test No. .... MASH Test 5-11  
 TTI Test No. .... 609591-03-1  
 Test Date..... 2018-06-28

**Test Article**

Type ..... Longitudinal Barrier - Bridge Rail  
 Name..... PennDOT PA Bridge Barrier  
 Installation Length..... 149 ft-10 inches  
 Material or Key Elements .... 24-inch tall x 18-inch thick reinforced concrete parapet with two HSS 5x4x3/8 rails at 37 inches and 50 inches

**Soil Type and Condition** ..... Concrete bridge deck, damp

**Test Vehicle**

Type/Designation ..... 2270P  
 Make and Model..... 2013 RAM 1500 Pickup  
 Curb ..... 4952 lb  
 Test Inertial ..... 5004 lb  
 Dummy ..... 165 lb  
 Gross Static..... 5169 lb

**Impact Conditions**

Speed ..... 63.2 mi/h  
 Angle ..... 24.8°  
 Location/Orientation ..... 4.3 ft upstream of post 9

**Impact Severity** ..... 121 kip-ft

**Exit Conditions**

Speed ..... 50.7 mi/h  
 Exit Traj./Heading Angle .... 4.4°/5.7°

**Occupant Risk Values**

Longitudinal OIV.....19.4 ft/s  
 Lateral OIV .....28.2 ft/s  
 Longitudinal Ridedown.....3.2 g  
 Lateral Ridedown .....6.7 g  
 THIV .....34.8 ft/s  
 PHD.....7.1 g  
 ASI .....2.06  
 Max. 0.050-s Average  
 Longitudinal.....-9.4 g  
 Lateral .....-15.9 g  
 Vertical .....-2.3 g

**Post-Impact Trajectory**

Stopping Distance..... 212 ft downstream  
 12 ft toward traffic

**Vehicle Stability**

Maximum Yaw Angle ..... 34°  
 Maximum Pitch Angle ..... 4°  
 Maximum Roll Angle ..... 4°  
 Vehicle Snagging ..... No  
 Vehicle Pocketing ..... No

**Test Article Deflections**

Dynamic..... 0.7 inches  
 Permanent ..... None  
 Working Width..... 18.0 inches  
 Working Width Height ..... 24.0 inches

**Vehicle Damage**

VDS..... 10-RFQ-5  
 CDC ..... 10FREW3  
 Max. Exterior Deformation ..... 11.0 inches  
 OCDI ..... RF0122110  
 Max. Occupant Compartment Deformation ..... 3.0 inches

**Figure 5.6. Summary of Results for MASH Test 5-11 on PennDOT PA Bridge Barrier.**

## **Chapter 6. MASH TEST 5-10 (CRASH TEST NO. 609591-03-2)**

### **6.1 TEST DESIGNATION AND ACTUAL IMPACT CONDITIONS**

*MASH* Test 5-10 involves an 1100C vehicle, weighing 2420 lb  $\pm$ 55 lb, impacting the CIP of the bridge rail at an impact speed of 62 mi/h  $\pm$ 2.5 mi/h and an angle of 25°  $\pm$ 1.5°. The target CIP for *MASH* Test 5-10 on the PennDOT PA Bridge Barrier was 3.6 ft  $\pm$ 1 ft upstream of post 13 edge with lower rail splice.

The 2011 Kia Rio\* used in the test weighed 2427 lb, and the actual impact speed and angle were 61.7 mi/h and 25.3°, respectively. The actual impact point was 4.1 ft upstream of the upstream edge of post 13. Minimum target IS was 51 kip-ft, and actual IS was 60 kip-ft.

### **6.2 WEATHER CONDITIONS**

The test was performed on the morning of June 26, 2018. Weather conditions at the time of testing were as follows: wind speed: 9 mi/h; wind direction: 182° (vehicle was traveling in a southerly direction); temperature: 88°F; relative humidity: 69 percent.

### **6.3 TEST VEHICLE**

Figures 6.1 and 6.2 show the 2011 Kia Rio used for the crash test. The vehicle's test inertia weight was 2427 lb, and its gross static weight was 2592 lb. The height to the lower edge of the vehicle bumper was 7.8 inches, and height to the upper edge of the bumper was 21.5 inches. Table D.1 in Appendix D1 gives additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.

---

\* An older model vehicle was used, based upon availability. An older model vehicle is permitted by AASHTO as long as it is otherwise *MASH* compliant. This vehicle meets the *MASH* dimensional specifications.



**Figure 6.1. PennDOT PA Bridge Barrier/Test Vehicle Geometrics for Test No. 609591-03-2.**



**Figure 6.2. Test Vehicle before Test No. 609591-03-2.**

#### **6.4 TEST DESCRIPTION**

The 2011 Kia Rio was traveling at an impact speed of 61.7 mi/h when it contacted the PennDOT PA Bridge Barrier was 4.1 ft upstream of the upstream edge of post 13 at an impact angle of 25.3°. Table 6.1 lists events that occurred during Test No. 609591-03-2. Figures D.1 and D.2 in Appendix D2 present sequential photographs during the test.

**Table 6.1. Events during Test No. 609591-03-2.**

<b>TIME (s)</b>	<b>EVENTS</b>
0.000	Vehicle makes contact with bridge rail
0.034	Vehicle begins to redirect
0.059	Right front panel and hood of vehicle contact post # 13
0.084	Left front and rear tire lift off of pavement
0.129	Dummy head at maximum extension outside of window but did not contact bridge rail.
0.162	Vehicle becomes parallel with bridge rail
0.184	Right rear of vehicle contacts bridge rail



0.293	Vehicle loses contact with bridge rail while traveling at 46.2 mi/h
0.326	Front left tire lands back on pavement
0.398	Rear left tire lands back on pavement

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. After loss of contact with the barrier, the vehicle came to rest 169 ft downstream of the impact and 2 ft toward traffic lanes.

## 6.5 DAMAGE TO TEST INSTALLATION

Figure 6.3 shows the damage to the PennDOT PA Bridge Barrier. There was only superficial damage to the traffic face of the concrete and some light scuffing on the railing. Working width was 18.0 inches at a height of 24 inches from the ground. There was no dynamic deflection and no permanent deformation in the PennDOT PA Bridge Barrier.



**Figure 6.3. PennDOT PA Bridge Barrier after Test No. 609591-03-2.**

## **6.6 VEHICLE DAMAGE**

Figure 6.4 shows the damage sustained by the vehicle. The front bumper, hood, radiator and support, right strut, right front fender, right head light, right front door and glass, right rear door, right rear quarter panel, right rear tail light, and rear bumper were damaged. The windshield sustained stress cracks starting at the bottom right side and radiating upward. Maximum exterior crush to the vehicle was 6.0 inches in the horizontal plane at the front bumper at bumper height. Maximum occupant compartment deformation was 3.0 inches at the floor

panel to lower instrument panel on the passenger side. Figure 6.5 shows the interior of the vehicle. Tables D.2 and D.3 in Appendix D1 provide exterior crush and occupant compartment measurements.



**Figure 6.4. Test Vehicle after Test No. 609591-03-2.**




**Figure 6.5. Interior of Test Vehicle for Test No. 609591-03-2.**

## **6.7 OCCUPANT RISK FACTORS**

Data from the accelerometer, located at the vehicle center of gravity, were digitized for evaluation of occupant risk and are shown in Table 6.2. Figure 6.6 summarizes these data and other pertinent information from the test. Figure C.3 in Appendix C3 shows the vehicle angular displacements, and Figures C.4 through C.9 in Appendix C4 show accelerations versus time traces.

**Table 6.2. Occupant Risk Factors for Test No. 609591-03-2.**

<b>Occupant Risk Factor</b>	<b>Value</b>	<b>Time</b>
<b>Occupant Impact Velocity (OIV)</b> Longitudinal Lateral	ft/s	at 0.0702 seconds on right side of interior
	<b>22.3</b>	
	<b>34.1</b>	
<b>Occupant Ridedown Accelerations (G's)</b> Longitudinal Lateral		
	<b>-7.9</b>	(0.2732 - 0.2832 seconds)
	<b>-9.7</b>	(0.1938 - 0.2038 seconds)
<b>Theoretical Head Impact Velocity (THIV)</b>	km/h	at 0.0696 seconds on right side of interior
	<b>44.5</b>	
	m/s	
	<b>12.4</b>	
<b>Post Head Deceleration (PHD) (G's)</b>	<b>10.2</b>	(0.2780 - 0.2880 seconds)
<b>Acceleration Severity Index (ASI)</b>	<b>2.93</b>	(0.0439 - 0.0939 seconds)
<b>Maximum 50-ms Moving Average (G's)</b> Longitudinal Lateral Vertical		
	<b>-12.6</b>	(0.0229 - 0.0729 seconds)
	<b>-20.9</b>	(0.0117 - 0.0617 seconds)
	<b>6.7</b>	(0.0158 - 0.0658 seconds)
<b>Maximum Roll, Pitch, and Yaw Angles</b> Roll Pitch Yaw	<b>Degrees</b>	
	<b>8</b>	(0.1345 seconds)
	<b>12</b>	(0.8042 seconds)
	<b>33</b>	(0.6349 seconds)



**General Information**

Test Agency ..... Texas A&M Transportation Institute (TTI)  
 Test Standard Test No. .... MASH Test 5-10  
 TTI Test No. .... 609591-03-2  
 Test Date..... 2018-06-26

**Test Article**

Type ..... Longitudinal Barrier - Bridge Rail  
 Name..... PennDOT Bridge Deck  
 Installation Length..... 149 ft-10 inches  
 Material or Key Elements .... 24-inch tall x 18-inch thick reinforced concrete wall with two HSS 5x4x3/8 rails at 37 inches and 50 inches

**Soil Type and Condition** ..... Concrete bridge deck, damp

**Test Vehicle**

Type/Designation ..... 1100C  
 Make and Model..... 2011 KIA RIO  
 Curb ..... 2457 lb  
 Test Inertial ..... 2427 lb  
 Dummy ..... 165 lb  
 Gross Static..... 2592 lb

**Impact Conditions**

Speed.....61.7 mi/hr  
 Angle .....25.3°  
 Location/Orientation .....49.2 inches upstream of Post 13

**Impact Severity**.....60 kip-ft

**Exit Conditions**

Speed.....46.3 mi/h  
 Exit Traj./Heading Angle ....3.4°/10.3°

**Occupant Risk Values**

Longitudinal OIV.....22.3 ft/s  
 Lateral OIV .....34.1 ft/s  
 Longitudinal Ridedown.....7.9 g  
 Lateral Ridedown .....9.7 g  
 THIV .....40.7 ft/s  
 PHD .....10.2g  
 ASI .....2.9

**Max. 0.050-s Average**

Longitudinal.....-12.6 g  
 Lateral .....-20.9 g  
 Vertical .....6.7 g

**Post-Impact Trajectory**

Stopping Distance..... 169 ft downstream  
 2 ft toward traffic

**Vehicle Stability**

Maximum Yaw Angle ..... 33°  
 Maximum Pitch Angle ..... 12°  
 Maximum Roll Angle..... 8°  
 Vehicle Snagging ..... No  
 Vehicle Pocketing ..... No

**Test Article Deflections**

Dynamic..... None  
 Permanent..... None  
 Working Width..... 18 inches  
 Working Width Height..... 24 inches

**Vehicle Damage**

VDS..... 10-RFQ-5  
 CDC ..... 10FREW3  
 Max. Exterior Deformation ..... 6.0 inches  
 OCDI..... RF0114100  
 Max. Occupant Compartment Deformation ..... 3.0 inches

**Figure 6.6. Summary of Results for MASH Test 5-10 on PennDOT PA Bridge Barrier.**

*This page intentionally left blank.*

## Chapter 7. MASH TEST 5-12 (CRASH TEST NO. 609591-03-3)

### 7.1 TEST DESIGNATION AND ACTUAL IMPACT CONDITIONS

MASH Test 5-12 involves a 36000V vehicle, weighing 79,300 lb  $\pm$  1100 lb, impacting the CIP of the bridge rail at an impact speed of 50 mi/h  $\pm$  2.5 mi/h and an angle of 15°  $\pm$  1.5°. The target CIP for MASH Test 5-12 on the PennDOT PA Bridge Barrier was 1 ft  $\pm$  1 ft downstream of the edge of post 5.

The 2008 Freightliner CL120 Tractor & 53ft 2002 Utility Trailer used in the test weighed 79,280 lb, and the actual impact speed and angle were 49.9 mi/h and 14.8°, respectively. The actual impact point was 1.9 ft downstream of the edge of post 15 with the lower rail splice. Minimum target IS was 404 kip-ft, and actual IS was 430.6 kip-ft.

### 7.2 WEATHER CONDITIONS

The test was performed on the morning of July 3, 2018. Weather conditions at the time of testing were as follows: wind speed: 7 mi/h; wind direction: 195° (vehicle was traveling in a southerly direction); temperature: 86°F; relative humidity: 71 percent.

### 7.3 TEST VEHICLE

Figures 7.1 and 7.2 show the 2008 Freightliner CL120 Tractor & 2002 Utility 53ft Trailer used for the crash test. The vehicle's test inertia weight was 79,280 lb. The height to the lower edge of the vehicle bumper was 15 inches, and height to the upper edge of the bumper was 34.5 inches. The height to the ballast's center of gravity was 72.5 inches. Tables E.1 and Figure E.1 in Appendix E1 give additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable guidance system under self-power, and was released to be freewheeling and unrestrained just prior to impact.



Figure 7.1. PennDOT PA Bridge Barrier/Test Vehicle Geometrics for Test No. 609591-03-3.



**Figure 7.2. Test Vehicle before Test No. 609591-03-3.**

#### **7.4 TEST DESCRIPTION**

The 2008 Freightliner CL120 Tractor & 2002 Utility 53ft Trailer was traveling at an impact speed of 61.7 mi/h when it contacted the PennDOT PA Bridge Barrier 1.9 ft downstream of the edge of Post 15 with the lower rail splice at an impact angle of 25.3°. Table 7.1 lists events that occurred during Test No. 609591-03-3. Figures E.2 and E.3 in Appendix E2 present sequential photographs during the test.

**Table 7.1. Events during Test No. 609591-03-3.**

<b>TIME (s)</b>	<b>EVENTS</b>
0.000	Tractor contacts bridge rail
0.101	Tractor begins to redirect
0.148	Front left tire of tractor lifts off of pavement
0.165	Trailer front right corner contacts rail
0.283	Tractor becomes parallel with bridge rail
0.347	Left front tire lands back on pavement
0.735	Trailer right rear corner contacts rail
0.766	Trailer becomes parallel with bridge rail
0.970	Trailer right rear corner makes furthest penetration to field side
0.973	Left turn indicator comes on and begins blinking
1.258	Tractor Trailer loses contact with bridge rail while traveling at 44.0 mi/h

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 65.6 ft downstream from loss of contact for vehicles other than cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. After loss of contact with the barrier, the vehicle came to rest 270 ft downstream of the impact and 8 ft toward traffic lanes.



## 7.5 DAMAGE TO TEST INSTALLATION

Figure 7.3 shows the damage to the PennDOT PA Bridge Barrier. Both top and bottom rails were deformed upstream of post 5 to post 7. The concrete at posts 4 through 7 was broken completely through. Working width was 51.9 inches at a height of 130.8 inches. Maximum dynamic deflection during the test was estimated (all views partially or fully obscured) to be 20 inches, and maximum permanent deformation was 6.5 inches, 43 inches downstream of center of post 5.



**Figure 7.3. PennDOT PA Bridge Barrier after Test No. 609591-03-3.**

## 7.6 VEHICLE DAMAGE

Figure 7.4 shows the damage sustained by the vehicle. The vehicle sustained damage to the front bumper, hood, front axle, right front U-bolts and springs, right head light, front right tire and rim, right door, right fuel tank, right front outer tire and rim on tractor, and right side of trailer. Maximum exterior crush to the vehicle was 18 inches in the horizontal plane at bumper height. Maximum occupant compartment deformation was 2.5 inches. Figure 7.5 shows the interior of the vehicle. Table C.3 and Figure C.41 in Appendix C11 provide exterior crush and occupant compartment measurements.



**Figure 7.4. Test Vehicle after Test No. 609591-03-3.**




**Figure 7.5. Interior of Test Vehicle for Test No. 609591-03-3.**

## 7.7 OCCUPANT RISK FACTORS

Data from the accelerometer, located near the 5<sup>th</sup> wheel of the Tractor, were digitized for informational purposes only. The results are shown in Table 7.2. Figure 7.6 summarizes these data and other pertinent information from the test. Figure E.4 in Appendix E3 shows the vehicle angular displacements, and Figures E.5 through E.13 in Appendix E4 show accelerations versus time traces.

**Table 7.2. Occupant Risk Factors for Test No. 609591-03-3. Measure from 5<sup>th</sup> wheel Accelerometers**

<b>Occupant Risk Factor</b>	<b>Value</b>	<b>Time</b>
<b>Occupant Impact Velocity (OIV)</b> Longitudinal Lateral	ft/s	at 0.1980 seconds on right side of interior
	<b>3.0</b>	
	<b>13.5</b>	
<b>Occupant Ridedown Accelerations (G's)</b> Longitudinal Lateral		
	<b>-8.9</b>	(0.2158 - 0.2258 seconds)
	<b>20.5</b>	(0.2394 - 0.2494 seconds)
<b>Theoretical Head Impact Velocity (THIV)</b>	km/h	at 0.1978 seconds on right side of interior
	<b>15.1</b>	
	m/s	
	<b>4.2</b>	
<b>Post Head Deceleration (PHD) (G's)</b>	<b>21.2</b>	(0.2393 - 0.2493 seconds)
<b>Acceleration Severity Index (ASI)</b>	<b>1.35</b>	(0.2214 - 0.2714 seconds)
<b>Maximum 50-ms Moving Average (G's)</b> Longitudinal Lateral Vertical		
	<b>-2.4</b>	(0.1760 - 0.2260 seconds)
	<b>-6.9</b>	(0.2569 - 0.3069 seconds)
	<b>12.8</b>	(0.2009 - 0.2509 seconds)
<b>Maximum Roll, Pitch, and Yaw Angles</b> Roll Pitch Yaw	<b>Degrees</b>	
	<b>22</b>	(1.3763 seconds)
	<b>35</b>	(1.9979 seconds)
	<b>25</b>	(1.9666 seconds)



**General Information**

Test Agency ..... Texas A&M Transportation Institute (TTI)  
 Test Standard Test No. .... MASH Test 5-12  
 TTI Test No. .... 609591-03-3  
 Test Date..... 2018-07-03

**Test Article**

Type ..... Longitudinal Barrier - Bridge Rail  
 Name..... PennDOT PA Bridge Barrier  
 Installation Length..... 149 ft-10 inches  
 Material or Key Elements .... 24-inch tall x 18-inch thick reinforced concrete wall with two HSS 5x4x3/8 rails at 37 inches and 50 inches  
 Soil Type and Condition ..... Concrete bridge deck, damp

**Test Vehicle**

Type/Designation ..... 36000V  
 Make and Model..... 2008 Freightliner CL120 & 2002 Utility 53ft  
 Curb ..... 28,750 lb  
 Test Inertial ..... 79.280 lb  
 Dummy ..... None  
 Gross Static..... 79,280 lb

**Impact Conditions**

Speed.....49.9 mi/h  
 Angle .....14.8°  
 Location/Orientation .....23 inches dwnstrm of post 5

**Impact Severity**

**Exit Conditions**  
 Speed.....44.0 mi/h  
 Exit Traj./Heading Angle ....4.2°/0.8°

**Occupant Risk Values**

Longitudinal OIV.....3.0 ft/s  
 Lateral OIV .....13.5 ft/s  
 Longitudinal Ridedown.....8.9 g  
 Lateral Ridedown .....20.5 g  
 THIV .....13.8 ft/s  
 PHD.....21.2 g  
 ASI .....1.4  
 Max. 0.050-s Average  
 Longitudinal.....-2.4 g  
 Lateral.....-6.9 g  
 Vertical .....12.8 g

**Post-Impact Trajectory**

Stopping Distance..... 270 ft downstream  
 8 ft toward traffic

**Vehicle Stability**

Maximum Yaw Angle ..... 25°  
 Maximum Pitch Angle ..... 35°  
 Maximum Roll Angle ..... 22°  
 Vehicle Snagging ..... No  
 Vehicle Pocketing ..... No

**Test Article Deflections**

Dynamic (View Partially Obscured) ..... 20 inches  
 Permanent ..... 7.0 inches  
 Working Width..... 51.9 inches  
 Working Width Height ..... 130.8 inches

**Vehicle Damage**

VDS..... NA  
 CDC ..... NA  
 Max. Exterior Deformation ..... 18 inches  
 OCDI ..... NA  
 Max. Occupant Compartment Deformation ..... 2.5 inches

**Figure 7.6. Summary of Results for MASH Test 5-12 on PennDOT PA Bridge Barrier.**

## **Chapter 8. SUMMARY AND CONCLUSIONS**

### **8.1 ASSESSMENT OF TEST RESULTS**

The crash testing reported herein was performed in accordance with *MASH* Tests 5-10, 5-11, and 5-12, which involves an 1100C and 2270P vehicle impacting the PennDOT PA Bridge Barrier at a target impact speed and impact angle of 62 mi/h and 25°, respectively, and a 36000V vehicle impacting the PennDOT PA Bridge Barrier at target impact speed and impact angle of 50 mi/h and 15°, respectively. An assessment of the tests based on the applicable safety evaluation criteria for *MASH* Tests 5-10, 5-11, and 5-12 for longitudinal barriers are provided in Table 8.1, 8.2, and 8.3.

### **8.2 CONCLUSIONS**

The PennDOT PA Bridge Barrier performed acceptably for *MASH* Tests 5-10, 5-11, and 5-12 for longitudinal barriers.

**Table 8.1. Performance Evaluation Summary for MASH Test 5-11 on PennDOT PA Bridge Barrier.**

Test Agency: Texas A&amp;M Transportation Institute

Test No.: 609591-03-1

Test Date: 2018-06-28

<b>MASH Test 5-10 Evaluation Criteria</b>	<b>Test Results</b>	<b>Assessment</b>
<b><u>Structural Adequacy</u></b>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The PennDOT PA Bridge Barrier contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. The dynamic deflection of the bridge rail during the test was 0.7 inches.	Pass
<b><u>Occupant Risk</u></b>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or to present hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 3.0 inches on the passenger side at the floor pan to roof, and wheel/foot well and toe pan area measurements.	Pass
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 2270P vehicle remained upright during and after the collision event. Roll and pitch angles were 4° and 4°, respectively.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 19.4 ft/s, and lateral OIV was 28.2 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 3.2 g, and lateral occupant ridedown acceleration was 6.7 g.	Pass

**Table 8.2. Performance Evaluation Summary for MASH Test 5-10 on PennDOT PA Bridge Barrier.**

Test Agency: Texas A&amp;M Transportation Institute

Test No.: 609591-03-2

Test Date: 2018-06-26

<b>MASH Test 5-10 Evaluation Criteria</b>	<b>Test Results</b>	<b>Assessment</b>
<b><u>Structural Adequacy</u></b>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The PennDOT PA Bridge Barrier contained and redirected the 1100C vehicle. The vehicle did not penetrate, underride, or override the installation. There was no observable dynamic deflection or residual permanent deformation of the bridge rail.	Pass
<b><u>Occupant Risk</u></b>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or to present hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 3.0 inches in the passenger side foot well area.	Pass
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 1100C vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 8° and 12°, respectively.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 22.3 ft/s, and lateral OIV was 34.1 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 7.9 g, and lateral occupant ridedown acceleration was 9.7 g.	Pass

**Table 8.3. Performance Evaluation Summary for MASH Test 5-12 on PennDOT PA Bridge Barrier.**

Test Agency: Texas A&amp;M Transportation Institute

Test No.: 609591-03-3

Test Date: year-mo-da

<b>MASH Test 5-12 Evaluation Criteria</b>	<b>Test Results</b>	<b>Assessment</b>
<b><u>Structural Adequacy</u></b>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The PennDOT PA Bridge Barrier contained and redirected the 36000V vehicle. The vehicle did not penetrate, underride, or override the installation. The dynamic deflection of the bridge rail during the test was 7.0 inches.	Pass
<b><u>Occupant Risk</u></b>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or to present hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 2.5 inches.	Pass
G. <i>It is preferable, although not essential, that the vehicle remain upright during and after collision.</i>	The 36000V vehicle remained upright during and after the collision.	Pass



**Table 8.4. Assessment Summary for *MASH* TL-5 Tests on PennDOT PA Bridge Barrier.**

<b>Evaluation Factors</b>	<b>Evaluation Criteria</b>	<b>Test No. 609591-03-2</b>	<b>Test No. 609591-03-1</b>	<b>Test No. 609591-03-3</b>
<b>Structural Adequacy</b>	A	S	S	S
<b>Occupant Risk</b>	D	S	S	S
	F	S	S	N/A
	G	N/A	N/A	S
	H	S	S	N/A
	I	S	S	N/A
	<b>Test No.</b>	<b><i>MASH</i> Test 5-10</b>	<b><i>MASH</i> Test 5-11</b>	<b><i>MASH</i> Test 5-12</b>
	<b>Pass/Fail</b>	Pass	Pass	Pass

S = Satisfactory  
 U = Unsatisfactory  
 N/A = Not Applicable


*This page intentionally left blank.*

## REFERENCES


1. AASHTO. *Manual for Assessing Roadside Safety Hardware, Second Edition*. 2016, American Association of State Highway and Transportation Officials: Washington, D.C.

*This page intentionally left blank.*

APPENDIX A. DETAILS OF THE BRIDGE RAIL




T:\11-11-17\ProjectFiles\609591-G-F WO #2 - Bullard\Drafting, 609591\2018-05-05-17\609591 Drawing



Roadside Safety and  
Physical Security Division -  
Proving Ground


Project 609591	PennDOT PA Bridge Barrier	2018-07-20
Drawn By GES	Scale:1:200	Sheet 2 of 9
Plan View		



- 3a. Mill to Bear is defined as follows: A minimum of 25% of the Post web and compression flange end area must fit within 1/32" of the Base Plate, with no gap more than 0.040" for the remaining 75% of the end area.
- 3b. Galvanize all components after fabrication is complete.
- 3c. All welding must be performed by certified welders using industry standard practices.

		Roadside Safety and Physical Security Division - Proving Ground		
		Project 609591	PennDOT PA Bridge Barrier	2018-05-17
Drawn By	GES	Scale 1:10	Sheet 3 of 9	Post Details


T:\1-ProjectFiles\609591-G-F WO #2 - Bullard\Drafting, 609591\2018-05-17\609591 Drawing



T:\1-ProjectFiles\609591-G-F WO #2 - Bullard\Drafting, 609591\2018-05-17\609591 Drawing




### New Concrete Cross Section




- 5a. Note 1/2" slope at top of Barrier and 1" slope on traffic face.
- 5b. R1" Fillet at front edge of Barrier. Chamfer 3/4" each way at back of Deck and Barrier, four places total.
- 5c. Rake finish construction joint between Barrier and Deck.
- 5d. The concrete strength shall be as follows: Working Slab and Moment Slab: minimum 3000 psi. Wall and Deck: 4000 psi. Barrier 3500 psi.
- 5e. Working Slab 12" overhang on the traffic side of the Wall is only at the new Moment Slab sections.

		Roadside Safety and Physical Security Division - Proving Ground					
		Project 609591	PennDOT PA Bridge Barrier	2018-05-17			
Drawn By	GES	Scale	1:20	Sheet	5 of 9	New Concrete Cross Section	



T:\1-ProjectFiles\609591-G-F WO #2 - Bullard\Drafting, 609591\2018-05-17\609591 Drawing

Section H-H  
See 7a



**7a.** Section H-H is typical at existing Moment Slab. Details not shown are same as Section G-G (previous sheet).

**7b.** Minimum rebar lap is 31" for #5 bars, 35" for #4 bars in the Barrier, and 25" for all other #4 bars.


**7c.** All rebar is grade 60, and epoxy coated unless otherwise indicated.

**7d.** The Anchor Bars weld to existing rebar (not shown here) protruding from the runway. Minimum 3" weld, bars at maximum 18" spacing.




Roadside Safety and  
Physical Security Division -  
Proving Ground

Project 609591	PennDOT PA Bridge Barrier	2018-05-17
Drawn By GES	Scale 1:20	Sheet 7 of 9 Section H-H



T:\1-ProjectFiles\609591-G-F WO #2 - Bullard\Drafting, 609591\2018-05-17\609591 Drawing




Roadside Safety and  
Physical Security Division -  
Proving Ground


Project 609591	PennDOT PA Bridge Barrier	2018-05-17
Drawn By GES	Scale 1:10	Sheet 9 of 9 Rebar Bends

T:\1-ProjectFiles\609591-G-F WO #2 - Bullard\Drafting, 609591\2018-05-17\609591 Drawing


*This page intentionally left blank.*

APPENDIX B. SUPPORTING CERTIFICATION DOCUMENTS






Section A-A

	Roadside Safety and Physical Security Division - Proving Ground	
	Project #609591 PenDOT	2018-05-31
Drawn by GES	Sheet 2 of 4 Concrete Map, working slab	




 <p><b>Texas A&amp;M Transportation Institute</b>  <small>Proving Ground 3100 SH 47, Bldg 7091 Bryan, TX 77807</small></p> <p><small>Texas A&amp;M University College Station, TX 77843 Phone 979-845-6375</small></p>	<b>5.7.2 Concrete Sampling</b>	Doc. No. QPF 5.7.2	Revision Date: 2018-04-17
		Revised by: B. L. Griffith Approved by: D. Kuhn	Revision: 6
<b>Quality Policy Form</b>			

Project No: 609591 Casting Date: 2018-05-19 Mix Design (psi): 3000

Printed Name of Technician taking Sample: Matt Robinson Printed Name of Technician breaking Sample: Matt Robinson  
 Signed Name of Technician taking Sample: [Signature] Signed Name of Technician breaking Sample: [Signature]

Load No.	Truck No.	Ticket No.	Location (from concrete map)
W2/T2	390127	0042224	Right Side Working Slab ≈ 30'
W2/T2	390144	12042225	Next to 1st Pour ≈ 30'
W3/T3	390119	0042228	Next to 2nd Pour ≈ 30'

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
W1/T1	2018-06-25	37 days	3395	96000	
W1/T1			3891	110000	3548
W1/T1			3360	95000	
W2/T2	2018-06-25	37 days	3714	105000	
W2/T2			3926	111000	3855
W2/T2			3926	111000	
W3/T3	2018-06-25	37 days	4204	119000	
W3/T3			4669	132000	4220
W3/T3			3784	107000	

 <b>Texas A&amp;M Transportation Institute</b> <small>Proving Ground 3100 SH 47, Bldg 7091 Bryan, TX 77807</small>	<b>5.7.2 Concrete Sampling</b>	Doc. No.	Revision
		QPF 5.7.2	Date: 2018-04-17
<b>Quality Policy Form</b>		Revised by: B. L. Griffith Approved by: D. Kuhn	Revision: 6 Page: 1 of 1

Project No: 609591 Casting Date: 2018-05-19 Mix Design (psi): 3000

Printed Name of Technician taking Sample: Matt Robinson Printed Name of Technician breaking Sample: Matt Robinson  
 Signed Name of Technician taking Sample: [Signature] Signed Name of Technician breaking Sample: [Signature]

Load No.	Truck No.	Ticket No.	Location (from concrete map)
<u>W4/T4</u>	<u>390107</u>	<u>0042230</u>	<u>Next to Pour #3, ≈ 30'</u>
<u>W5/T5</u>	<u>390150</u>	<u>0042231</u>	<u>Final Pour on Left, ≈ 30'</u>

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
<u>W4/T4</u>	<u>2018-06-25</u>	<u>37 days</u>	<u>3749</u>	<u>106000</u>	
<u>W4/T4</u>	<u> </u>	<u> </u>	<u>4067</u>	<u>115000</u>	<u>3961</u>
<u>W4/T4</u>	<u> </u>	<u> </u>	<u>4067</u>	<u>115000</u>	
<u>W5/T5</u>	<u>2018-06-25</u>	<u>37 days</u>	<u>3961</u>	<u>112000</u>	
<u>W5/T5</u>	<u> </u>	<u> </u>	<u>3997</u>	<u>117000</u>	<u>3890</u>
<u>W5/T5</u>	<u> </u>	<u> </u>	<u>3714</u>	<u>105000</u>	



AN MDU RESOURCES COMPANY

Bryan Plant #6

**SOUTH REGION/MAIN OFFICE**  
 6310 State Highway 21 West  
 Bryan, TX 77807  
 PH: (979) 361-2900  
 FAX: (979) 361-2920

**BRYAN**  
 6310 Hwy. 21 West  
 Bryan, TX 77807  
 DISPATCH: (979) 361-2931  
 FAX: (979) 361-2920

**B 0042224**

TUCKER CONSTRUCTION  
 7425 MIZE RD  
 BRYAN

TTI TEN RAIL  
 RT 21 LF 47 RT RIVERSIDE CAMPUS  
 GO STRAIGHT TO THE BACK TO JOB

Disp Order#: 2002

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
7:50:07	CLALS	10.00	50.00	EDDIE SWE 390127	
DATE	LOAD #	YARDS DEL	BATCH #	WATER TRIM	TICKET NUMBER
05/19/18	1	10.00		SLUMP 5.00in	6141567

**WARNING**  
 IRRITATING TO THE SKIN AND EYES

Contains Portland Cement. Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. KEEP CHILDREN AWAY.

CONCRETE IS A PERISHABLE COMMODITY AND BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES OR CANCELLATION OF ORIGINAL INSTRUCTIONS MUST BE TELEPHONED TO THE OFFICE BEFORE LOADING starts.

The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.

All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum.

Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.

A \$15.00 Service Charge and Loss of the Cash Discount will be collected on all Returned Checks.

Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
 (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)

Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.

X

Excessive Water is Detrimental to Concrete Performance.  
 H<sub>2</sub>O Added by Request / Authorized By:

GAL X

WEIGHMASTER

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY

x

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX. 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00CY	CLALS	CLASS A 3000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		
LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP.	
8:07					
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS	

Task  
 Prev. AMT  
 Ticket Tot  
 Grand Total

ADDITIONAL CHARGE 1 \_\_\_\_\_

ADDITIONAL CHARGE 2 \_\_\_\_\_

**GRAND TOTAL** ▶

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
390127	548949	user	6141567	50017	7:50	B190042224
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
10.00 CYDS	CLALS				D	45
Material	Design Qty	Required	Batched	% Var	Moisture	Actual Wat
SAND	1385 lb	14473 lb	14380 lb	-0.64%	4.50% M	74 gl
MSTN1"	1400 lb	14105 lb	14000 lb	-0.74%	0.75% M	12 gl
GRAVEL 3/8"	470 lb	4771 lb	4790 lb	0.41%	1.50% M	8 gl
CEMENT	315.0 lb	3150.0 lb	3128.0 lb	-0.70%		
WYASH	105.0 lb	1050.0 lb	1048.0 lb	-0.19%		
WATER	30.2 gl	186.3 gl	186.7 gl	0.22%		
WZ200	19.00 oz	190.00 oz	190.00 oz	0.00%		186.7 gl
Actual	Num Batches: 1		Manual	7:50:07		
Load Total:	28916 lb	Design W/C: 0.600	Water/Cement: 0.604	Design Water: 302.0 gl	Actual Water: 281.9 gl	To Add: 28.1 gl
Pump:	5.00 in	Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	Load Trim Water: -2.0 gl	CYDS	



AN MDU RESOURCES COMPANY

Bryan Plant #6

**SOUTH REGION/MAIN OFFICE**  
 6310 State Highway 21 West  
 Bryan, TX 77807  
 PH: (979) 361-2900  
 FAX: (979) 361-2920

**BRYAN**  
 6310 Hwy. 21 West  
 Bryan, TX 77807  
 DISPATCH: (979) 361-2931  
 FAX: (979) 361-2920

**B 0042231**

TUCKER CONSTRUCTION  
 7425 MIZE RD  
 BRYAN

#5

TTI TEN RAIL  
 RT 21 LF 47 RT RIVERSIDE CAMPUS  
 WAIT AT THE FRONT ENTRANCE THEY  
 WILL PICK YOU UP AND TAKE YOU T  
 HE JOB

Disp Order#: 2002

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
8:42:04	CLALS	10.00	50.00	ROBERT WJ 390150	
DATE	LOAD #	YARDS DEL	BATCH #	WATER TRIM	TICKET NUMBER
05/19/18	5	50.00			6141574
				5.00in	

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
 Contains Portland Cement. Wear Rubber Boots and Gloves, PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES OR CANCELLATION OF ORIGINAL INSTRUCTIONS MUST BE TELEPHONED TO THE OFFICE BEFORE LOADING starts.

The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.

All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.

A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
 (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)

Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and the supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and the supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.

SIGNED: X

Excessive Water is Detrimental to Concrete Performance.  
 H<sub>2</sub>O Added by Request / Authorized By: GAL X

WEIGHMASTER

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY: X

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00CY	CLALS	CLASS A 3000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		Tax
			SLUMP	CONCRETE TEMP.	Prev. AMT
					Ticket Tot
			AIR	CYLINDERS	Grand Total
					ADDITIONAL CHARGE 1
					ADDITIONAL CHARGE 2
					<b>GRAND TOTAL</b>

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
390150	455351	user	6141574	50024	8:42	19
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
10.00 CYDS	CLALS				D	52
Material	Design Qty	Required	Batched	% Var	Moisture	Actual Wat
SAND	1385 lb	14473 lb	14410 lb	-0.44%	4.50% M	74 gl
WSTN1*	1400 lb	14105 lb	14070 lb	-0.25%	0.75% M	13 gl
RAVEL 3/8"	470 lb	4771 lb	4700 lb	0.20%	1.50% M	8 gl
EMENT	315.0 lb	3150.0 lb	3230.0 lb +	2.54%		
LYASH	105.0 lb	1050.0 lb	1050.0 lb	0.00%		
ATER	30.2 gl	186.3 gl	185.7 gl	-0.29%		185.7 gl
OZZ80	19.00 oz	190.00 oz	190.00 oz	0.00%		
ctual	Nus Batches: 1					
oad Total:	39102 lb	Design W/C: 0.600	Water/Cement: 0.589 T	Manual	8:42:04	
lump:	5.00 in	Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	Design Water: 302.0 gl	Actual Water: 281.1 gl	To Add: 20.9 gl
				Load Trim Water: -2.0 gl		



**SOUTH REGION/MAIN OFFICE**  
 6310 State Highway 21 West  
 Bryan, TX 77807  
 PH: (979) 361-2900  
 FAX: (979) 361-2920

**BRYAN**  
 6310 Hwy. 21 West  
 Bryan, TX 77807  
 DISPATCH: (979) 361-2931  
 FAX: (979) 361-2920

**B 0042230**

Bryan Plant #6

TUCKER CONSTRUCTION  
 7425 MIZE RD  
 BRYAN

TTI TEN RAIL  
 RT 21 LF 47 RT RIVERSIDE CAMPUS  
 GO STRAIGHT TO THE BACK TO JOB

Disp Order#: 2002

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
8:22:39	CLALS	10.00	50.00	LARRY J.	390107
DATE	LOAD #	YARDS DEL	BATCH #	WATER TRIM	TICKET NUMBER
05/19/18	TTITENRAI	4	40.00	5.00in	6141573

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
 Contains Portland Cement. Wear Rubber Boots and Gloves, PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES or CANCELLATION of ORIGINAL INSTRUCTIONS MUST be TELEPHONED to the OFFICE BEFORE LOADING starts.

The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.

All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.

A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
 (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)

Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can. Out in order to do this the driver is requesting that you sign this RELEASE relieving him and his supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not enter the public street. Further, an additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and his supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.

SIGNED: X

Excessive Water is Detrimental to Concrete Performance.  
 H<sub>2</sub>O Added by Request / Authorized By:  
 GAL X

WEIGHMASTER

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY  
 X

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00CY	CLALS	CLASS A 3000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		
LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP.	
	9:05	9:15			
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS	

Tax  
 Prev. AMT  
 Ticket Tot  
 Grand Total

ADDITIONAL CHARGE 1 \_\_\_\_\_  
 ADDITIONAL CHARGE 2 \_\_\_\_\_

**GRAND TOTAL** ▶

Truck	Driver	User	Disp Ticket	Num	Ticket ID	Time	Date
390107	520723	user	6141573	50023	50023	8:22	05/19/18
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
10.00 CYDS	CLALS				D	51	
Material	Design Qty	Required	Batched	% Var	Moisture	Actual Wat	
AND	1385 lb	14473 lb	14380 lb	-0.64%	4.50% M	74 g/l	
MSTN1"	1400 lb	14105 lb	13960 lb	-1.83%	0.75% M	12 g/l	
RAVEL 3/8"	470 lb	4771 lb	4730 lb	-0.85%	1.50% M	0 g/l	
EMENT	315.0 lb	3150.0 lb	3234.0 lb	2.67%			
LYASH	105.0 lb	1050.0 lb	1052.0 lb	0.19%			
ATER	30.2 gl	185.3 gl	185.7 gl	-0.29%		185.7 g/l	
02280	19.00 oz	190.00 oz	190.00 oz	0.00%			
ctual	Num Batches: 1						
oad Total:	38918 lb	Design W/C: 0.600	Water/Cement: 0.588		Manual	8:22:39	
ump:	5.00 in	Water in Truck: 0.0 gl	Adjust Water: 0.0 gl		Design Water: 302.0 gl	Actual Water: 280.8 gl	To Add: 21.2 gl
					Load Trim Water: -2.0 gl		



AN MDU RESOURCES COMPANY

Bryan Plant #6

SOUTH REGION/MAIN OFFICE  
6310 State Highway 21 West  
Bryan, TX 77807  
PH: (979) 361-2900  
FAX: (979) 361-2920

BRYAN  
6310 Hwy, 21 West  
Bryan, TX 77807  
DISPATCH: (979) 361-2931  
FAX: (979) 361-2920

B 0042228

TUCKER CONSTRUCTION  
7425 MIZE RD  
BRYAN

TTI TEN RAIL  
RT 21 LF 47 RT RIVERSIDE CAMPUS  
GO STRAIGHT TO THE BACK TO JOB

Disp Order#: 2002

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
8:14:06	CLALS	10.00	50.00	JAMES BRO 390119	
DATE	LOAD #	YARDS DEL.	BATCH #	WATER TRIM	TICKET NUMBER
05/19/18	3	30.00		SLUMP 5.00 in	6141572

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
Contains Portland Cement. Wear Rubber Boots and Gloves, PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention **KEEP CHILDREN AWAY.**

**PROPERTY DAMAGE RELEASE**  
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)  
Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can. But in order to do this the driver is requesting that you sign this RELEASE relieving him and the supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc. by the delivery of this material. And that you also agree to help him remove mud from the wheels of his vehicle so that he will not lose the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and the supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.  
SIGNED: X

Excessive Water is Detrimental to Concrete Performance.  
H<sub>2</sub>O Added by Request / Authorized By: GAL X

WEIGHMASTER  
Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY  
x *Domino Sauer*

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00	CY CLALS	CLASS A 3000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING	AIR TEMP
		855	TESTING LAB:	
LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP.
	841	850		
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS

ADDITIONAL CHARGE 1 \_\_\_\_\_  
ADDITIONAL CHARGE 2 \_\_\_\_\_  
**GRAND TOTAL** ▶

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
390119	64290	user	6141572	50021	8:14	05/19/18
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
10.00 CYDS	CLALS				D	50

Material	Design Qty	Required	Batched	% Var	Moisture	Actual Wat
AND	1385 lb	14473.3b	14380 lb	-0.64%	4.50% M	74 gl
MSTN1"	1400 lb	14105 lb	13950 lb	-1.03%	0.75% M	12 gl
RAVEL3/B"	470 lb	4771 lb	4740 lb	-0.64%	1.50% M	8 gl
EMENT	315.0 lb	3150.0 lb	3146.0 lb	-0.13%		
LYASH	105.0 lb	1050.0 lb	1048.0 lb	-0.19%		
ATER	30.2 gl	186.3 gl	186.7 gl	0.22%		186.7 gl
DZ780	19.00 oz	190.00 oz	190.00 oz	0.00%		

Actual Num Batches: 1  
Manual 8:14:06  
oad Total: 38844 lb Design W/C: 0.600 Water/Cement: 0.601 T Design Water: 302.0 gl Actual Water: 281.8 gl To Add: 20.3 gl  
lump: 5.00 in Water in Truck: 0.0 gl Adjust Water: 0.0 gl/Load Trim Water: -2.0 gl/CYDS



AN MDU RESOURCES COMPANY

Bryan Plant #6

SOUTH REGION/MAIN OFFICE  
6310 State Highway 21 West  
Bryan, TX 77807  
PH: (979) 361-2900  
FAX: (979) 361-2920

BRYAN  
6310 Hwy. 21 West  
Bryan, TX 77807  
DISPATCH: (979) 361-2931  
FAX: (979) 361-2920

B 0042225

TUCKER CONSTRUCTION  
7425 MIZE RD  
BRYAN

TTI TEN RAIL  
RT 21 LF 47 RT RIVERSIDE CAMPUS  
GO STRAIGHT TO THE BACK TO JOB

Disp Order#: 2002

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
8:01:35	CLALS	10.00	50.00	RAY ALWEL 390144	
DATE	LOAD #	YARDS DEL.	BATCH #	WATER TRIM	TICKET NUMBER
05/19/18	TTITENRAI	2	20.00	5.00in	6141568

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
Contains Portland Cement. Wear Rubber Boots and Gloves, PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. KEEP CHILDREN AWAY.  
CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES or CANCELLATION OF ORIGINAL INSTRUCTIONS MUST BE TELEPHONED to the OFFICE BEFORE LOADING starts.  
The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.  
All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.  
A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)  
Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and the supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.  
X


Excessive Water is Detrimental to Concrete Performance.  
H<sub>2</sub>O Added by Request / Authorized By:  
GAL X  
WEIGHMASTER  
Thank you for your business  
NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.  
LOAD RECEIVED BY  
x

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00CY	CLALS	CLASS A 3000 PSI			


RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		
			SLUMP	CONCRETE TEMP.	
			AIR	CYLINDERS	

Tax  
Prev. AMT  
Ticket Tot  
Grand Total  
ADDITIONAL CHARGE 1  
ADDITIONAL CHARGE 2  
GRAND TOTAL

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
390144	554014	user	6141568	50018	8:01	5/19/18
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
10.00 CYDS	CLALS					46
Material	Design Qty	Required	Batched	% Var	Moisture	Actual Wat
SAND	1385 lb	14473 lb	14370 lb	-0.71%	4.50% M	74 gl
WSTN1	1400 lb	14105 lb	14010 lb	-0.67%	0.75% M	12 gl
ROVEL 3/8"	470 lb	4771 lb	4790 lb	0.41%	1.50% M	8 gl
EMENT	315.0 lb	3150.0 lb	3140.0 lb	-0.32%		
LYASH	105.0 lb	1050.0 lb	1050.0 lb	0.00%		
ATER	30.2 gl	186.3 gl	186.5 gl	0.09%		186.5 gl
OZZ80	13.00 oz	190.00 oz	190.00 oz	0.00%		
Actual	Num Batches: 1					
oad Total: 38920 lb	Design W/C: 0.600	Water/Cement: 0.602	Manual	8:01:35		
Pump: 5.00 in	Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	Design Water: 302.0 gl	Actual Water: 281.5 gl	To Add: 20.4 gl	
			Load Trim Water: -2.0 gl			





 <b>Texas A&amp;M Transportation Institute</b> <small>Proving Ground 3100 SH 42, Bldg 7991 Bryan, TX 77807</small>	<b>5.7.2 Concrete Sampling</b>	Doc. No. QPF 5.7.2	Revision Date: 2018-04-17
		Revised by: B. L. Griffith Approved by: D. Kuhn	Revision: 6
<b>Quality Policy Form</b>			

Project No: 609951 Casting Date: 2018-05-31 Mix Design (psi): 4000

Printed Name of Technician taking Sample: GREG FRITZ  
 Printed Name of Technician breaking Sample: Matth Robinson  
 Signed Name of Technician taking Sample: [Signature]  
 Signed Name of Technician breaking Sample: [Signature]

Load No.	Truck No.	Ticket No.	Location (from concrete map)
BW1/T1	39RENTAL2	0021446	Bottom HALF WALL $\approx 110'$
BW2/T2	39RENTAL2	0021447	Top HALF <sup>SOUTH 6 Post</sup> WALL / BOTTOM HALF $\approx 45'$
BW3/T3	39RENTAL2	0021448	Top HALF <sup>from 8th 7th Post to</sup> WALL $15'$ from end

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
BW1/T1	2018-06-25	26 days	5659	160000	
BW1/T1			5659	160000	5659
BW1/T1			5659	160000	
BW2/T2	2018-06-25	26 days	6720	190000	
BW2/T2			6685	189000	6685
BW2/T2			6650	188000	
BW3/T3	2018-06-25	26 day	6508	184000	
BW3/T3			6013	170000	6331
BW3/T3			6423	187000	



AN MDU RESOURCES COMPANY  
Riverbend

SOUTH REGION/MAIN OFFICE  
6310 State Highway 21 West  
Bryan, TX 77807  
PH: (979) 361-2900  
FAX: (979) 361-2920

RB 0021448

TUCKER CONSTRUCTION  
7425 MIZE RD  
BRYAN

TTI TEN RAIL  
LF 47 LF RELIS CAMPUS STOP AT E  
NTRANCE WILL HAVE A PERSON TO TA  
KE TRUCKS IN.

Disp Order#: 2008

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
5:04:17	CLSLS	10.00	120.00	B'S TRANS 39RENTAL1	
DATE	PROJECT	LOAD #	YARDS DEL.	BATCH #	TICKET NUMBER
05/31/18	TTITENRAI	3	30.00		5.00 in 20012566

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
Contains Portland Cement. Wear Rubber Boots and Gloves, PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES or CANCELLATION of ORIGINAL INSTRUCTIONS MUST be TELEPHONED to the OFFICE BEFORE LOADING starts. The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.  
All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.  
A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)

Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of this vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.  
SIGNED:

X

Excessive Water is Detrimental to Concrete Performance.  
H<sub>2</sub>O Added by Request / Authorized By:

GAL X

WEIGHMASTER

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY

X

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00 YC	CLSLS	CLASS S 4000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		Prev. AMT
			SLUMP	CONCRETE TEMP	Ticket Total
					Grand Total
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS	ADDITIONAL CHARGE 1
					ADDITIONAL CHARGE 2
<b>GRAND TOTAL</b>					

Truck 39RENTAL1 Driver 1 User user Disp Ticket Num 20012566 Ticket ID 12514 Time Date 5:04 5/31/18  
Load Size 10.00 CYDS Mix Code CLSLS Returned Qty 3 Mix Age Seq D Load ID 3  
RB 0021448

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
CEMENT	417.00 lb	417.00 lb	416.00 lb	-0.14%			
FLYASH	143.00 lb	143.00 lb	141.50 lb	-0.98%			
SAND	1223 lb	1293 lb	1300 lb	0.52%	5.79% M	83 g	
LM STR#	1390 lb	1363 lb	1390 lb	0.62%	0.28% M	4 g	
GRAVEL3#	450 lb	462 lb	498 lb	7.72%	0.50% M	3 g	
WATER	252 lb	152 lb	151 lb	-0.09%			151 g
POZZ2#	25.00 oz	250.00 oz	250.00 oz	0.00%			
AE-90	3.00 oz	30.00 oz	30.00 oz	0.00%			

Actual	Design	Actual	Design	Actual	Design	Actual	Design
Load 39089 lb	Design W/C: 0.460	Water/Cement: 0.462 T	Design 302.0 g	Actual 282.5 g	To Add 19.5 g		
Slump: 5.00 in	Water In Truck: 0.0 g	Adjust Water: 0.0 g / Load	Trim Water: -2.0 g /	CYC			
Actual W/C Ratio: 0.423	Actual Water: 282 g	Batched Cement: 5950 lb	Allowable Water: 153 g				



AN MDU RESOURCES COMPANY  
Riverbend

SOUTH REGION/MAIN OFFICE  
6310 State Highway 21 West  
Bryan, TX 77807  
PH: (979) 361-2900  
FAX: (979) 361-2920

RB 0021447

TUCKER CONSTRUCTION  
7425 MIZE RD  
BRYAN

TTI TEN RAIL  
LF 47 LF RELLIS CAMPUS STOP AT E  
NTRANCE WILL HAVE A PERSON TO TA  
KE TRUCKS IN.

Disp Order#: 2008

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	YARDS DEL.	DRIVER/TRUCK	PLANT TRANSACTION #	
4:47:44	CLSLS	10.00	120.00		B'S TRANS 39RENTAL2		
DATE	PROJECT	LOAD #	YARDS DEL.	BATCH #	WATER TRIM	SLUMP	TICKET NUMBER
05/31/18	TTITENRAI	2	20.00			5.00 in	20012565

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
Contains Portland Cement. Wear Rubber Boots and Gloves, PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

**PROPERTY DAMAGE RELEASE**  
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)  
Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.

Excessive Water is Detrimental to Concrete Performance.  
H<sub>2</sub>O Added by Request / Authorized By:  
GAL X

WEIGHMASTER

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE

LOAD RECEIVED BY  
X

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4' SLUMP	UNIT PRICE	EXTENDED PRICE
10.00 CY	CLSLS	CLASS 3 4000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		
LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP.	
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS	

Tax  
 Prev. AMT  
 Ticket Total  
 Grand Total  
 ADDITIONAL CHARGE 1 \_\_\_\_\_  
 ADDITIONAL CHARGE 2 \_\_\_\_\_  
**GRAND TOTAL** ▶

Truck 39RENTAL2 Driver 2 User user Disp Ticket Num 20012565 Ticket ID 12513 Time Date 4:47 5/31/18  
 Load Size 10.00 CYDS Mix Code CLSLS Returned Qty Mix Age Seq Load ID  
 RB 0021447

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
CEMENT	417.00 lb	417.00 lb	4134.00 lb	-0.86%			
FLYASH	143.00 lb	143.00 lb	1429.00 lb	-0.42%			
SAND	1223 lb	12333 lb	12970 lb	0.29%	5.75% M	88 g	
LMSTN*	1360 lb	13836 lb	13780 lb	-0.39%	0.20% M	4 g	
GRAVEL3/8"	460 lb	4523 lb	4720 lb	> 2.10%	0.50% M	3 g	
WATER	262 lb	1852 lb	1692 lb	-0.02%		191 g	
POZZOL	26.00 oz	263.00 oz	263.00 oz	0.00%			
AE-30	3.00 oz	30.00 oz	30.00 oz	0.00%			

Actual Load 38638 lb Design W/C: 0.480 Water/Cement: 0.453 T Design 302.0 g Actual 282.2 g To Add 19.8 g  
 Slump: 5.00 in Water in Truck: 0.0 g Adjust Water: 0.0 g / Load Trim Water: -2.0 g / CYC  
 Actual W/C Ratio: 0.424 Actual Water: 262 g Batched Cement: 5558 lb Allowable Water: 146 g



SOUTH REGION/MAIN OFFICE  
6310 State Highway 21 West  
Bryan, TX 77807  
PH: (979) 361-2900  
FAX: (979) 361-2920

RB 0021446

Riverbend

TUCKER CONSTRUCTION  
7425 MIZE RD  
BRYAN

TTI TEN RAIL  
LF 47 LF RELLIS CAMPUS STOP AT E  
NTRANCE WILL HAVE A PERSON TO TA  
KE TRUCKS IN.

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
4:32:59	CLSLS	10.00	10.00	BIG TRANC 39RENTAL1	
DATE	PROJECT	LOAD #	YARDS DEL.	BATCH #	TICKET NUMBER
05/31/18	TTITENRAI	1	10.00		20012564

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
Contains Portland Cement, Wear Rubber Boots and Gloves, PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**  
CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES OR CANCELLATION OF ORIGINAL INSTRUCTIONS MUST BE TELEPHONED TO THE OFFICE BEFORE LOADING starts.  
The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.  
All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.  
A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks.  
Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)  
Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not tear the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.  
SIGNED:  
X

Excessive Water is Detrimental to Concrete Performance.  
H<sub>2</sub>O Added by Request / Authorized By:  
GAL X  
WEIGHMASTER  
Thank you for your business  
NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.  
LOAD RECEIVED BY  
X


QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00 yd	CLSLS	CLASS S 4000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP <sub>ax</sub>
			TESTING LAB:		Prev. AMT
			SLUMP	CONCRETE TEMP.	Ticket Total
					Grand Total
			AIR	CYLINDERS	ADDITIONAL CHARGE 1
					ADDITIONAL CHARGE 2
					<b>GRAND TOTAL</b>


Truck 39RENTAL1 Driver 1 User user Disp Ticket Num 20012564 Ticket ID 12512 Time Date 4:32:59  
Load Size 10.00 CYDS Mix Code CLSLS Returned Qty 10.00 Mix Age 1 Seq D 1  
RB 0021446


Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wast
CEMENT	417.00 lb	417.00 lb	4162.00 lb	0.23%			
FLYASH	143.00 lb	143.00 lb	1420.00 lb	-0.70%			
SAND	1325 lb	1325 lb	1325 lb	0.13%	0.75% M	94 g	
LIQSTN	1350 lb	13625 lb	13950 lb	0.83%	0.25% M	4 g	
GRAVEL3/8"	450 lb	4623 lb	4590 lb	7.94%	0.50% M	3 g	
WATER	252 lb	1532 lb	1586 lb	-0.27%		150 g	
POZZ80	25.00 oz	250.00 oz	250.00 oz	0.00%			
AE-90	3.00 oz	30.00 oz	30.00 oz	0.00%			

Actual Load 29096 lb Design W/C: 0.450 Water/Cement: 0.450 T Design 302.0 g Actual 281.8 g To Add 20.2 g  
Slump: 5.00 in Water In Truck: 0.0 g Adjust Water: 0.0 g / Load Trim Water: -2.0 g / CYC  
Actual W/C Ratio: 0.420 Actual Water: 282 g Batched Cement: 5602 lb Allowable Water: 169 g



Plan view of Deck and Moment Slab

	Roadside Safety and Physical Security Division - Proving Ground	
	Project #609591 PenDOT	2018-05-31
Drawn by GES	Scale 1:200	Sheet 4 of 4 Concrete Map, Deck and MS

 <b>Texas A&amp;M Transportation Institute</b> <small>Proving Ground 3100 SH 47, Bldg 7091 Bryan, TX 77807</small>	<b>5.7.2 Concrete Sampling</b>	Doc. No. QPF 5.7.2	Revision Date: 2018-04-17
		Revised by: B. L. Griffith Approved by: D. Kuhn	Revision: 6


Project No: 60951 Casting Date: 2018-05-31 Mix Design (psi): 4000

Printed Name of Technician taking Sample: GREG FRITZ Printed Name of Technician breaking Sample: Matt Robinson  
 Signed Name of Technician taking Sample: [Signature] Signed Name of Technician breaking Sample: [Signature]

BK  
018-06-25

Load No.	Truck No.	Ticket No.	Location (from concrete map)
<del>D1/T4</del>	390143	0021449	Final 15' of Top Wall, SOUTHERN DECK to Post #3
<del>D2/T5</del>	390120	0042464	Start @ Post #3 on South Deck to Post #10
<del>D3/T6</del>	390133	0021450	Start @ Post #10 from South Deck to Post #15

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
D1/T4	2018-06-25	26 days	6225	126000	
D1/T4			5510	156000	6060
D1/T4			6437	102000	
D2/T5	2018-06-25	26 days	5942	168000	
D2/T5			6190	175000	6119
D2/T5			6225	176000	
D3/T6	2018-06-25	26 days	5836	165000	
D3/T6			5695	161000	5694
D3/T6			5553	157000	

 <b>Texas A&amp;M Transportation Institute</b> <small>Proving Ground 3100 SH 47, Bldg 7091 Bryan, TX 77807</small>	<b>5.7.2 Concrete Sampling</b>	Doc. No. QPF 5.7.2	Revision Date: 2018-04-17
		Revised by: B. L. Griffith Approved by: D. Kuhn	Revision: 6 Page: 1 of 1
<b>Quality Policy Form</b>			

Project No: 609951 Casting Date: 2018-05-31 Mix Design (psi): 4000

Printed Name of Technician taking Sample: GREG FITZ Printed Name of Technician breaking Sample: MATT ROBINSON  
 Signed Name of Technician taking Sample: [Signature] Signed Name of Technician breaking Sample: [Signature]

Load No.	Truck No.	Ticket No.	Location (from concrete map)
D4/T7	390108	0021452	Post #15 from South Side to Post #18 W/MS
D5/T8	390126	0021454	Post #18 W/MS to End of Deck
D6/T9	39Renta/2	0042475	10' x 15' section w/ P Moment Slab NE corner

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
D4/T7	2018-06-25	26 days	5164	146000	
D4/T7			5164	146000	5140
D4/T7			5093	144000	
D5/T8	2018-06-25	26 days	5552	157000	
D5/T8			5129	145000	5423
D5/T8			5588	158000	
D6/T9	2018-06-25	26 days	6473	189000	
D6/T9			6614	187000	6449
D6/T9			6261	177000	



AN MDU RESOURCES COMPANY  
Bryan Plant #6

**SOUTH REGION/MAIN OFFICE**  
6310 State Highway 21 West  
Bryan, TX 77807  
PH: (979) 361-2900  
FAX: (979) 361-2920

**BRYAN**  
6310 Hwy, 21 West  
Bryan, TX 77807  
DISPATCH: (979) 361-2931  
FAX: (979) 361-2920

**B 0042464**

TUCKER CONSTRUCTION  
7425 MIZE RD  
BRYAN

TTI TEN RAIL  
LF 47 LF RELLIS CAMPUS STOP AT E  
ENTRANCE WILL HAVE A PERSON TO TAKE  
TRUCKS IN.

Disp Order#: 2008

TIME	FORMULA	LOAD SIZE	YARDS ORDERED		DRIVER/TRUCK	PLANT TRANSACTION #
5:50:01	CL6LS	10.00	120.00		DON KING 390128	
DATE		LOAD #	YARDS DEL	BATCH #	WATER TRIM	TICKET NUMBER
03/31/18	TTI TENRAI	5	50.00		5.00 in	6141807

<p><b>WARNING</b> <b>IRRITATING TO THE SKIN AND EYES</b> Contains Portland Cement. Wear Rubber Boots and Gloves, PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. <b>KEEP CHILDREN AWAY.</b></p> <p>CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES or CANCELLATION OF ORIGINAL INSTRUCTIONS MUST be TELEPHONED to the OFFICE BEFORE LOADING starts.</p> <p>The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.</p> <p>All accounts not paid within 30 days of delivery will bear interest at the rate of 15% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.</p> <p>A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.</p>	<p><b>PROPERTY DAMAGE RELEASE</b> (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)</p> <p>Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.</p> <p>SIGNED:</p> <p>X</p>	<p>Excessive Water is Detrimental to Concrete Performance. H<sub>2</sub>O Added by Request / Authorized By:</p> <p>GAL X</p> <p>WEIGHMASTER</p> <p>Thank you for your business</p> <p>NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.</p> <p>LOAD RECEIVED BY</p> <p>X</p>
--	--	---

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00 CY	CL6LS	CLASS 5 4000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		
LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP.	
6:00	6:30	6:15			
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS	

Tax  
Prev. AMT  
Ticket Tot  
Grand Total

ADDITIONAL CHARGE 1 \_\_\_\_\_  
ADDITIONAL CHARGE 2 \_\_\_\_\_

**GRAND TOTAL** ▶

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time Date
390128	64534	user	6141807	50256	5:50 B31 0042464
Load Size	Mix Code	Returned	Qty	Mix Age	Seq Load ID
10.00 CYDS	CL6LS				3
Material	Design Qty	Required	Batched	% Var	Moisture
SAND	1223 lb	12750 lb	12530 lb	-0.94%	4.25% M
MS7N1*	1380 lb	13800 lb	13570 lb	-0.94%	
GRAVEL 3/8"	460 lb	4669 lb	4740 lb	+ 1.52%	1.50% M
CEMENT	417.0 lb	4170.0 lb	4184.0 lb	+ 0.34%	
LYRSH	143.0 lb	1430.0 lb	1468.0 lb	+ 2.18%	
WATER	30.3 gl	212.4 gl	212.3 gl	-0.05%	
E-90	3.00 oz	30.00 oz	30.00 oz	0.00%	212.3 gl
OZZ80	25.00 oz	250.00 oz	250.00 oz	0.00%	
Actual Num Batches:	1				
oad Total:	38474 lb	Design W/C: 0.452	Water/Cement: 0.448	T Design Water: 303.0 gl	Actual Water: 282.4 gl
Slump:	5.00 in	Water in Trucks: 0.0 gl	Adjust Water: 0.0 gl	Load Trim Water: -2.0 gl	CYDS To Add: 20.6 gl





AN MDU RESOURCES COMPANY

Riverbend

**SOUTH REGION/MAIN OFFICE**  
 6310 State Highway 21 West  
 Bryan, TX 77807  
 PH: (979) 361-2900  
 FAX: (979) 361-2920

RB 0021449

TUCKER CONSTRUCTION  
 7425 MIZE RD  
 BRYAN

TTI TEN RAIL  
 LF 47 LF RELLIS CAMPUS STOP AT E  
 ENTRANCE WILL HAVE A PERSON TO TA  
 KE TRUCKS IN.

Disp Order#: 2008

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	POB	DRIVER/TRUCK	PLANT TRANSACTION #	
5:19:05	CLSLS	10.00	120.00		ROY DAVIS 390143		
DATE	PROJECT	LOAD #	YARDS DEL	BATCH #	WATER TRIM	SLUMP	TICKET NUMBER
05/31/18	TTITENRAI	4	40.00			5.00 in	20012567

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
 Contains Portland Cement. Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. KEEP CHILDREN AWAY.

CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES or CANCELLATION of ORIGINAL INSTRUCTIONS MUST be TELEPHONED to the OFFICE BEFORE LOADING starts.

The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.

All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.

A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
 (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)

Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.

SIGNED: \_\_\_\_\_  
 X

Excessive Water is Detrimental to Concrete Performance.  
 H<sub>2</sub>O Added by Request / Authorized By: \_\_\_\_\_  
 GAL X \_\_\_\_\_

WEIGHMASTER

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY \_\_\_\_\_  
 X

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00	yc CLSLS	CLASS 3 4000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		
			SLUMP	CONCRETE TEMP.	
5:35	5:49	6:22			
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS	

Tax AMT

Prev. AMT

Ticket Total

Grand Total

ADDITIONAL CHARGE 1 \_\_\_\_\_

ADDITIONAL CHARGE 2 \_\_\_\_\_

**GRAND TOTAL** ▶

Truck 390143 Driver 554626 User user Disp Ticket Num 20012567 Ticket ID 12515 Time Date 5:19 5/31/18

Load Size 10.00 CYDS Mix Code CLSLS Returned Qty Mix Age Seq Load ID 4

RB 0021449

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wet
CEMENT	417.00 lb	4170.00 lb	4150.00 lb	-0.48%			
FLYASH	143.00 lb	1430.00 lb	1432.00 lb	0.14%			
SAND	1223 lb	12842 lb	12360 lb	0.94%	5.00% M	74 g	
LM STN*	1360 lb	13835 lb	13980 lb	1.25%	0.25% M	4 g	
GRAVEL 3/8"	460 lb	4623 lb	4910 lb	> 6.21%	0.50% M	3 g	
WATER	252 lb	1684 lb	1683 lb	-0.07%		202 g	
POZZO	25.00 oz	250.00 oz	250.00 oz	0.00%			
AE-90	3.00 oz	30.00 oz	30.00 oz	0.00%			

Actual Load 39123 lb Design W/C: 0.450 Water/Cement: 0.452 T Design 302.0 g Actual 292.7 g To Add: 19.3 g

Slump: 5.00 in Water in Truck: 0.0 g Adjust Water: 0.0 g / Load Trim Water: -2.0 g / Cyt

Actual W/C Ratio: 0.423 Actual Water: 283 g Batched Cement: 5592 lb Allowable Water: 152 g



AN MDU RESOURCES COMPANY  
Riverbend

SOUTH REGION/MAIN OFFICE  
6310 State Highway 21 West  
Bryan, TX 77807  
PH: (979) 361-2900  
FAX: (979) 361-2920

RB 0021450

TUCKER CONSTRUCTION  
7425 MIZE RD  
BRYAN

TTI TEN RAIL  
LE 47 LF RELLIS CAMPUS STOP AT E  
NTRANCE WILL HAVE A PERSON TO TA  
KE TRUCKS IN.

Disp Order#: 2008

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
6:03:46	CLSLS	10.00	120.00	LLOYD JON 390133	
DATE	PROJECT	LOAD #	YARDS DEL	BATCH #	TICKET NUMBER
05/31/18	TTITENRAI	6	60.00		5.00 in 20012569

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
Contains Portland Cement. Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**  
CONCRETE IS A PERISHABLE COMMODITY AND BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES OR CANCELLATION OF ORIGINAL INSTRUCTIONS MUST BE TELEPHONED TO THE OFFICE BEFORE LOADING starts.  
The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.  
All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.  
A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)  
Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.  
SIGNED:  
X

Excessive Water is Detrimental to Concrete Performance.  
H<sub>2</sub>O Added by Request / Authorized By:  
GAL X  
WEIGHMASTER  
Thank you for your business  
NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.  
LOAD RECEIVED BY  
X

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00	CLSLS	CLASS 5 4000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		
			SLUMP	CONCRETE TEMP.	
10:19	6:36				
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS	

Prev. AMT  
Ticket Total  
Grand Total  
ADDITIONAL CHARGE 1  
ADDITIONAL CHARGE 2  
GRAND TOTAL ▶

Truck 390133 Driver 490896 User user Disp Ticket Num 20012569 Ticket ID 12516 Time Date 6:03 5/31/18  
Load Size 10.00 CYDS Mix Code CLSLS Returned Qty Mix Age Seq Load ID 5  
RB 0021450

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wet
CEMENT	417.00 lb	417.00 lb	418.00 lb	0.34%			
FLYASH	143.00 lb	143.00 lb	144.00 lb	1.25%			
SAND	1223 lb	1298.2 lb	1298 lb	0.32%	5.00% M	74 g	
LAGGERS	1300 lb	1393.8 lb	1368 lb	0.19%	0.29% M	4 g	
GRAVELS	460 lb	452.3 lb	501 lb	8.37%	0.50% M	3 g	
WATER	252 lb	168.4 lb	168.3 lb	-0.07%		202 g	
P-02280	25.00 oz	280.00 oz	250.00 oz	0.00%			
AE-90	3.00 oz	30.00 oz	30.00 oz	0.00%			

Actual Num Batches: 1  
Load 39163 lb Design W/C: 0.460 Water/Cement: 0.447 T Design 302.0 g Actual 282.8 g To Add 19.2 g  
Slump: 5.00 in Water in Truck: 0.0 g Actual Water: 0.0 g / Load Trim Water: -2.0 g / CYC  
Actual W/C Ratio: 0.419 Actual Water: 283 g Batched Cement: 5632 lb Allowable Water: 174 g



AN MDU RESOURCES COMPANY  
Bryan Plant #6

**SOUTH REGION/MAIN OFFICE**  
6310 State Highway 21 West  
Bryan, TX 77807  
PH: (979) 361-2900  
FAX: (979) 361-2920

**BRYAN**  
6310 Hwy. 21 West  
Bryan, TX 77807  
DISPATCH: (979) 361-2931  
FAX: (979) 361-2920

**B 0042475**

TUCKER CONSTRUCTION  
7425 MIZE RD  
BRYAN

TTI TEN RAIL  
LP 47 LP RELLIS CAMPUS STOP AT E  
NTRANCE WILL HAVE A PERSON TO TA  
KE TRUCKS IN.

Disp Order#: 2008

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
8:57:52	CLSLS	8.00	98.00	B'S TRANS	39RENTAL2
DATE	LOAD #	YARDS DEL	BATCH #	WATER TRIM	TICKET NUMBER
05/31/18	10	98.00		5.00in	6141818

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
Contains Portland Cement. Wear Rubber Boots and Gloves. **PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water If Irritation Persists. Get Medical Attention KEEP CHILDREN AWAY.**

**PROPERTY DAMAGE RELEASE**  
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)  
Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.  
SIGNED: \_\_\_\_\_  
X

**Excessive Water is Detrimental to Concrete Performance.**  
H<sub>2</sub>O Added by Request / Authorized by: \_\_\_\_\_  
GAL X \_\_\_\_\_

**WEIGHMASTER**  
Thank you for your business

**NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.**

**LOAD RECEIVED BY**  
\_\_\_\_\_

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
8.00CY	CLSLS	CLASS S 4000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING	AIR TEMP
			TESTING LAB:	
LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS

Tax  
Prev. AMT  
Ticket Tot  
Grand Total

ADDITIONAL CHARGE 1 \_\_\_\_\_  
ADDITIONAL CHARGE 2 \_\_\_\_\_  
**GRAND TOTAL** ▶

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
39RENTAL2	2	user	6141818	50267	8:57	05/31/18
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
8.00 CYDS	CLSLS				D	14
Material	Design Qty	Required	Batched	% Var Moisture	Actual Mat	
SAND	1823 lb	1820 lb	1010 lb	-0.19%	4.25% M	50 gl
WATER	1390 lb	1104 lb	1117 lb	1.18%		
GRAVEL 3/8"	460 lb	3735 lb	3730 lb	-0.14%	1.50% M	7 gl
CEMENT	417.0 lb	3336.0 lb	3310.0 lb	-0.78%		
WASH	143.0 lb	1144.0 lb	1140.0 lb	-0.35%		
WATER	30.3 gl	170.0 gl	169.9 gl	-0.02%		
WATER	3.00 oz	24.00 oz	24.00 oz	0.00%		169.9 gl
WATER	25.00 oz	200.00 oz	200.00 oz	0.00%		
Actual	Num Batches: 1			Manual		8:57:52
Load Total:	30962 lb	Design W/C: 0.452	Water/Cement: 0.455 T	Design Water: 242.4 gl	Actual Water: 226.3 gl	To Add: 16.1 gl
Slump:	5.00 in	Water in Trucks: 0.0 gl	Adjust Water: 0.0 gl	Load Trim Water: -2.0 gl / CYDS		



AN MDU RESOURCES COMPANY

Riverbend

**SOUTH REGION/MAIN OFFICE**  
 6310 State Highway 21 West  
 Bryan, TX 77807  
 PH: (979) 361-2900  
 FAX: (979) 361-2920

RB 0021454

TUCKER CONSTRUCTION  
 7425 MIZE RD  
 BRYAN

TTI TEN RAIL  
 LF 47 LF RELLIS CAMPUS STOP AT E  
 ENTRANCE WILL HAVE A PERSON TO TA  
 KE TRUCKS IN.

Disp Order#: 2008

TIME	FORMULA	LOAD SIZE	YARDS ORDERED		DRIVER/TRUCK	PLANT TRANSACTION #
7:03:09	CLSLS	10.00	120.00		FREDDIE E 390126	
DATE	PROJECT	LOAD #	YARDS DEL.	BATCH #	WATER TRIM	TICKET NUMBER
05/31/18	TTITENRAI	9	90.00			5.00 in 20012574

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
 Contains Portland Cement. Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

CONCRETE IS A PERISHABLE COMMODITY AND BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES OR CANCELLATION OF ORIGINAL INSTRUCTIONS MUST BE TELEPHONED TO THE OFFICE BEFORE LOADING starts.

The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.

All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.

A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
 (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)

Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and the supplier from any responsibility from damage that may occur to the curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.

SIGNED:  
 X

Excessive Water is Detrimental to Concrete Performance.  
 H<sub>2</sub>O Added by Request / Authorized By:  
 GAL X

WEIGHMASTER

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY  
 X

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00 yd	CLSLS	CLASS S 4000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP <sup>max</sup>
			TESTING LAB:		Prev: AMT
			SLUMP	CONCRETE TEMP:	Ticket Total
7:20	7:35				Grand Total
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS	ADDITIONAL CHARGE 1
					ADDITIONAL CHARGE 2
					<b>GRAND TOTAL</b> ▶

Truck 390126 Driver 559579 User user Disp Ticket Num 20012574 Ticket ID 12520 Time Date 7:03 5/31/18  
 Load Size 10.00 CYDS Mix Code CLSLS Returned Qty Mix Age Seq Load ID 10  
 RB 0021454

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wtr
CEMENT	417.00 lb	417.00 lb	416.00 lb	0.24%			
FLYASH	143.00 lb	143.00 lb	142.20 lb	-0.56%			
SAND	1225 lb	1294 lb	1299 lb	0.07%	3.00% M	73	g
LIQUID	1390 lb	1399 lb	1399 lb	0.14%	0.50% M	3	g
GRAVELS <sup>3/8"</sup>	460 lb	462 lb	502 lb	8.59%	0.50% M		
WATER	282 lb	1664 lb	1696 lb	0.11%		202	g
POZZOL	26.00 oz	260.00 oz	260.00 oz	0.00%			
AE-90	3.00 oz	30.00 oz	30.00 oz	0.00%			

Actual	Design	Water/Cement	Actual	To Add
Load 39036 lb	Design 302.0 g	Water/Cement: 0.450 T	Actual 282.8 g	To Add 19.5 g
Slump: 5.00 in	Water in Truck: 0.0 g	Adjust Water: 0.0 g / Load	Trim Water: -2.0 g / CYL	
Actual W/C Ratio: 0.421	Actual Water: 282 g	Batched Cement: 5602 lb	Allowable Water: 163 g	



AN MDU RESOURCES COMPANY

**SOUTH REGION/MAIN OFFICE**  
 6310 State Highway 21 West  
 Bryan, TX 77807  
 PH: (979) 361-2900  
 FAX: (979) 361-2920

**RB 0021452**

Riverbend

**TUCKER CONSTRUCTION**  
 7425 MIZE RD  
 BRYAN

**TTI TEN RAIL**  
 LF 47 LF RELLIS CAMPUS STOP AT E  
 NTRANCE WILL HAVE A PERSON TO TA  
 KE TRUCKS IN.

Disp Order#: 2008

TIME	FORMULA	LOAD SIZE	YARDS ORDERED		DRIVER/TRUCK	PLANT TRANSACTION #
6:37:49	CLSLS	10.00	120.00		MELVIN MA 390108	
DATE	PROJECT	LOAD #	YARDS DEL.	BATCH #	WATER TRIM	TICKET NUMBER
05/31/18	TTITENRAI	8	80.00		5.00 in	20012572

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
 Contains Portland Cement. Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

**CONCRETE** is a PERISHABLE COMMODITY and BECOMES THE PROPERTY of the PURCHASER UPON LEAVING THE PLANT. ANY CHANGES or CANCELLATION of ORIGINAL INSTRUCTIONS MUST be TELEPHONED to the OFFICE BEFORE LOADING starts. The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed. All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered. A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
 (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)  
 Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE, relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.  
 SIGNED: X

Excessive Water is Detrimental to Concrete Performance.  
 H<sub>2</sub>O Added by Request / Authorized By:  
 GAL X

**WEIGHMASTER**

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY: X


QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00 yd	CLSLS	CLASS 5 4000 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
			TESTING LAB:		Prev. AMT
			SLUMP	CONCRETE TEMP.	Ticket Total
					Grand Total
			AIR	CYLINDERS	ADDITIONAL CHARGE 1
					ADDITIONAL CHARGE 2
					<b>GRAND TOTAL</b>

Truck 390108 Driver 569696 User user Disp Ticket Num 20012572 Ticket ID 12518 Time Date 6:37 5/31/18  
 Load Size 10.00 CYDS Mix Code CLSLS Returned Qty Mix Age Seq Load ID 8

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
CEMENT	417.00 lb	417.00 lb	416.00 lb	-0.14%			
FLYASH	143.00 lb	143.00 lb	142.00 lb	-0.26%			
SAND	1262 lb	1262 lb	1260 lb	-0.16%	0.00%	74 g	
LIME	1300 lb	1300 lb	1298 lb	-0.15%	0.20%	4 g	
GRAVEL#3	460 lb	462 lb	500 lb	> 3.59%	0.50%	3 g	
WATER	292 lb	1684 lb	1683 lb	-0.07%		212 g	
POZZOL	25.00 oz	250.00 oz	250.00 oz	0.00%			
AE-90	3.00 oz	30.00 oz	30.00 oz	0.00%			

Actual Load 39231 lb Design W/C: 0.450 Water/Cement: 0.451 T Design 302.0 g Actual 282.9 g To-Add 19.1 g  
 Slump: 5.00 in Water in Truck: 0.0 g Adjust Water: 0.0 g / Load Trim Water: -2.0 g / CYC  
 Actual W/C Ratio: 0.422 Actual Water: 283 g Batched Cement: 5590 lb Allowable Water: 154 g



Roadside Safety and  
Physical Security Division -  
Proving Ground

Project #609591 PenDOT		2018-05-31
Drawn by GES	Scale 1:200	Sheet 5 of 5 Concrete Map, Parapet





AN MDU RESOURCES COMPANY

**SOUTH REGION/MAIN OFFICE**  
 6310 State Highway 21 West  
 Bryan, TX 77807  
 PH: (979) 361-2900  
 FAX: (979) 361-2920

**RB 0021554**

Riverbend

TUCKER CONSTRUCTION  
 7425 MIZE RD  
 BRYAN

TTI TEN RAIL  
 LF 47 LF RELIS CAMPUS STOP AT THE ENTRANCE AN WAIT THEY WILL HAVE A PERSON PICK UP THE TRUCKS AND TAKE TO JOB.

Disp Order#: 2002

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
8:54:32	CLCLS	10.00	20.00	DON KING 390149	
DATE	PROJECT	LOAD #	YARDS DEL	BATCH #	TICKET NUMBER
06/05/18	TTITENRAI	1	10.00		5.00 in 20012674

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
 Contains Portland Cement. Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

CONCRETE IS A PERISHABLE COMMODITY AND BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES OR CANCELLATION OF ORIGINAL INSTRUCTIONS MUST BE TELEPHONED TO THE OFFICE BEFORE LOADING starts.

The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.

All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible for Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.

A \$15.00 Service Charge and Loss of the Cash Discount will be Collected on all Returned Checks. Excess Delay Time Charged @ \$75.00/hr.

**PROPERTY DAMAGE RELEASE**  
 (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)

Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to clear the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.

SIGNED: \_\_\_\_\_

X

Excessive Water is Detrimental to Concrete Performance.  
 H<sub>2</sub>O Added by Request / Authorized By: \_\_\_\_\_

GAL X  
 WEIGHMASTER

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY  
 X *S. Mate*

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00 yd	CLCLS	CLASS C 3600 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP
		9:53	TESTING LAB:		
LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP.	
9:10	9:28	9:33			
TOTAL ROUND TRIP	TOTAL AT JOB	UNLOADING TIME	AIR	CYLINDERS	

Prev. AMT  
 Ticket Total  
 Grand Total

ADDITIONAL CHARGE 1 \_\_\_\_\_  
 ADDITIONAL CHARGE 2 \_\_\_\_\_

**GRAND TOTAL** ▶

Truck 90149 Driver 64534 User user Disp Ticket Num 20012674 Ticket ID 12620 Time Date 8:54 6/5/18

Load Size 10.00 CYDS Mix Code CLCLS Returned Qty Mix Age Seq D Load ID 7

**RB 0021554**

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wet
CEMENT	396.00 lb	396.00 lb	394.00 lb	-0.40%			
WASH SAND	154.00 lb	154.00 lb	153.00 lb	-0.62%			
WATER	1227 lb	1227 lb	1229 lb	0.16%	3.00% M	1232 lb	1232 lb
ADDITIONAL WATER	1360 lb	1360 lb	1350 lb	-0.44%	0.50% M	1355 lb	1355 lb
ADDITIONAL WASH SAND	480 lb	480 lb	510 lb	6.49%	0.75% M	515 lb	515 lb
ADDITIONAL WATER	247 lb	247 lb	149 lb	-40.08%		149 lb	149 lb
ADDITIONAL WASH SAND	28.00 oz	28.00 oz	28.00 oz	0.00%			

Num Batches: 1

Design W/C: 0.450 Water/Cement: 0.452 T Design 295.5 g Actual 277.1 g To Add 19.3 g

Water in Truck: 0.0 g Adjust Water: 0.0 g / Load Trim Water: -2.0 g / CYC

Actual Water: 277 g Batched Cement: 547.5 lb Allowable Water: 150 g





**SOUTH REGION/MAIN OFFICE**  
 6310 State Highway 21 West  
 Bryan, TX 77807  
 PH: (979) 361-2900  
 FAX: (979) 361-2920

**RB 0021556**

Riverbend

TUCKER CONSTRUCTION  
 7425 MIZE RD  
 BRYAN

TTI TEN RAIL  
 LF 47 LF RELLIS CAMPUS STOP AT THE ENTRANCE AN WAIT THEY WILL HAVE A PERSON PICK UP THE TRUCKS AND TAKE TO JOB.

Disp Order#: 2002

TIME	FORMULA	LOAD SIZE	YARDS ORDERED	DRIVER/TRUCK	PLANT TRANSACTION #
9:28:21	CLCLS	10.00	20.00	FREDBICK 390141	
DATE	PROJECT	LOAD #	YARDS DEL.	BATCH #	TICKET NUMBER
06/05/18	TTITENRAI	2	20.00		5.00 in 20012676

**WARNING**  
**IRRITATING TO THE SKIN AND EYES**  
 Contains Portland Cement. Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact With Skin. In Case of Contact With Skin or Eyes, Flush Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

**PROPERTY DAMAGE RELEASE**  
 (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)  
 Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, drive-ways, curbs, etc., by the delivery of this material, and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public street. Further, as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order.  
 SIGNED: X

Excessive Water is Detrimental to Concrete Performance.  
 H<sub>2</sub>O Added by Request / Authorized By: 5 GAL X  
 WEIGHMASTER

Thank you for your business

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.  
 LOAD RECEIVED BY  
 X Danillee SANCHEZ

QUANTITY	CODE	DESCRIPTION	OUR MIXES ARE DESIGNED TO ACHIEVE SPECIFICATIONS AT A MAX 4" SLUMP	UNIT PRICE	EXTENDED PRICE
10.00 yd	CLCLS	CLASS C-3600 PSI			

RETURNED TO PLANT	LEFT JOB	FINISH UNLOADING	ON SITE TESTING		AIR TEMP**
			TESTING LAB:		Prev. AMT
					Ticket Total
					Grand Total
					ADDITIONAL CHARGE 1
					ADDITIONAL CHARGE 2
					<b>GRAND TOTAL</b>

Truck 390141 Driver 424514 User user Disp Ticket Num 20012676 Ticket ID 12622 Time Date 9:28 6/5/18  
 Load Size 10.00 Mix Code CYCLS Returned Qty Mix Age Seq Load ID 8  
**RB 0021556**

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wal
CEMENT	396.00 lb	396.00 lb	396.00 lb	0.00%			
FLYASH	154.00 lb	154.00 lb	154.00 lb	0.00%			
SAND	1287 lb	1287 lb	1288 lb	0.02%	3.50% M	37 g	
LMSTN#	1380 lb	1380 lb	1380 lb	0.07%	0.50% M	8 g	
GRAVEL3"	430 lb	430 lb	526 lb	3.56%	0.75% M	5 g	
WATER	247 lb	1434 lb	1493 lb	-0.08%		173 g	
POZZOL	28.00 oz	280.00 oz	280.00 oz	0.00%			

Actual Load	Design W/C	Water/Cement	Design	Actual	To Add
39631 lb	0.450	0.450 T	255.5 g	276.9 g	19.7 g
Slump: 5.00 in	Water in Truck: 0.0 g	Adjust Water: 0.0 g / Load	Trim Water: 5500 lb	-2.0 g /	CYC
Actual W/C Ratio: 0.420	Actual Water: 277 g	Batched Cement:	Allowable Water: 164 g		

3/4x12 Bolt



Vulcan Threaded Products  
10 Cross Creek Trail  
Pelham, AL 35124  
Tel (205) 620-5100  
Fax (205) 620-5150

**JOB MATERIAL CERTIFICATION**

<b>Job No:</b> 545930	<b>Job Information</b>	<b>Certified Date:</b> 8/29/17
<b>Containers:</b> S12836326	<i>W/B</i>	<b>Ship To:</b> 18060 Al Hwy 21 Sycamore, AL 35149
<b>Customer:</b> AmeriBolt, Inc		
<b>Vulcan Part No:</b> ATR F1554-55 3/4x12 HDG		<b>Shipped Qty:</b> 60 Ft
<b>Customer Part No:</b> ATR F1554-55 3/4x12 HDG		<b>Line No:</b> 2
<b>Customer PO No:</b> 0075668 <i>-10</i>		
<b>Order No:</b> 338482		
<b>Note:</b>	<i>TR 57-075 X 1800</i>	

**Applicable Specifications**

Type	Specification	Rev	Amend	Option
-	ASTM F1554 Gd 55	2015		

**Test Results**

**Part No:** ATR F1554-55 3/4x12 - 2A

**Test No:** 44335 **Test:** F1554-55 Physical Results1

Description	Tensile (ksi)	Yield (ksi)	Elongation (%)	Elongation GL (in)	Reduction of Area (%)	Note
	81	71	27	4D	63	

**Certified Chemical Analysis**

Heat No: DL17104915 Lot: .718				Origin: USA		
C	Mn	P	S	Si	Cu	
0.160	0.64	0.006	0.024	0.20	0.24	
Ni	Cr	Mo	V	Cb	PR	
0.08	0.10	0.02	0.004	0.004	120.6:1	

**Notes**

No welds, no Mercury were used in production of this material. Melted and Manufactured In the USA.  
Document is in accordance with EN 10204 - 3.1B of 2004 (3.1).

*Griffin Mitchell* 8/29/17  
Griffin, Mitchell - Certification Engineer Date

TR No. 609591-03

79

2018-09-27



12400 Highway 43 North, Axis, Alabama 36505, US

# H1A 85550, 85551, 85552 Test Certificate

Form TC1: Revision 2: Date 23 Apr 2014

Customer: CHAPEL STEEL CO PO BOX 1000  SPRING HOUSE PA 19477				Customer P.O.No.:HOU-8544				Mill Order No. 41-522620-05				Shipping Manifest: AR255328									
Product Description: ASTM A572-50/M345(15)/A709-50/M345(17) TYPE 2, .010% MAX S LCVN 20 FT.LBS @ -22F/A673-H								Ship Date: 11 Dec 17 Cert Date: 11 Dec17				Cert No: 081637479 (Page 1 of 1)									
Size: 1.000 X 120.0 X 480.0 (IN)																					
Tested Pieces:				Tensiles:				Charpy Impact Tests													
Heat Id	Piece Id	Piece Dimensions	Tst Loc	YS (KSI)	UTS (KSI)	%RA	Elong % 2in 8in	Tst Dir	Hardness	Abs. Energy(FTLB) 1 2 3 Avg				% Shear 1 2 3 Avg				Tst Tmp	Tst Dir	Tst Siz (mm)	BDWTT Tst %Shr
E7L024	A14	1.001 (DISCRT)	L	56	74		25	T		61	96	72	76					-22F	L	10.	
Heat Id				Chemical Analysis														ORGN			
E7L024	C	Mn	P	S	Si	Tot Al	So Al	Cu	Ni	Cr	Mo	Cb	V	Ti	IIW	USA					
	.16	1.05	.011	.001	.20	.027	.026	.24	.08	.11	.03	.002	.042	.002	.39						
<p>KILLED STEEL MERCURY IS NOT A METALLURGICAL COMPONENT OF THE STEEL AND NO MERCURY WAS INTENTIONALLY ADDED DURING THE MANUFACTURE OF THIS PRODUCT. KILLED STEEL, PRODUCED TO A FINE GRAIN PRACTICE CEV (IIW) = C + MN/6 + (CR+MO+V)/5 + (NI+CU)/15 MTR EN 10204:2004 INSPECTION CERTIFICATE 3.1 COMPLIANT 100% MELTED AND MANUFACTURED IN THE USA. PRODUCTS SHIPPED: E7L024            A14            PCES:    3, LBS:    49005</p>																					
HT# E7L024												Material provided by: 									
(P) Cust Part #:										WE HEREBY CERTIFY THAT THIS MATERIAL WAS TESTED IN ACCORDANCE WITH, AND MEETS THE REQUIREMENTS OF, THE APPROPRIATE SPECIFICATION											
										Justin Ward SENIOR METALLURGIST - PRODUCT											

**ArcelorMittal Burns Harbor Plate**

QUALITY ASSURANCE  
REPORT OF TEST AND ANALYSES

US HWY 12 Burns Harbor, Indiana

SHIPMENT NO. <b>8GA-09695</b>		DATE SHIPPED <b>03-06-17</b>	CAR OR VEHICLE NO. <b>CUSTOMER TRUCK T RICH PAGE</b>		
S O L D T O	SUNBELT GROUP L P 1990 POST OAK BLVD SUITE 950 HOUSTON TX 77056-3813		S H I P T O	SUNBELT GROUP L P C/O ARROW STEEL PROCESSORS 8710 CLINTON DR HOUSTON TX 77547	

S E R I A L N O T E	S E R I A L N O. N O.	P A T T E R N N O.	H E A T N O. N O.	N O. P C S.	S I Z E A N D Q U A N T I T Y				Y I E L D P O I N T	T E N S I L E S T R E N G T H	A F F R A C. E L O N G.	R E D.
					T H I C K N E S S	W I D T H O R D I A.	L E N G T H	W E I G H T				

					INCHES	INCHES	INCHES	POUNDS	PSI	PSI	IN	%
QUALITY STEEL MELTED & MANUFACTURED IN THE U. S. A.												
PLATES - AASHTO M270-12 GR 50 KLD FINE GRAIN												
PRAC NO IMPACTS REQUIRED TYPE 2,												
ASTM A709-07 GR 50, ASTM A572-06 GR												
50, ASME SA572 GR 50 2013 EDITION												
MFST - MFST MILL SERIAL# & PATTERN# MFST PROC ON												
GH820-5721A LIFT MAX 15 TON-SIZES & GRADES SEP												
UNLDG FORK LIFT-SIDE FOR ULTIMATE DELIVERY												
LATER												
CO#	23.127						GH 403-1151A					
	811S06140	1	1		96		240	6534	56100	80800	8	24
									60100	80400	8	26
B55205904												
	811S06140	1	1		96		240	6534	56100	80800	8	24
									60100	80400	8	26
B55206001												
	811S06140	1	1		96		240	6534	56100	80800	8	24
									60100	80400	8	26
B55206003												

HIA 85731, 85732

Q-QUENCH TEMPERATURE	T-TEMPER TEMPERATURE	N-NORMALIZE TEMPERATURE
----------------------	----------------------	-------------------------

S E R I A L N O.	P A T T E R N N O.	H E A T N O.	H A R D B H N	B E N D	T H I C K N E S S I N C H E S	T Y P E	S I Z E	D I R	T E M P E R E	C H A R P Y I M P A C T								
										E N E R G Y F T L B S			S H E A R (%)			L A T. E X P		
										1	2	3	1	2	3	1	2	3

H E A T N O.	C H E M I C A L A N A L Y S I S																M Q U I D G R A I N S I Z E
	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	V	Ti	Al	B	Cb	N	Sn	

811S06140 .18 1.20 .013 .003 .273.018 .01 .02.005.055.002.030.0002 .002.003.003



HT# 811S06140

I certify that the above results are a true and correct copy of actual results contained in records maintained by ArcelorMittal Burns Harbor and are in full compliance with the requirements of the specification cited above. This test report cannot be altered and must be transmitted intact with any subsequent third party test reports, if required.

**R. SPANGLER II PER LSS**

BHPLTRPT.TIF SUPV. QUALITY ASSURANCE

Base Plate

TR No. 609591-03

81

2018-09-27



**MILL TEST CERTIFICATE**

A0H 85647

1700 HOLT RD N.E.  
Tuscaloosa, AL 35404-1000  
800 800-8204  
customerservice@nucortusk.com

Load Number	Tally	Mill Order Number	PO NO   Line NO	Part Number	Certificate Number	Prepared
R152486	00000000724815	N-154733-001	V10881Q217 01		S72481501-1	04/30/2017 16:58

<b>Grade</b>	<b>Customer:</b>
<b>Order Description:</b> Hot Roll Plate From Coil A36, 0.2500 IN x 96.000 IN x 480.000 IN <b>Quality Plan Description:</b> A36MODMN-TRIPLE: ASTM A36-14/A709-36-15/ASME SA36-13 MOD MN	<b>Sold TO:</b> LEECO STEEL LLC Lisle IL <b>Ship TO:</b> LEECO STEEL LLC Hudson TX <b>Sent TO:</b>

Shipped Item	Certified By	Heat Number	Yield ksi	Tensile ksi	Y/T %	ELONGATION %		Bend OK?	Hard HB	Charpy Impacts (ft-lbs)				Shear %				Test Temp	
						2"	8"			Size mm	1	2	3	Avg	1	2	3		Avg
7D3213F	S7D3213MTT	B7Q4224 ***	49.4	65.5	75.4	31.1													

Items: 10 PCS: 50 Weight: 163353 LBS

Mercury has not come in contact with this product during the manufacturing process nor has any mercury been used by the manufacturing process. Certified in accordance with EN 10204 3.1. No weld repair has been performed on this material. Material conforms to NACE MR0175 Annex 2.1.2. Manufactured to a fully killed fine grain practice. NUTEMPER TEMPER PASSED plate from coil ISO 9001:2015 Registered, PED Certified

We hereby certify that the product described above passed all of the tests required by the specifications.

*Quilin Yu*  
Dr. Quilin Yu - Metallurgist

\*\*\* indicates Heats melted and Manufactured in the U.S.A.



MILL TEST CERTIFICATE

AOH 85647

1700 HOLT RD N.E.  
Tuscaloosa, AL 35404-1000  
800 800-8204  
customerservice@nucortusk.com

Load Number	Tally	Mill Order Number	PO NO   Line NO	Part Number	Certificate Number	Prepared
R152486	00000000724815	N-154733-001	V10881Q217 01		S72481501-1	04/30/2017 16:58
Grade				Customer:		
Order Description: Hot Roll Plate From Coil A36, 0.2500 IN x 96.000 IN x 480.000 IN Quality Plan Description: A36MODMN-TRIPLE: ASTM A36-14/A709-36-15/ASME SA36-13 MOD MN				Sold TO: LEEEO STEEL LLC Lisle IL Ship TO: LEEEO STEEL LLC Hudson TX Sent TO:		

Anchor Plate

Shipped Item	Heat/Slab Number	Certified By	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Cb	V	Al	Ti	N2	B	Ca	Sn	CEV	ACI
7D3212B	B7Q4224-02 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	
7D3212C	B7Q4224-02 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	
7D3212D	B7Q4224-02 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	
7D3212E	B7Q4224-02 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	
7D3212F	B7Q4224-02 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	
7D3213B	B7Q4224-01 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	
7D3213C	B7Q4224-01 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	
7D3213D	B7Q4224-01 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	
7D3213E	B7Q4224-01 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	
7D3213F	B7Q4224-01 ***	B7Q4224	0.18	0.84	0.013	0.006	0.06	0.18	0.06	0.08	0.019	0.001	0.003	0.031	0.001	0.007	0.0001	0.0018	0.006	0.36	

HT# B7Q4224



Mercury has not come in contact with this product during the manufacturing process nor has any mercury been used by the manufacturing process. Certified in accordance with EN 10204 3.1. No weld repair has been performed on this material. Material conforms to NACE MR0175 Annex 2.1.2 Manufactured to a fully killed fine grain practice. NUTEMPER TEMPER PASSED plate from coil ISO 9001:2015 Registered, PED Certified

We hereby certify that the product described above passed all of the tests required by the specifications.

*Quilin Yu*  
Dr. Quilin Yu - Metallurgist

\*\*\*\* indicates Heats melted and Manufactured in the U.S.A.



# A0K 85022 Test Certificate

12400 Highway 43 North, Axis, Alabama 36505, US

Form TC1: Revision 2: Date 23 Apr 2014

Customer: CHAPEL STEEL CO PO BOX 1000  SPRING HOUSE PA 19477	Customer P.O.No.:HOU-8540	Mill Order No. 41-522186-03	Shipping Manifest: AR256408
	Product Description: ASTM A36(14)/A709(17)36/ASME SA36(17) AASHTO M270(15)36		Ship Date: 27 Dec 17 Cert Date: 27 Dec17
	Size: 0.375 X 120.0 X 480.0 (IN)		

Plate Washers

Tested Pieces:				Tensiles:						Charpy Impact Tests												
Heat Id	Piece Id	Piece Dimensions	Tst Loc	YS (KSI)	UTS (KSI)	%RA	Elong %		Tst Dir	Hardness	Abs. Energy(FTLB)			% Shear			Tst Tmp	Tst Dir	Tst Siz (mm)	BDWTT Tmp %Shr		
							2in	8in			1	2	3	Avg	1	2	3	Avg				
E7L229	A16	0.381 (DISCRT)	L	50	69			25	T													
M7L230	A28	0.372 (DISCRT)	L	53	68			27	T													
M7L714	D11	0.371 (DISCRT)	L	48	66			27	T													
W7L740	A17	0.380 (DISCRT)	L	49	68			25	T													
W7L741	A31	0.247 (DISCRT)	L	57	70			24	T													
W7L741	A34	0.373 (DISCRT)	L	53	67			23	T													

Heat Id	Chemical Analysis														ORGN	
	C	Mn	P	S	Si	Tot Al	Cu	Ni	Cr	Mo	Cb	V	Ti	B		N
E7L229	.19	.52	.011	.002	.14	.026	.33	.16	.13	.04	.000	.003	.014	.0001	.0079	USA
M7L230-A28	.18	.54	.007	.002	.13	.028	.26	.11	.10	.04	.001	.002	.012	.0001	.0071	USA
M7L714-D11	.17	.29	.010	.005	.18	.028	.30	.12	.11	.03	.001	.002	.020	.0001	.0082	USA
W7L740	.18	.52	.010	.001	.13	.025	.30	.15	.11	.05	.000	.003	.015	.0001	.0078	USA
W7L741	.18	.28	.008	.001	.15	.025	.26	.14	.08	.04	.001	.002	.012	.0001	.0068	USA

KILLED STEEL  
 MERCURY IS NOT A METALLURGICAL COMPONENT OF THE STEEL AND NO MERCURY WAS INTENTIONALLY ADDED DURING THE MANUFACTURE OF THIS PRODUCT.  
 MTR EN 10204:2004 INSPECTION CERTIFICATE 3.1 COMPLIANT  
 100% MELTED AND MANUFACTURED IN THE USA.  
 PRODUCTS SHIPPED:  
 W7L741            A33            PCES: 7, LBS: 42882            E7L229            A16            PCES: 1, LBS: 6126  
 W7L740            A17            PCES: 2, LBS: 12252            M7L230            A28            PCES: 6, LBS: 36756  
 M7L714            D11            PCES: 3, LBS: 18378

HT# M7L230

(P) Cust Part #:	WE HEREBY CERTIFY THAT THIS MATERIAL WAS TESTED IN ACCORDANCE WITH, AND MEETS THE REQUIREMENTS OF, THE APPROPRIATE SPECIFICATION	Justin Ward SENIOR METALLURGIST - PRODUCT
------------------	--	--

Wide Flange Beam



**GERDAU**

US-ML-MIDLOTHIAN  
300 WARD ROAD  
MIDLOTHIAN, TX 76065  
USA

**CERTIFIED MATERIAL TEST REPORT**

Page 1/1

<b>CUSTOMER SHIP TO</b> KLOECKNER METALS US SOUTH LOOP 4 BUDA, TX 78610 USA		<b>CUSTOMER BILL TO</b> KLOECKNER METALS CORPORATION 500 COLONIAL CENTER PKWY ROSWELL, GA 30076-8853 USA		<b>GRADE</b> A992/A572-50	<b>SHAPE / SIZE</b> Wide Flange Beam / 8 X 31# / 200 X 46.1	<b>DOCUMENT ID:</b> 000000000	
<b>SALES ORDER</b> 5940437/000070		<b>CUSTOMER MATERIAL N°</b> B831W601400		<b>LENGTH</b> 6000"	<b>PCS</b> 6	<b>WEIGHT</b> 11,160 LB	<b>HEAT / BATCH</b> 59077719/03
<b>CUSTOMER PURCHASE ORDER NUMBER</b> 7223194		<b>BILL OF LADING</b> 1327-0000261173		<b>DATE</b> 12/20/2017		<b>SPECIFICATION / DATE or REVISION</b> ASTM A6-14 ASTM A709-15 ASTM A992-11 (2015), A572-15 CSA G40.21-13 345WM	

<b>CHEMICAL COMPOSITION</b>	C %	Mn %	P %	S %	Si %	Cu %	Ni %	Cr %	Mo %	Sn %	V %	Nb %	Al %
	0.07	0.82	0.026	0.024	0.15	0.34	0.09	0.19	0.017	0.006	0.001	0.018	0.003

<b>CHEMICAL COMPOSITION</b>	CeqvA6 %
	0.28

<b>MECHANICAL PROPERTIES</b>	YS 0.2% PSI	UTS PSI	YS MPa	UTS MPa	Y/T ratio %	G/L Inch
	54823	72151	378	498	0.760	8.000
	56661	71943	391	496	0.790	8.000

<b>MECHANICAL PROPERTIES</b>	G/L mm	Elong. %
	200.0	25.10
	200.0	25.10

COMMENTS / NOTES

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

*Bhaskar*  
BHASKAR YALAMANCHILI  
QUALITY DIRECTOR

Phone: (409) 769-1014 Email: Bhaskar.Yalamanchili@gerdau.com

*Wade Lumpkins*  
WADE LUMPKINS  
QUALITY ASSURANCE MGR.

Phone: 972-779-3118 Email: Wade.Lumpkins@gerdau.com





CMC STEEL TEXAS  
1 STEEL MILL DRIVE  
SEGUIN TX 78155-7510

**CERTIFIED MILL TEST REPORT**  
For additional copies call  
830-372-8771

We hereby certify that the test results presented here  
are accurate and conform to the reported grade specification

*Tommy Hewitt*  
TOMMY HEWITT

**1SERIES-BPS®**

Quality Assurance Manager

HEAT NO.:3067587 SECTION: CHANNEL 3"x6.0# 40'0" A36/52950 GRADE: ASTM A36-14/A529-14 Gr50 ROLL DATE: MELT DATE: 12/03/2016 Cert. No.: 82115476 / 067587A632		S Delta Steel Inc O L 7355 Roundhouse Ln D Houston TX US 77078-4528 T 7136238080 O 7136350048	S Delta Steel Inc Houston Div H I 7355 Roundhouse Ln P Houston TX US 77078-4528 T 7136351200 O 7136350048	Delivery#: 82115476 BOL#: 72095406 CUST PO#: DHO-151547 CUST P/N: DLVRY LBS / HEAT: 9360.000 LB DLVRY PCS / HEAT: 39 EA	
Characteristic	Value	Characteristic	Value	Characteristic	Value
C	0.15%	Yield Strength test 2	53.2ksi		
Mn	0.68%	Tensile Strength test 2	75.3ksi		
P	0.023%	Elongation test 2	27%		
S	0.036%	Elongation Gage Lgth test 2	8IN		
Si	0.23%	Yield to tensile ratio test2	0.71		
Cu	0.35%				
Cr	0.15%				
Ni	0.09%				
Mo	0.027%				
V	0.013%				
Cb	0.002%				
Sn	0.012%				
Al	0.000%				
Carbon Eq A529	0.37%				
Yield Strength test 1	51.9ksi				
Tensile Strength test 1	73.1ksi				
Elongation test 1	33%				
Elongation Gage Lgth test 1	8IN				
Yield to tensile ratio test1	0.71				
<p>The Following is true of the material represented by this MTR:</p> <ul style="list-style-type: none"> <li>*Material is fully killed</li> <li>*100% milled and rolled in the USA</li> <li>*EN10204:2004 3.1 compliant</li> <li>*Contains no weld repair</li> <li>*Contains no Mercury contamination</li> <li>*Manufactured in accordance with the latest version of the plant quality manual</li> <li>*Meets the "Buy America" requirements of 23 CFR635.410</li> </ul>					

**REMARKS :**

ALSO MEETS ASTM GRADE A36, A529-50, A572-50, A709-36, A709-50, A992, AASHTO M270-36, M270-50, CSA G40.21-04 44W, 50W

06/22/2017 00:28:33

Page 1 OF 1

Certificate of Mill Test Results  
Heat No: 3067587

Page 1 of 1



**GERDAU**

US-ML-CARTERSVILLE  
384 OLD GRASSDALE ROAD NE  
CARTERSVILLE, GA 30121  
USA

**CERTIFIED MATERIAL TEST REPORT**

Page 1/1

<b>CUSTOMER SHIP TO</b> KLOECKNER METALS US SOUTH LOOP 4 BUDA, TX 78610 USA		<b>CUSTOMER BILL TO</b> KLOECKNER METALS CORPORATION 500 COLONIAL CENTER PKWY ROSWELL, GA 30076-8853 USA		<b>GRADE</b> A992/A572-50	<b>SHAPE / SIZE</b> Wide Flange Beam / 8 X 24# / 200 X 35.9	<b>DOCUMENT ID:</b> 000000000	
<b>SALES ORDER</b> 6155134/000010		<b>CUSTOMER MATERIAL N°</b> B824W401400		<b>LENGTH</b> 4000"	<b>PCS</b> 10	<b>WEIGHT</b> 9,600 LB	<b>HEAT / BATCH</b> 55053188/02
<b>CUSTOMER PURCHASE ORDER NUMBER</b> 7243904		<b>BILL OF LADING</b> 1323-0000106083		<b>DATE</b> 02/21/2018		<b>SPECIFICATION / DATE or REVISION</b> ASTM A6-17 ASTM A709-17 ASTM A992-11 (2015), A572-15 CSA G40.21-13 345WM	

<b>CHEMICAL COMPOSITION</b>											
C %	Mn %	P %	S %	Si %	Cu %	Ni %	Cr %	Mo %	Sn %	V %	Nb %
0.09	1.14	0.015	0.025	0.28	0.27	0.12	0.08	0.030	0.008	0.000	0.012

<b>MECHANICAL PROPERTIES</b>						
YS 0.2% PSI	UTS PSI	YS MPa	UTS MPa	Y/T <sub>ratio</sub> %	G/L Inch	
54200	76600	374	528	0.710	8.000	
55200	76800	381	530	0.720	8.000	

<b>MECHANICAL PROPERTIES</b>	
Elong. %	
20.80	
21.20	

**COMMENTS / NOTES**

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

*Bhaskar*

BHASKAR YALAMANCHILI  
QUALITY DIRECTOR

Phone: (409) 769-1014 Email: Bhaskar.Yalamanchili@gerdau.com

*Yan Wang*

YAN WANG  
QUALITY ASSURANCE MGR.

Phone: (770) 387 5718 Email: yan.wang@gerdau.com



CMC STEEL TEXAS  
1 STEEL MILL DRIVE  
SEGUIN TX 78155-7510

**CERTIFIED MILL TEST REPORT**  
For additional copies call  
830-372-8771

We hereby certify that the test results presented here are accurate and conform to the reported grade specification

*Tommy Hewitt*  
TOMMY HEWITT

Quality Assurance Manager

HEAT NO.:3079581 SECTION: REBAR 16MM (#5) 60'0" 420/60 GRADE: ASTM A615-16 Gr 420/60 ROLL DATE: 04/22/2018 MELT DATE: 04/22/2018 Cert. No.: 82366893 / 079581A002	S O L D T O	CMC COATING WAXAHACHIE  901 CANTRELL STREET WAXAHACHIE TX US 75165-3120 972-937-9841	S H I P T O	CMC Coatings Waxahachie  901 Cantrell St Waxahachie TX US 75165-3120 972 937 9841	Delivery#: 82366893 BOL#: 72448918 CUST PO#: CUST P/N: DLVRY LBS / HEAT: 15020.000 LE DLVRY PCS / HEAT: 240 EA
--	----------------------------	---	----------------------------	--	---

Characteristic	Value	Characteristic	Value	Characteristic	Value
C	0.41%				
Mn	0.89%				
P	0.013%				
S	0.046%				
Si	0.17%				
Cu	0.28%				
Cr	0.13%				
Ni	0.16%				
Mo	0.063%				
V	0.000%				
Cb	0.002%				
Sn	0.012%				
Al	0.001%				
Yield Strength test 1	66.4ksi				
Tensile Strength test 1	104.1ksi				
Elongation test 1	14%				
Elongation Gage Lgth test 1	8IN				
Bend Test Diameter	2.188IN				
Bend Test 1	Passed				
				The Following is true of the material represented by this MTR:  *Material is fully killed *100% milled and rolled in the USA *EN10204 2004 3.1 compliant *Contains no weld repair *Contains no Mercury contamination *Manufactured in accordance with the latest version of the plant quality manual *Meets the "Buy America" requirements of 23 CFR635 410	

REMARKS :



CMC STEEL TEXAS  
1 STEEL MILL DRIVE  
SEGUIN TX 78155-7510

**CERTIFIED MILL TEST REPORT**  
For additional copies call  
830-372-8771

We hereby certify that the test results presented here are accurate and conform to the reported grade specification

*Tommy Hewitt*  
TOMMY HEWITT

Quality Assurance Manager

HEAT NO.:3079583 SECTION: REBAR 16MM (#5) 60"0" 420/60 GRADE: ASTM A615-16 Gr 420/60 ROLL DATE: 04/22/2018 MELT DATE: 04/22/2018 Cert. No.: 82366893 / 079583A002	S O L D T O	CMC COATING WAXAHACHIE  901 CANTRELL STREET WAXAHACHIE TX US 75165-3120 972-937-9841	S H I P T O	CMC Coatings Waxahachie  901 Cantrell St Waxahachie TX US 75165-3120 972 937 9841	Delivery#: 82366893 BOL#: 72448918 CUST PO#: CUST P/N: DLVRY LBS / HEAT: 30040.000 LB DLVRY PCS / HEAT: 480 EA
--	----------------------------	---	----------------------------	--	---

Characteristic	Value	Characteristic	Value	Characteristic	Value
C	0.42%				
Mn	0.83%				
P	0.013%				
S	0.047%				
Si	0.18%				
Cu	0.29%				
Cr	0.15%				
Ni	0.20%				
Mo	0.077%				
V	0.000%				
Cb	0.003%				
Sn	0.013%				
Al	0.001%				
Yield Strength test 1	67.4ksi				
Tensile Strength test 1	101.7ksi				
Elongation test 1	14%				
Elongation Gage Lgth test 1	8IN				
Bend Test Diameter	2.188IN				
Bend Test 1	Passed				
				The Following is true of the material represented by this MTR: *Material is fully killed *100% melted and rolled in the USA *EN10204:2004 3.1 compliant *Contains no weld repair *Contains no Mercury contamination *Manufactured in accordance with the latest version of the plant quality manual *Meets the "Buy America" requirements of 23 CFR635 410	

REMARKS :



CMC STEEL TEXAS  
1 STEEL MILL DRIVE  
SEGUIN TX 78155-7510

**CERTIFIED MILL TEST REPORT**  
For additional copies call  
830-372-8771

We hereby certify that the test results presented here  
are accurate and conform to the reported grade specification

*Tommy Hewitt*  
TOMMY HEWITT

Quality Assurance Manager

HEAT NO.:3078975 SECTION: REBAR 13MM (#4) 60'0" 420/60 GRADE: ASTM A615-16 Gr 420/60 ROLL DATE: 04/05/2018 MELT DATE: 03/30/2018 Cert. No.: 82365532 / 078975A265	S O L D T O	CMC COATING WAXAHACHIE 901 CANTRELL STREET WAXAHACHIE TX US 75165-3120 972-937-9841	S H I P T O	CMC Coatings Waxahachie 901 Cantrell St Waxahachie TX US 75165-3120 972 937 9841	Delivery#: 82365532 BOL#: 72446899 CUST PO#: CUST P/N: DLVRY LBS / HEAT: 40404.000 LB DLVRY PCS / HEAT: 1008 EA
--	----------------------------	---	----------------------------	--	--

Characteristic	Value	Characteristic	Value	Characteristic	Value
C	0.42%				
Mn	0.79%				
P	0.009%				
S	0.042%				
Si	0.17%				
Cu	0.31%				
Cr	0.10%				
Ni	0.18%				
Mo	0.064%				
V	0.000%				
Cb	0.003%				
Sn	0.010%				
Al	0.002%				
Yield Strength test 1	65.8ksi				
Tensile Strength test 1	104.0ksi				
Elongation test 1	15%				
Elongation Gage Lgth test 1	8IN				
Bend Test Diameter	1.750IN				
Bend Test 1	Passed				
				<p>The Following is true of the material represented by this MTR:</p> <ul style="list-style-type: none"> <li>*Material is fully killed</li> <li>*100% melted and rolled in the USA</li> <li>*EN10204 2004 3.1 compliant</li> <li>*Contains no weld repair</li> <li>*Contains no Mercury contamination</li> <li>*Manufactured in accordance with the latest version of the plant quality manual</li> <li>*Meets the "Buy America" requirements of 23 CFR635.410</li> </ul>	

REMARKS :

# Valspar Corporation

## CERTIFICATION of COMPLIANCE

Date: 4/18/2018

Specification: ASTM A775, ASTM A1078, AASHTO M284, AASHTO M254

Valspar Product Code: 720A009 (Epoxy Powder for Coating)

Batch Number: 8496026992

Production Date: 4/17/2018 (Expiration is 6 months post production date)

Batch Size: 18,000 lbs.

I hereby certify that the above lot of material was manufactured to formulation, meeting all the requirements of the above specifications and that this material is chemically the same material that was tested by Valley Forge Laboratories of Devon, PA. or Wiss, Janney, Elstner Associates of Northbrook, IL.

The individual signing below has the legal authority to bind Valspar to the material.

Eric Gregory / DC Supervisor  
Name and Title  
Eric Gregory  
Signature  
4/18/18  
Date

10300 Claude Freeman Drive  
Charlotte, NC 28262  
Phone: (704) 548-2820  
Fax: (704) 547-0634

State/Commonwealth NC County of Cabarrus  
On this the 18<sup>th</sup> Day of April, 2018, before me Renee L. Motley,  
Name of Notary Public  
The undersigned Notary Public, personally appeared Eric Gregory  personally known to me  
Name(s) of Signer(s)



To be the person(s) whose name(s) is/are subscribed to the within instrument, and acknowledged to me that he/she/they executed the same for the purposes therein stated.

Witness my hand and official seal  
Renee L. Motley  
Signature of Notary Public

11-29-2020

Other Required Information (Printed Name of Notary, Residence, etc.)

The articles and instruments here were produced in the United States and qualify as "U.S.-made end products", "domestic construction materials" and "domestic manufactured goods"

The data on this sheet represent measured values. Since application variables are a major factor in product performance, this information should serve only as a general guide. Valspar assumes no obligation or liability for use of this information. UNLESS VALSPAR AGREES OTHERWISE IN WRITING, VALSPAR MAKES NO WARRANTIES, EXPRESS OR IMPLIED, AND DISCLAIMS ALL IMPLIED WARRANTIES INCLUDING WARRANTIES OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR FREEDOM FROM PATENT INFRINGEMENT. VALSPAR WILL NOT BE LIABLE FOR ANY SPECIAL, INCIDENTAL OR CONSEQUENTIAL DAMAGES. Your only remedy for any defect in this product is the replacement of the defective product, or a refund of its purchase price, at our option.



A Nelson Fastener Systems Company

69

7/09/18

Certificate of Compliance

CUSTOM FABRICATORS  
1379 N HARVEY MITCHELL PKWY  
BRYAN

TX  
77803

Material Description/Part Numbers	Quantity	Heat Number	Lab Number
CPL 3/4-10 X 2 1/2 MS 101017428	90	10530700	24071

Nelson Order Number: 1015428

Customer P.O.: 21486

The product supplied under the contract or purchase order number shown is certified to comply with the latest revision of one or more of the applicable product specifications therein; AWS D1.1, AWS D1.5, AWS D1.6, ISO 13918, BS 5950, ASTM A108, ASTM A29, ASTM A276, ASTM A493, ASTM A1064, ASTM A496, ASTM A479, ASTM A1022.


The chemical analysis reported below was extracted from the certified mill test report. This report will be supplied when specified in the customer order or upon request. The physical properties reported were determined to be in conformance using ASTM A370 testing procedure.

Nelson Stud Welding is an ISO/TS 16949:2009 certified supplier. Our IATF certificate # is 0222148. This material is free from mercury contamination and is RoHS compliant. This product is melted and manufactured in the USA. No weld repair was performed on the raw material or the studs. Parts are manufactured from cold drawn bar.

Grade	C-1015
Heat Number	10530700
Ultimate PSI	82,300
Yield PSI	77,400
% Reduction of Area	60.0
% Elong. (in 2"or4D)	22.0
% Elong. (in 5D)	19.000
Carbon	.160
Manganese	.550
Phosphorous	.005
Sulphur	.008

I hereby certify that the data listed in this Certificate of Compliance is true and correct as as contained in the company test records and that it complies with the specifications shown.

Authorized by:



Nelson® Stud Welding · 2211 Century Center Blvd. #105 · Irving, TX 75062  
PH: (972) 721-9055 · FAX: (972) 438-7883 · www.NelsonStud.com



**CHARTER STEEL**

A Division of Charter Manufacturing Company, Inc.

FILE

1658 Cold Springs Road  
Saukville, Wisconsin 53080  
(262) 268-2400  
1-800-437-8789  
Fax (262) 268-2570

Melted in USA Manufactured in USA

**CHARTER STEEL TEST REPORT**

**Nelson Stud Welding - A Nelson Fastener Systems Company**  
7900 West Ridge Road  
QC Department  
Elyria, OH-44035

Cust P.O.	425341
Customer Part #	103004036
Charter Sales Order	50049368
Heat #	10530700
Ship Lot #	1231181
Grade	1015 M SK FG RHQ 45/64 RNDCOIL
Process	HR
Finish Size	45/64
Ship date	17-JAN-18

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed below and that it satisfies these requirements. The recording of false, fictitious and fraudulent statements or entries on this document may be punishable as a felony under federal statute.

Lab Code: 7388

CHEM %Wt

Test results of Heat Lot # 10530700											
C	MN	P	S	SI	NI	CR	MO	CU	SN	V	
.16	.55	.005	.008	.170	.04	.08	.02	.09	.006	.002	
AL	N	B	TI	CA	NB	SB	AS				
.024	.0080	.0001	.001	.0001	.001	.002	.004				
PB											
.001											

JOMINY(HRC)

J1	J3
42	20

JOMINY SAMPLE TYPE ENGLISH=C

ROCKWELL B (HRBW)	# of Tests	Test results of Rolling Lot # 1231181		Mean Value	RB LAB = 0358-02
		Min Value	Max Value		
	1	72	72	72	

REDUCTION RATIO=78:1

Specifications: Manufactured per Charter Steel Quality Manual Rev Date 05/12/17  
Charter Steel certifies this product is indistinguishable from background radiation levels by having process radiation detectors in place to measure for the presence of radiation within our process & products.  
Meets customer specifications with any applicable Charter Steel exceptions for the following customer documents:  
Customer Document = MPS-102C Revision = G Dated = 17-OCT-16

Additional Comments: This material meets the chemistry requirements of ASTM-A108 (latest version), ASTM A29 (latest version), and EN 10025-2 S-235-J2G3

*Lab 24071*

Melt Source:  
Charter Steel  
Saukville, WI, USA

Trip: 1213927



Page 1 of 2

This MTR supersedes all previously dated MTRs for this order

*Janice Barnard*  
Janice Barnard Division Mgr. of Quality Assurance  
barnardJ@chartersteel.com  
Printed Date : 01/17/2018



The following statements are applicable to the material described on the front of this Test Report:

1. Except as noted, the steel supplied for this order was melted, rolled, and processed in the United States meeting DFARS compliance, LEEDS compliance, REACH compliance, ROHS-WEEE compliance, and Conflict Materials Restrictions.
2. Mercury was not used during the manufacture of this product, nor was the steel contaminated with mercury during processing.
3. Unless directed by the customer, there are no welds in any of the coils produced for this order.
4. The laboratory that generated the analytical or test results can be identified by the following key:

Certificate Number	Lab Code	Laboratory	Address
0358-01	7388	CSSM Charter Steel Melting Division	1658 Cold Springs Road, Saukville, WI 53080
0358-02	8171	CSSR/CSSP Charter Steel Rolling/ Processing Division	1658 Cold Springs Road, Saukville, WI 53080
0358-03	123633	CSFP Charter Steel Ohio Processing Division	6255 US Highway 23, Rising Sun, OH 43457
0358-04	125544	CSCM/CSCR Charter Steel Cleveland	4300 E. 49th St., Cuyahoga Heights, OH 44125-1004
*	*	--	Subcontracted test performed by laboratory not in Charter Steel System

5. When run by a Charter Steel laboratory, the following tests were performed according to the latest revisions of the specifications listed below, as noted in the Charter Steel Laboratory Quality Manual:

Test	Specifications	CSSM	CSSR/CSSP	CSFP	CSCM/CSCR
Chemistry Analysis	ASTM E415; ASTM E1019	X			X
Macroetch	ASTM E381	X			X
Hardenability (Jominy)	ASTM A255; SAE J406; JIS G0561	X			X
Grain Size	ASTM E112	X	X	X	X
Tensile Test	ASTM E8; ASTM A370		X	X	X
Rockwell Hardness	ASTM E18; ASTM A370	X	X	X	X
Microstructure (spheroidization)	ASTM A892		X	X	
Inclusion Content (Methods A, E)	ASTM E45		X		X
Decarburization	ASTM E1077		X	X	X

Charter Steel has been accredited to perform all of the above tests by the American Association for Laboratory Accreditation (A2LA). These accreditations expire 01/31/19. All other test results associated with a Charter Steel laboratory that appear on the front of this report, if any, were performed according to documented procedures developed by Charter Steel and are not accredited by A2LA.

6. The test results on the front of this report are the true values measured on the samples taken from the production lot. They do not apply to any other sample.
7. This test report cannot be reproduced or distributed except in full without the written permission of Charter Steel. The primary customer whose name and address appear on the front of this form may reproduce this test report subject to the following restrictions:
  - It may be distributed only to their customers
  - Both sides of all pages must be reproduced in full
8. This certification is given subject to the terms and conditions of sale provided in Charter Steel's acknowledgement (designated by our Sales Order number) to the customer's purchase order. Both order numbers appear on the front page of this Report.
9. Where the customer has provided a specification, the results on the front of this test report conform to that specification unless otherwise noted on this test report.



HANGZHOU SPRING WASHER CO.,LTD  
 QUALITY TEST CERTIFICATE OF SPRING LOCK WASHER

Standard: ASME B 18.21.1-2009 Contract No.: 14HZW11585/12650  
 Order No.: PO U23775 Invoice No.: 15SHD052

Chemical Composition (%)	C	Si	Mn	P	S	Cr	Ni	Cu
	0.65	0.2	0.55	0.01	0.004	0.02	0.02	0.03
Material Type.	65#			Heat No.		T490009102		
Specification	REGULAR HELICAL LOCK WASHER 3/4" HDG							
Quantity	162 M				COUNTRY OF ORIGIN:CHINA			
Lot No.	1412295							
Part No.	350006							
Testing Item	Ac/n	Norm	Result	Reject	Norm	Result	Reject	
Inside Diameter	2/100	19.33-19.86	19.6-19.86	0				
Outside Diameter	1/32	Max32.93	Max32.27	0				
Width	1/32	Min6.04	Min6.04	0				
Thickness	1/32	4.88-5.33	5.18-5.31	0				
Height								
Section								
Surface Defects	2/100	None	None	0				
Hardness	0/8	HRC38-46	HRC44-45	0				
Springing								
Toughness	0/8	Qualified	Qualified	0				
Zinc Coating	0/8	Min53um	Min61.6um	0				
Zinc Coating Standard of:								
Customer Name:		BRIGHTON BEST INTERNATIONAL (TAIWAN) INC.						
General:		The spring lock washers are conformed with the standard of ASME B 18.21.1-2009. QUALIFIED.						

Inspector: Shiweiqing

Quality Inspection  
 Chief:

Date 2015.02.28

**Certified Material Test Report to BS EN 10204-2004 3.1  
 FOR ASME SA194/ ASTM A194-14 GRADE 2H HVY HEX NUTS**

FACTORY: NINGBO HAIXIN HARDWARE CO.,LTD. DATE: APR.30.2016  
 ADDRESS: XIJINGTANG,LUOTUO NINGBO ZHEJIANG 315205 COUNTRY OF ORIGIN: CHINA  
CHINA MFG LOT NUMBER: 5106740003  
 CUSTOMER: BRIGHTON-BEST INTERNATIONAL (TAIWAN) INC PO NUMBER: MILL  
 QNTY SHIPPED: 153.000MPCS PART NO: 313200  
 SAMPLE SIZE: ACC. TO ASME B18.18.1-11 MANUFACTURER DATE: 2016/3/28  
 SIZE & DESCRIPTION 3/4-10+0.020"(HDG)  
 FINISH: H. T. HOT DIP GAL PER ASTM A153-09/ASTM F2329-13

STEEL PROPERTIES:  
 STEEL GRADE: SWRCH45K SIZE: 30mm HEAT NO: 331508880

CHEMISTRY COMPOSITION:

CHEMIST	C %	Mn %	P %	S %	Si %	Cr %	Ni %	Cu %	Mo %	OTHERS
SPE:	MIN	MAX	MAX	MAX	MAX					
	0.40	1.00	0.04	0.05	0.40					
TEST:	0.44	0.7	0.012	0.003	0.18					

DIMENSIONAL INSPECTIONS SPECIFICATION: ASME/ANSI B18.2.2-2010

CHARACTERISTICS	TEST METHOD	SPECIFIED	ACTUAL RESULT	ACC.	REJ.
APPEARANCE	ASTM F812-12		PASSED	100	0
WIDTH A/F	1.212"-1.250"		1.232"-1.249"	32	0
WIDTH A/C	1.382"-1.443"		1.392"-1.434"	32	0
THREAD	ASME B1.1-03		PASSED	8	0
HEIGHT	0.710"-0.758"		0.735"-0.752"	32	0
MARK	2HZN LM		PASSED	100	0
HDG THICKNESS	ASTM A153-09/ASTM F2329-13 min:43um		70UM-82UM	20	0

MECHANICAL PROPERTIES: TO 1-1/2" in SPECIFICATION: ASME SA194/ ASTM A194-14

CHARACTERISTICS	TEST METHOD	SPECIFIED	ACTUAL RESULT	ACC.	REJ.
HARDNESS	ASTM E18-12	24-35HRC	HRC29-30	5	0
PROOF LOAD	ASTM F606-11	MIN58450LBF	58450LBF	5	0
HARDNESS AFTER 24H AT 540°C	ASTM A194 MIN 89 HRB		HRB 96-98	5	0
TEMPERING TEMPERATURE	Min455°C		PASSED(520°C)		
MACROETCH	ASTM E381-12	S1/R1/C1~S4/R4/C4	S2/R2/C2	5	0

PARTS ARE MANUFACTURED AND TESTED IN ACCORDANCE WITH ASME SA194/ ASTM A194-14  
 ALL TESTS IN ACCORDANCE WITH THE METHODS PRESCRIBED SPECIFICATION. WE CERTIFY  
 THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL  
 SUPPLIER AND OUR TESTING LABORATORY.

All parts meet the requirements of FQA and records of compliance are on file.  
 Maker's ISO#00109Q211593R0M/3302





## Certificate of Compliance

CUSTOMER: CUSTOM FAB  
 CUSTOMER PO #: QUADTEX 21486  
 MADDEN BOLT SO#: 103681

BOLTS: F1554 GR 105  
 HEX NUTS: A194  
 FLAT F436  
 WASHER: \_\_\_\_\_  
 LOCK \_\_\_\_\_  
 WASHER: \_\_\_\_\_  
 COATING: A153  
 TEMPLATE: \_\_\_\_\_  
 OTHER: \_\_\_\_\_

NOTES:

\_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Madden Bolt certifies that the above material is in compliance with the chemical and physical requirements of the ASTM or AISI specifications.

Thank you,

Authorized Signature: \_\_\_\_\_  
 James Dagen

Date: April 11, 2018

13420 Hempstead HWY ● Houston, TX 77040 ● PH (713) 939-9999 ● FAX (713) 9397200

WWW.MADDENBOLT.COM



April 11, 2018  
Madden Bolt Corporation  
13420 Hempstead Hwy.  
Houston, TX 77040

**RE: Galvanization Certificate of Compliance**

To Whom It May Concern:

We certify that our Hot Dip process meets the requirements of ASTM A153 Specification on the following order.

**CUSTOMER:** CUSTOM FAB.

**SALES ORDER:** 103681

**PURCHASE ORDER:** QUADTEX 21486


Approved By: \_\_\_\_\_

A handwritten signature in black ink, appearing to read 'Roger Trejo', written over a horizontal line.

Roger Trejo

13420 Hempstead HWY ● Houston, TX 77040 ● PH (713) 939-9999 ● FAX (713) 9397200

WWW.MADDENBOLT.COM



 <p>Vulcan Threaded Products 10 Cross Creek Trail Pelham, AL 35124 Tel (205) 620-5100 Fax (205) 620-5150</p>	<b>JOB MATERIAL CERTIFICATION</b>																								
	<p><b>Job No:</b> 567407</p> <p><b>Containers:</b> S13658914</p> <p><b>Customer:</b> Madden Bolt Corp</p> <p><b>Vulcan Part No:</b> HRB B7 1.152x290 GR105</p> <p><b>Customer Part No:</b> HRB B7 1.152x290 GR105</p> <p><b>Customer PO No:</b> PE57890</p> <p><b>Order No:</b> 341568</p> <p><b>Note:</b></p>	<p><b>Job Information</b></p> <p><b>Certified Date:</b> 3/22/18</p> <p><b>Ship To:</b> 13420 Hempstead Hwy Houston, TX 77040</p> <p><b>Shipped Qty:</b> 4456 lbs</p> <p><b>Line No:</b> 3</p>																							
<b>Applicable Specifications</b>																									
<table border="1"> <thead> <tr> <th>Type</th> <th>Specification</th> <th>Rev</th> <th>Amend</th> <th>Option</th> </tr> </thead> <tbody> <tr> <td rowspan="2">Heat Treat</td> <td>ASTM F1554 Gd 105 S4</td> <td>2015</td> <td></td> <td></td> </tr> <tr> <td>ASME SA-193/SA-193M B7</td> <td>2013</td> <td></td> <td></td> </tr> <tr> <td rowspan="2">Quality</td> <td>ASTM A193 B7</td> <td>2016</td> <td></td> <td></td> </tr> <tr> <td>EN 10204 3.1</td> <td>2004</td> <td></td> <td></td> </tr> </tbody> </table>	Type	Specification	Rev	Amend	Option	Heat Treat	ASTM F1554 Gd 105 S4	2015			ASME SA-193/SA-193M B7	2013			Quality	ASTM A193 B7	2016			EN 10204 3.1	2004				
Type	Specification	Rev	Amend	Option																					
Heat Treat	ASTM F1554 Gd 105 S4	2015																							
	ASME SA-193/SA-193M B7	2013																							
Quality	ASTM A193 B7	2016																							
	EN 10204 3.1	2004																							
<b>Test Results</b>																									
See following pages for tests																									
<b>Certified Chemical Analysis</b>																									
Heat No: A181012 Lot: 1.152						Origin: USA																			
C	Mn	P	S	Si	Cr	Mo	Ni	V	Cu	Al															
0.400	0.77	0.012	0.022	0.28	0.90	0.16	0.13	0.003	0.21	0.025															
Sn	Ti	N	B	Ca	As	Sb	H, ppm	DI	RR	G.S.															
0.009	0.001	0.0072	0.0002	0.0007	0.005	0.003	1.4	4.50	139.3:1	8															
Macro S	Macro R	Macro C	J1	J2	J3	J4	J5	J6	J7	J8															
1	1	2	56	56	56	56	56	53	52	50															
J9	J10	J12	J14	J16	J18	J20	J24	J28	J32																
49	47	44	42	40	38	37	36	33	32																
<b>Notes</b>																									
<p>Material was manufactured, tested and inspected in accordance with Vulcan Threaded Products Inc. Quality Assurance Program and Manual Rev. A, dated 8/23/11. Processed material is Quenched and Tempered - Stress Free. No weld repair performed on the material. No Mercury used in the production of this material. Melted and Manufactured in the USA.</p> <p>Document is in accordance with EN 10204 - 3.1B of 2004 (3.1).</p>																									

Plex 3/22/18 2:13 PM vulc.mgri Page 1 of 2

PE57890  
A181012  
Vulcan  
1.152x24  
3  
B7

**REVIEWED**  
4/10/18

[https://www.plexonline.com/072e42ca-71e0-4cae-824c-4281b4d93dde/Sales/Report\\_Job\\_Cert.asp?Mode=...](https://www.plexonline.com/072e42ca-71e0-4cae-824c-4281b4d93dde/Sales/Report_Job_Cert.asp?Mode=...) 4/6/2018

	Vulcan Threaded Products 10 Cross Creek Trail Pelham, AL 35124 Tel (205) 620-5100 Fax (205) 620-5150		<b>JOB MATERIAL CERTIFICATION</b>							
	<b>Job No:</b> 567407		<b>Job Information</b>		<b>Certified Date:</b> 3/22/18					
<b>Containers:</b> S13658914										
<b>Test Results</b>										
<b>Part No:</b> HRB B7 1.152x290 GR105										
<b>Test No: 47483 Test: Quench &amp; Temper Information (Lbs)</b>										
<b>Description</b>	<b>Austenitizing Temp (F)</b>	<b>Tempering Temp (F)</b>	<b>Run Speed (Ft/min)</b>	<b>Quench Water Temp (F)</b>	<b>Note</b>					
	1,712	1,326	19.5	89						
<b>Test No: 47491 Test: F1554-105 FB Requirements</b>										
<b>Description</b>	<b>Tensile (ksi)</b>	<b>Yield 0.2% Offset (ksi)</b>	<b>Elongation (%)</b>	<b>Elongation Gage Length (8in)</b>	<b>ROA (%)</b>	<b>Note</b>				
	131	118	17	8in	61					
<b>Test No: 47489 Test: A193 B7, F1554-105 Requirements</b>										
<b>Description</b>	<b>Tensile (ksi)</b>	<b>Yield 0.2% Offset (ksi)</b>	<b>Elongation (%)</b>	<b>Elongation Gage Length</b>	<b>ROA (%)</b>	<b>Midradius Hardness</b>	<b>Surface Hardness</b>	<b>Center Hardness</b>	<b>Hardness Test Type</b>	<b>Note</b>
	134	119	22	4D	64	29	28		HRC	
	135	119	21	4D	66	28	27		HRC	
	134	119	21	4D	65	28	27		HRC	
	135	121	21	4D	63	29	28		HRC	
<b>Test No: 47490 Test: F1554-15 gd105 S4 Charpy ft/lbs Requirements</b>										
<b>Description</b>	<b>Container</b>	<b>Test Temp (F)</b>	<b>Test1 (ft/lbs)</b>	<b>Test2 (ft/lbs)</b>	<b>Test3 (ft/lbs)</b>	<b>Results Avg (ft/lbs)</b>	<b>Note</b>			
		-20	95	95	93	94				
						 Griffin, Mitchell - Certification Engineer	3/22/18 Date			

Plex 3/22/18 2:13 PM vulc.mgri Page 2 of 2

[https://www.plexonline.com/072e42ca-71e0-4cae-824c-4281b4d93dde/Sales/Report\\_Job\\_Cert.asp?Mode=...](https://www.plexonline.com/072e42ca-71e0-4cae-824c-4281b4d93dde/Sales/Report_Job_Cert.asp?Mode=...) 4/6/2018

**Purchaser:** BRIGHTON-BEST INTERNATIONAL (TAIWAN),INC. **Date:** 2017-5-16  
**P.O.NO:** PO B17020241/U42733 **ISO NO:** 15/17Q5611R30  
**INV NO:** 217ZL046L **Expire:** 14-Sep-18  
**Manufacturer:** ZHEJIANG GUORUI CO.,LTD.  
**Address:** No.283 Chengxi North Road,Wuyuan Town,Haiyan Zhejiang,P.R.China  
**Commodity:** F436 HARD ROUND STRUCTURAL FLAT WASHER **CUSTOMER PART NO.:** 355120  
**Size:** 1-1/8 X 2-1/4 **MANUFACTURING DATE:** 2017.3.15  
**Lot NO.:** 217L0321-19 **HEAT NO.:** H17000150  
**Ship quantity:** 43.200 **MPCS** **MATERIAL:** 45# CARBON STEEL  
**Finish:** PLN

**DIMENSIONAL INSPECTION ACCORDING TO: ASTM F436-11**

INSPECTION ITEM	SAMPLE SIZE	SPECIFIED	ACTUAL RESULT	ACCEPT	REJECT
Appearance	100	ASTM F436-11	OK	100	0
Marking	100	F436 AND JLX	OK	100	0
Outside Dia	8	2.313-2.187	2.200-2.199	8	0
Inside Dia	8	1.251-1.188	1.238-1.236	8	0
Thickness	8	0.177-0.136	0.142-0.140	8	0

**CHEMICAL COMPOSITION ACCORDING TO: ASTM F436-11**

CHEMICAL ELEMENT (%)	C	Mn	P	S	Si	Cr	Mo	Ni	Al	Ti	V
SPECIFIED			0.040 MAX	0.050 MAX							
TEST RESULT	0.46	0.59	0.019	0.004	0.22	0.044	0.003	0.015			

**MECHANICAL PROPERTIES ACCORDING TO: ASTM F436-11**

TEST ITEM	SAMPLE SIZE	SPECIFIED	ACTUAL RESULT	ACCEPT	REJECT
HARDNESS(HRC)	8	38-45	40-42	8	0

WE CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL SUPPLIER AND OUR TESTING LABORATORY

Madden Bolt Receiving Wash	
PO #: PES7759	LN #: 6
Heat #: H17000150	
Lot #: 217L0321-19	
Supplier: BRIGHTON BEST	
Size: 1 1/8	Grade: F436

SIGNATURE: HEMING TITLE: QC MANAGER

REVIEWED  
2/14/18



**Certified Material Test Report to BS EN 10204-2004 3.1  
 FOR ASME SA194/ ASTM A194-14 GRADE 2H HVY HEX NUTS**

FACTORY NINGBO HAIXIN HARDWARE CO.,LTD. DATE: MAR.10.2016  
 ADDRESS XIJIANGTANGLUOTUO NINGBO ZHEJIANG 315205 CHINA COUNTRY OF ORIGIN: CHINA  
 MFG LOT NUMBER: 5105830005  
 CUSTOMER BRIGHTON-BEST INTERNATIONAL (TAIWAN) INC PO NUMBER: MILL  
 QNTY SHIPPED: 2,160MPCS PART NO: 313370  
 SAMPLE SIZE: ACC. TO ASME B18.18.1-11 MANUFACTURER DATE: 2016/2/25  
 SIZE & DESCRIPTION 1.1/8-7+0.024"(HDG)  
 FINISH: H.T.HOT DIP GAL PER ASTM A153-09/ASTM F2329-13

STEEL PROPERTIES:  
 STEEL GRADE: 45# SIZE: 32mm HEAT NO: C5090582

CHEMISTRY COMPOSITION:

CHEMIST	C %	Mn %	P %	S %	Si %	Cr %	Ni %	Cu %	Mo %	OTHERS
SPE:	MIN	MAX	MAX	MAX	MAX					
	0.40	1.00	0.04	0.05	0.40					
TEST:	0.45	0.58	0.017	0.007	0.24					

DIMENSIONAL INSPECTIONS SPECIFICATION: ASME/ANSI B18.2.2-2010

CHARACTERISTICS	TEST METHOD	SPECIFIED	ACTUAL RESULT	ACC.	REJ.
APPEARANCE	ASTM F812-12		PASSED	100	0
WIDTH A/F		1.756"-1.812"	1.763"-1.779"	32	0
WIDTH A/C		2.002"-2.093"	2.012"-2.075"	32	0
THREAD	ASME B1.1-03		PASSED	8	0
HEIGHT		1.079"-1.139"	1.089"-1.129"	32	0
MARK	2HZN LM		PASSED	100	0
HDG THICKNISS	ASTM A153-09/ASTM F2329-13 min:43um		58UM-66UM	20	0

MECHANICAL PROPERTIES: TO 1-1/2" in SPECIFICATION: ASTM/ASME A194/SA194-14

CHARACTERISTICS	TEST METHOD	SPECIFIED	ACTUAL RESULT	ACC.	REJ.
HARDNESS	ASTM E18-12	24-35HRC	HRC29-30	5	0
PROOF LOAD	ASTM F606-11	MIN133525LBF	133525LBF	5	0
HARDNESS AFTER 24H AT 540°C	ASTM A194 MIN 89 HRB		HRB 92-93	5	0
TEMPERING TEMPERATURE	Min455°C		PASSED(520°C)		
MACROETCH	ASTM E381-12	S1/R1/C1-S4/R4/C	S2/R2/C2	5	0

PARTS ARE MANUFACTURED AND TESTED IN ACCORDANCE WITH ASTM/ASME A194/SA194-14  
 ALL TESTS IN ACCORDANCE WITH THE METHODS PRESCRIBED SPECIFICATION. WE CERTIFY  
 THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL  
 SUPPLIER AND OUR TESTING LABORATORY.

All parts meet the requirements of FQA and records of compliance are on file.  
 Maker's ISO#00109Q211593R0M/3302

Brighton Best Receiving IN	
PO #: PE57791	Lot #: 2
Heat #: C5090582	
Lot #: 5105830005	
Supplier: Brighton Best	
Size: 1/8"	Grade: A194-2H

(SIGNATURE OF STA. MGR.)  
 (NAME OF MANUFACTURER)

REVIEWED  
 2/20/18

TR No. 609591-03

102

2018-09-27



CMC STEEL TEXAS  
1 STEEL MILL DRIVE  
SEGUIN TX 78155-7510

CERTIFIED MILL TEST REPORT  
For additional copies call  
830-372-8771

We hereby certify that the test results presented here  
are accurate and conform to the reported grade specification

*Tommy Hewitt*  
TOMMY HEWITT

Quality Assurance Manager

1SERIES-BPS®

HEAT NO.:3077684 SECTION: ROUND 1.150 x 20'0" A36/52950 GRADE: ASTM A36-14/A529-14 Gr 50 ROLL DATE: 02/15/2018 MELT DATE: 02/08/2018 Cert. No.: 82330672 / 077684A738	S O L D US T O	Madden Bolt Corp 13420 Hempstead Rd Houston TX US 77040-5813 7139399999 7139397200	S H I P US T O	Madden Bolt Corp 13420 Hempstead Rd Houston TX US 77040-5813 7139399999 7139397200	Delivery#: 82330672 BOL#: 72394800 CUST PO#: PE57851 CUST P/N: DLVRY LBS / HEAT: 4450.000 LB DLVRY PCS / HEAT: 63 EA
--	----------------------------------	---	----------------------------------	---	---

Characteristic	Value	Characteristic	Value	Characteristic	Value
C	0.18%	Reduction of Area test 1	56%		
Mn	0.82%	Yield to tensile ratio test1	0.69		
P	0.009%	Yield Strength test 2	53.6ksi		
S	0.024%	Tensile Strength test 2	77.5ksi		
Si	0.18%	Elongation test 2	47%		
Cu	0.26%	Elongation Gage Lgth test 2	2IN		
Cr	0.09%	Reduction of Area test 2	53%		
Ni	0.08%	Yield to tensile ratio test2	0.69		
Mo	0.024%				
V	0.015%				
Cb	0.002%				
Sn	0.009%				
Al	0.002%				
Carbon Eq F1554	0.33%				
Carbon Eq A529	0.40%				
Yield Strength test 1	53.9ksi				
Tensile Strength test 1	77.9ksi				
Elongation test 1	25%				
Elongation Gage Lgth test 1	8IN				

PE57851 5  
3077684  
CMC  
1.150 x 20 : A36

The Following is true of the material represented by this MTR:  
 \*Material is fully killed  
 \*100% melted and rolled in the USA  
 \*EN10204:2004 3.1 compliant  
 \*Contains no weld repair  
 \*Contains no Mercury contamination  
 \*Manufactured in accordance with the latest version of the plant quality manual  
 \*Meets the "Buy America" requirements of 23 CFR635.41D

REMARKS :

ALSO MEETS ASTM GRADE A36, A529-50, A572-50, A709-36, A709-50, A992, AASHTO M270-36, M270-50, CSA G40.21-04 44W, 50W

03/07/2018 22:59:36  
Page 1 OF 1

*JJ* 3/9/18



MAQUILACERO, S.A. DE C.V.  
 Av. Adolfo López Mateos 1220, Col. Margarita Róz Salazar, San Nicolas de Los Garza, N.L.  
 Codigo Postal / Postal Code: 66479 Telefono / Phone number: +52(81)8158-0300  
 www.maquilacero.com

CERTIFICADO DE CALIDAD - MILL TEST CERTIFICATE


Fecha de emision / (Date of invoice)  
 (M/A) 26-08 2017 14:47  
 No. / (Document number)

Codigo de cliente / (Customer ID) Cliente / (Customer) ONE0025 TRIPLE-S STEEL SUPPLY	Factura / (Invoice Num.) FAC/ 65261
Direccion / (Address) 6000 JENSEN DRIVE HOUSTON TX 77026 95-713-697-7105 Estados	Pedido / (Sales Order) 700004977
Destinatario / (Consigned to) TRIPLE-S STEEL SUPPLY 8411 IRVINGTON HOUSTON TX 77022 Estados Unidos	Orden de compra / (Purchase Order) HOU-177126

Datos generales / (General Data)

Part (Item)	Descripcion / (Description)	Cantidad Quantity	UND	No. Lote (Lot Number)	Colada (Heat)	ASTM	Composicion quimica (Chemical composition)				Prueba de tension (Tensile test)			
							C	Mn	P	S	Cedencia (Yield strength) ksi	Resistencia a la Tension (Tensile Strength) ksi	%Elong.	Dureza (Rockwell B Hardness)
PRE1501500740N	PTR1.50x1.50,C-3/16,40" WELDED SQUARE TUBING NON ALLOY" STEEL 1.5" X 1.5" 3/16 GA 4	14.4000	CFT		1730631	A-500 GRADE B & C	0.083	0.390	0.007	0.002	60.0000	64.0000	24.0000	75.0000
PRE40030031240N	PTR4x3C-5/16 ,40" WELDED SQUARE TUBING NON ALLOY" STEEL 4" X 3" 5/16 GA, 40"	6.4000	CFT	PT1222	1711482	A-500 GRADE B & C	0.082	0.420	0.018	0.002	70.0000	79.0000	25.0000	74.0000

Certificamos que el material descrito satisface las especificaciones requeridas. La composicion quimica son transcripcion de los certificados del Proveedor de acero.  
 We certify that the above described material satisfies the required specifications. The chemical composition is transcription from the mill test certificate of the steel supplier.  
 NOTE: NINGUN PRODUCTO HA SIDO PRORADO HIDROSTATICAMENTE. NONE OF THIS PRODUCTS HAVE BEEN HYDROSTATICALLY TESTED. NO WELD REPAIR WAS MADE IN ALL THIS ITEMS.

  
 Firma / (Signature)  
 Calidad / (Quality)

**MAQUILACERO, S. A. DE C. V.**  
**AV. ADOLFO LOPEZ MATEOS No. 1220**  
**R.F.C. MAQ-860203-MX5**

**Sold By:**  
**INDEPENDENCE TUBE CORPORATION**  
6226 W. 74th St.  
Chicago, IL 60638  
Tel: 708-496-0380  
Fax: 708-563-1950

Purchase Order No: 7253396  
Sales Order No: CHI 280303 - 13  
Bill of Lading No: CHI 167448 - 3  
Invoice No:

Shipped: 3/20/2018  
Invoiced:

**Sold To:**  
**1430 - KLOECKNER METALS CORPORATION**  
500 COLONIAL PARKWAY  
SUITE 500  
ROSWELL, GA 30076

**Ship To:**  
**4 - KLOECKNER METALS-NORTH**  
14806 W RIDGE LANE  
563-583-7329  
DUBUQUE, IA 52003

**CERTIFICATE of ANALYSIS and TESTS**

Certificate No: CHI 743245

Customer Part No:

Test Date: 3/19/2018

**TUBING A500 GRADE B(C)**  
5" X 4" X 3/8" X 30'

Total Pieces    Total Weight  
4                    2,378

Bundle Tag	Mill	Heat	Specs	Y/T Ratio	Pieces	Weight
4680	4N	281552	YLD=67405/TEN=73366/ELG=27.66	0.9187	4	2,378

Mill #: 4N Heat #: 281552 Carbon Eq: 0.3098 Heat Src Origin: MELTED AND MANUFACTURED IN THE USA

C	Mn	P	S	Si	Al	Cu	Cr	Mo	V	Ni	Nb	Cb
0.2000	0.5300	0.0090	0.0050	0.0200	0.0370	0.0940	0.0460	0.0150	0.0020	0.0390	0.0020	0.0020

Sn	N	B	Ti	Sb	O	H
0.0040	0.0070	0.0000	0.0030	0.0010	0.0000	0.0000

LEED Information (based on the most recent LEED information from the producing mill)

Method	Location	Recycled Content	Post Consumer	Post Industrial
EAF	Crawfordsville, IN	81.1%	28.2%	52.9%

Certification:

I certify that the above results are a true and correct copy of records prepared and maintained by Independence Tube Corporation. Sworn this day, 3/19/2018

WE PROUDLY MANUFACTURE ALL OUR PRODUCT IN THE USA. INDEPENDENCE TUBE PRODUCT IS MANUFACTURED, TESTED, AND INSPECTED IN ACCORDANCE WITH ASTM STANDARDS. MATERIAL IDENTIFIED AS A500 GRADE B(C) MEETS BOTH ASTM A500 GRADE B AND A500 GRADE C SPECIFICATIONS.



Chris Allen, ASQ CMQ/OE  
Quality Systems Supervisor

CURRENT STANDARDS:  
A252-10  
A500/A500M-13  
A513-13  
ASTM A53/A53M-12 | ASME SA-53/SA-53M-13  
A847/A847M-14  
A1085/A1085M-15



Vulcan Threaded Products  
 10 Cross Creek Trail  
 Pelham, AL 35124  
 Tel (205) 620-5100  
 Fax (205) 620-5150

## Material Certification

Customer: **Triple-S Steel**  
 Ship To: **Houston**  
 Customer PO No: **HOU-178081**  
 Vulcan Order No: **332140**  
 Order Line: **7**  
 Shipped Qty: **4228**  
 Vulcan Part No: **CDR 1018 .375x240 DOM**  
 Customer Part No: **CDR 1018 .375x240 DOM**  
 Customer Part Description:  
 Reference No:  
 Country of Origin: **USA**  
 Rolled Mill: **Gerdau Ameristeel - Beaumont, TX**  
 Melted Mill: **Gerdau Ameristeel - Beaumont, TX**  
 Grade: **1018**  
 Heat: **53147048/03**  
 Note: **7/16**  
 Spec No: **AISI 1018**  
 Spec Note:  
 Spec No: **ASTM A108-13**  
 Spec Note:

Material Specification Type	Material Specification	Actual
Chemistry	Carbon (C)	0.1640 %
	Manganese (Mn)	0.62 %
	Phosphorus (P)	0.011 %
	Sulfur (S)	0.014 %
	Silicon (Si)	0.22 %
	Copper (Cu)	0.20 %
	Nickel (Ni)	0.08 %
	Chromium (Cr)	0.10 %
	Molybdenum (Mo)	0.019 %
	Tin (Sn)	0.008 %
	Nitrogen (N)	0.0095 %

This document certifies that the foregoing data is furnished by the producing mill and test lab.  
 No mercury, lead, radium, or alpha containing material or equipment is used or deliberately added in the production of this steel. No weld or weld repairs were performed on this material.

*This page intentionally left blank.*

# APPENDIX C. MASH TEST 5-11 (CRASH TEST NO. 609591-03-1)

## C1 VEHICLE PROPERTIES AND INFORMATION

Table C.1. Vehicle Properties for Test No. 609591-03-1.

Date:	2018-06-28	Test No.:	609591-03-1	VIN No.:	1C6RR6FT1DS712245
Year:	2013	Make:	RAM	Model:	1500
Tire Size:	265/70 R 17	Tire Inflation Pressure:	35 PSI		
Tread Type:	HIGHWAY	Odometer:	236392		
Note any damage to the vehicle prior to test:	NONE				

• Denotes accelerometer location.


NOTES: \_\_\_\_\_

Engine Type: **V-8**  
 Engine CID: **4.7 L**

Transmission Type:  
 Auto or  Manual  
 FWD  RWD  4WD

Optional Equipment:  
**NONE**

Dummy Data:  
 Type: **50 PERCENTILE**  
 Mass: **165 LBS**  
 Seat Position: **IMPACT SIDE**



Geometry: inches									
A	78.50	F	40.00	K	20.00	P	3.00	U	27.50
B	74.00	G	29.00	L	30.00	Q	30.50	V	30.50
C	227.50	H	60.98	M	68.50	R	18.00	W	60.98
D	44.00	I	11.75	N	68.00	S	13.00	X	77.00
E	140.50	J	27.00	O	46.00	T	77.00		
Wheel Center Height Front	14.75	Wheel Well Clearance (Front)	6.00	Bottom Frame Height - Front	12.00				
Wheel Center Height Rear	14.75	Wheel Well Clearance (Rear)	9.25	Bottom Frame Height - Rear	25.50				

RANGE LIMIT: A=78 ±2 inches; C=237 ±13 inches; E=148 ±12 inches; F=39 ±3 inches; G = > 28 inches; H = 63 ±4 inches; O=43 ±4 inches; M+N/2=67 ±1.5 inches

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static	
Front	3700	M <sub>front</sub>	2908	2832	2917
Back	3900	M <sub>rear</sub>	2044	2172	2252
Total	6700	M <sub>Total</sub>	4952	5004	5169

(Allowable Range for TIM and GSM = 5000 lb ±110 lb)

Mass Distribution:	LF:	RF:	LR:	RR:
lb	1400	1432	1085	1087

**Table C.2. Measurements of Vehicle Vertical CG for Test No. 609591-03-1.**

Date: 2018-06-28 Test No.: 609591-03-1 VIN: 1C6RR6FT1DS712245  
 Year: 2013 Make: RAM Model: 1500  
 Body Style: QUAD CAB Mileage: 236392  
 Engine: 4.7L V-8 Transmission: AUTO  
 Fuel Level: EMPTY Ballast: 114 LBS (440 lb max)  
 Tire Pressure: Front: 35 psi Rear: 35 psi Size: 265/70 R 17

Measured Vehicle Weights: (lb)			
LF:	<u>1400</u>	RF:	<u>1432</u>
		Front Axle:	<u>2832</u>
LR:	<u>1085</u>	RR:	<u>1087</u>
		Rear Axle:	<u>2172</u>
Left:	<u>2485</u>	Right:	<u>2519</u>
		Total:	<u>5004</u>
			5000 ±110 lb allow ed
Wheel Base:	<u>140.50</u> inches	Track: F:	<u>68.50</u> inches
	148 ±12 inches allow ed	R:	<u>68.00</u> inches
			Track = (F+R)/2 = 67 ±1.5 inches allow ed
Center of Gravity, SAE J874 Suspension Method			
X:	<u>61.00</u> inches	Rear of Front Axle	(63 ±4 inches allow ed)
Y:	<u>0.24</u> inches	Left - Right +	of Vehicle Centerline
Z:	<u>29.00</u> inches	Above Ground	(minumum 28.0 inches allow ed)

Hood Height: 46.00 inches  
 43 ±4 inches allowed

Front Bumper Height: 27.00 inches

Front Overhang: 40.00 inches  
 39 ±3 inches allowed

Rear Bumper Height: 30.00 inches

Overall Length: 227.50 inches  
 237 ±13 inches allowed



**Table C.3. Exterior Crush Measurements for Test No. 609591-03-1.**

Date: 2018-06-28 Test No.: 609591-03-1 VIN No.: 1C6RR6FT1DS712245  
 Year: 2013 Make: RAM Model: 1500

**VEHICLE CRUSH MEASUREMENT SHEET<sup>1</sup>**

Complete When Applicable	
End Damage	Side Damage
Undeformed end width <input style="width: 50px;" type="text"/>	Bowing: B1 <input style="width: 50px;" type="text"/> X1 <input style="width: 50px;" type="text"/>
Corner shift: A1 <input style="width: 50px;" type="text"/>	B2 <input style="width: 50px;" type="text"/> X2 <input style="width: 50px;" type="text"/>
A2 <input style="width: 50px;" type="text"/>	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} = $ <input style="width: 50px;" type="text"/>
< 4 inches <input style="width: 50px;" type="text"/>	
≥ 4 inches <input style="width: 50px;" type="text"/>	

Note: Measure C<sub>1</sub> to C<sub>6</sub> from Driver to Passenger Side in Front or Rear impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L**	C <sub>1</sub>	C <sub>2</sub>	C <sub>3</sub>	C <sub>4</sub>	C <sub>5</sub>	C <sub>6</sub>	±D
		Width** (CDC)	Max*** Crush								
1	AT FT BUMPER	24	10	36	1	3	5	6	8	10	+18
2	ABOVE FT BUMPER	24	11	48	1	3	5	7	8	11	+76
	inches ▼										

<sup>1</sup>Table taken from National Accident Sampling System (NASS).

\*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.




\*\*Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

\*\*\*Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

**Table C.4. Occupant Compartment Measurements for Test No. 609591-03-1.**

Date:	2018-06-28	Test No.:	609591-03-1	VIN No.:	1C6RR6FT1DS712245
Year:	2013	Make:	RAM	Model:	1500



\*Lateral area across the cab from driver's side kickpanel to passenger's side kickpanel.

**OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT**

	Before	After inches ▼	Differ.
A1	65.00	65.00	0.00
A2	63.00	63.00	0.00
A3	65.50	64.00	-1.50
B1	45.00	45.00	0.00
B2	38.00	36.50	-1.50
B3	45.00	42.00	-3.00
B4	39.50	39.50	0.00
B5	43.00	43.00	0.00
B6	39.50	39.50	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	23.00	-3.00
D1	11.00	11.00	0.00
D2	0.00	0.00	0.00
D3	11.50	9.50	-2.00
E1	58.50	57.50	-1.00
E2	63.50	65.00	1.50
E3	63.50	63.50	0.00
E4	63.50	63.50	0.00
F	59.00	57.00	-2.00
G	59.00	59.00	0.00
H	37.50	37.50	0.00
I	37.50	36.50	-1.00
J*	25.00	22.00	-3.00

**C2 SEQUENTIAL PHOTOGRAPHS**



0.000 s



0.100 s



0.200 s



0.300 s



**Figure C.1. Sequential Photographs for Test No. 609591-03-1 (Overhead and Gut Views).**



0.400 s



0.500 s



0.600 s



0.700 s



**Figure C.1. Sequential Photographs for Test No. 609591-03-1 (Overhead and Gut Views)  
(Continued).**



0.000 s



0.100 s



0.200 s



0.300 s



0.400 s



0.500 s




0.600 s



0.700 s

**Figure C.2. Sequential Photographs for Test No. 609591-03-1 (Rear View).**



Test Number: 609591-03-1  
 Test Standard Test Number: MASH 5-11  
 Test Article: PennDOT PA Bridge Barrier  
 Test Vehicle: 2013 RAM 1500 Pickup  
 Inertial Mass: 5004 lb  
 Gross Mass: 5169 lb  
 Impact Speed: 63.2 mi/h  
 Impact Angle: 24.8°

Axes are vehicle-fixed.  
 Sequence for determining orientation:  
 1. Yaw.  
 2. Pitch.  
 3. Roll.






Figure C.3. Vehicle Angular Displacements for Test No. 609591-03-1.




**Figure C.4. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-1 (Accelerometer Located at Center of Gravity).**




**Figure C.5. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-1  
 (Accelerometer Located at Center of Gravity).**






Test Number: 609591-03-1  
 Test Standard Test Number: MASH 5-11  
 Test Article: PennDOT PA Bridge Barrier  
 Test Vehicle: 2013 RAM 1500 Pickup  
 Inertial Mass: 5004 lb  
 Gross Mass: 5169 lb  
 Impact Speed: 63.2 mi/h  
 Impact Angle: 24.8°

**Figure C.6. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-1 (Accelerometer Located at Center of Gravity).**



**Figure C.7. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-1 (Accelerometer Located Rear of Center of Gravity).**


### Y Acceleration Rear of CG



— SAE Class 60 Filter    — 50-msec average

Test Number: 609591-03-1  
Test Standard Test Number: MASH 5-11  
Test Article: PennDOT PA Bridge Barrier  
Test Vehicle: 2013 RAM 1500 Pickup  
Inertial Mass: 5004 lb  
Gross Mass: 5169 lb  
Impact Speed: 63.2 mi/h  
Impact Angle: 24.8°

**Figure C.8. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-1  
(Accelerometer Located Rear of Center of Gravity).**



**Figure C.9. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-1  
(Accelerometer Located Rear of Center of Gravity).**

# APPENIDX D. MASH TEST 5-10 (CRASH TEST NO. 609591-03-2)

## D1 VEHICLE PROPERTIES AND INFORMATION

**Table D.1. Vehicle Properties for Test No. 609591-03-2.**

Vehicle Inventory Number: **1331**

Date: **2018-06-26** Test No.: **609591-03-02** VIN No.: **KNADH4A3XB6926848**

Year: **2011** Make: **KIA** Model: **RIO**

Tire Inflation Pressure: **32 PSI** Odometer: **154005** Tire Size: **185/65R14**



Describe any damage to the vehicle prior to test: **None**

• Denotes accelerometer location.

NOTES: **None**

Engine Type: **4 cylinder**  
 Engine CID: **1.6 L**  
 Transmission Type:  
 Auto or  Manual  
 FWD  RWD  4WD  
 Optional Equipment:  
**None**

Dummy Data:  
 Type: **50th percentile male**  
 Mass: **165 LBS**  
 Seat Position: **IMPACT SIDE**



Geometry: inches										
A	66.38	F	33.00	K	12.25	P	4.12	U	14.50	
B	51.50	G		L	25.25	Q	22.50	V	19.75	
C	165.75	H	35.90	M	57.75	R	15.50	W	35.90	
D	34.00	I	7.75	N	57.70	S	8.25	X	100.65	
E	98.75	J	21.50	O	28.25	T	66.20			
Wheel Center Ht Front			11.00	Wheel Center Ht Rear			11.00	W-H		0.00

RANGE LIMIT: A = 65 ±3 inches; C = 168 ±8 inches; E = 98 ±5 inches; F = 35 ±4 inches; G = 39 ±4 inches; O = TOP OF RADIATOR SUPPORT (21 ±4 inches); M+N/2 = 56 ±2 inches; W-H < 2 inches or use MASH Paragraph A4.3.2

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front	1718	M <sub>front</sub>	1544	1629
Back	1874	M <sub>rear</sub>	883	963
Total	3638	M <sub>Total</sub>	2427	2592

Allowable TIM = 2420 lb ±55 lb | Allowable GSM = 2585 lb ± 55 lb

Mass Distribution:

lb	LF:	<b>773</b>	RF:	<b>771</b>	LR:	<b>449</b>	RR:	<b>434</b>
----	-----	------------	-----	------------	-----	------------	-----	------------

**Table D.2. Exterior Crush Measurements for Test No. 609591-03-2.**

Vehicle Inventory Number: **1331**

Date: **2018-06-26** Test No.: **609591-03-02** VIN No.: **KNADH4A3XB6926848**

Year: **2011** Make: **KIA** Model: **RIO**

**VEHICLE CRUSH MEASUREMENT SHEET<sup>1</sup>**

Complete When Applicable	
End Damage	Side Damage
Undeformed end width <input style="width: 50px;" type="text"/>	Bowing: B1 <input style="width: 30px;" type="text"/> X1 <input style="width: 30px;" type="text"/>
Corner shift: A1 <input style="width: 50px;" type="text"/>	B2 <input style="width: 30px;" type="text"/> X2 <input style="width: 30px;" type="text"/>
A2 <input style="width: 50px;" type="text"/>	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} = $ <input style="width: 50px;" type="text"/>
< 4 inches <input style="width: 50px;" type="text"/>	
≥ 4 inches <input style="width: 50px;" type="text"/>	

Note: Measure C<sub>1</sub> to C<sub>6</sub> from Driver to Passenger Side in Front or Rear impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L**	C <sub>1</sub>	C <sub>2</sub>	C <sub>3</sub>	C <sub>4</sub>	C <sub>5</sub>	C <sub>6</sub>	±D
		Width** (CDC)	Max*** Crush								
1	AT FT BUMPER	14	6	16	6	4	1				+16
2	ABOVE FT BUMPER	14	6	30	1	3			5	6	+59
	Units in inches ▼										

<sup>1</sup>Table taken from National Accident Sampling System (NASS).

\*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.




\*\*Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

\*\*\*Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

**Table D.3. Occupant Compartment Measurements for Test No. 609591-03-2.**

Vehicle Inventory Number:		1331	
Date:	2018-06-26	Test No.:	609591-03-02
		VIN No.:	KNADH4A3XB6926848
Year:	2011	Make:	KIA
		Model:	RIO



**OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT**

	Before	After inches ▼	Differ.
A1	67.50	67.50	0.00
A2	67.25	67.25	0.00
A3	67.75	67.75	0.00
B1	40.50	40.50	0.00
B2	39.00	39.00	0.00
B3	40.50	39.00	-1.50
B4	36.25	36.25	0.00
B5	36.00	36.00	0.00
B6	36.25	34.25	-2.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	25.00	-1.00
D1	9.50	9.50	0.00
D2	0.00	0.00	0.00
D3	9.50	6.50	-3.00
E1	51.50	53.25	1.75
E2	51.00	53.50	2.50
F	51.00	51.00	0.00
G	51.00	51.00	0.00
H	37.50	37.50	0.00
I	37.50	37.50	0.00
J*	51.00	51.00	0.00

\*Lateral area across the cab from driver's side kickpanel to passenger's side kickpanel.

**D2 SEQUENTIAL PHOTOGRAPHS**



0.000 s



0.100 s



0.200 s



0.300 s



**Figure D.1. Sequential Photographs for Test No. 609591-03-2 (Overhead and Gut Views).**





0.400 s



0.500 s



0.600 s



0.700 s



**Figure C.1. Sequential Photographs for Test No. 609591-03-2 (Overhead and Gut Views) (Continued).**



0.000 s



0.100 s



0.200 s



0.300 s



0.400 s



0.500 s





0.600 s



0.700 s


**Figure D.2. Sequential Photographs for Test No. 609591-03-2 (Rear View).**



Axes are vehicle-fixed.  
 Sequence for determining orientation:  
 1. Yaw.  
 2. Pitch.  
 3. Roll.


Test Number: 609591-03-2  
 Test Standard Test Number: MASH 5-10  
 Test Article: PennDOT PA Bridge Barrier  
 Test Vehicle: 2011 Kia Rio  
 Inertial Mass: 2,427 lb  
 Gross Mass: 2,592 lb  
 Impact Speed: 61.7 mi/h  
 Impact Angle: 25.3°

Figure D.3. Vehicle Angular Displacements for Test No. 609591-03-2.




Test Number: 609591-03-2  
Test Standard Test Number: MASH 5-10  
Test Article: PennDOT PA Bridge Barrier  
Test Vehicle: 1100C, Small Car  
Inertial Mass: 2,427 lb  
Gross Mass: 2,592 lb  
Impact Speed: 61.7 mi/h  
Impact Angle: 25.3°

**Figure D.4. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-2  
(Accelerometer Located at Center of Gravity).**




Test Number: 609591-03-2  
Test Standard Test Number: MASH 5-10  
Test Article: PennDOT PA Bridge Barrier  
Test Vehicle: 1100C, Small Car  
Inertial Mass: 2,427 lb  
Gross Mass: 2,592 lb  
Impact Speed: 61.7 mi/h  
Impact Angle: 25.3°


**Figure D.5. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-2  
(Accelerometer Located at Center of Gravity).**



**Figure D.6. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-2  
(Accelerometer Located at Center of Gravity).**




**Figure D.7. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-2 (Accelerometer Located Rear of Center of Gravity).**



**Figure D.8. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-2  
(Accelerometer Located Rear of Center of Gravity).**





**Figure D.9. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-2 (Accelerometer Located Rear of Center of Gravity).**

*This page intentionally left blank.*

# APPENIDX E. MASH TEST 5-12 (CRASH TEST NO. 609591-03-3)

## E1 VEHICLE PROPERTIES AND INFORMATION

Table E.1. Vehicle Properties for Test No. 609591-03-3.

Vehicle Inventory Number: **13001299**


DATE: **2018-07-03** TEST NO.: **609591-03-3**

**TRACTOR**  
 YEAR: **2008** MAKE: **FREIGHTLINER** MODEL: **CL 120**

VIN No.: **1FUJA6CV68DAA5274** ODOMETER: **846,840**

**TRAILER**  
 YEAR: **2002** MAKE: **UTILITY** MODEL: **53'**

VIN No.: **1UYVS25302P787333**




**GEOMETRY ( inches )**

A	96.00	D	50.00	G		K	50.00	O	15.00	R	73.00	U	23.00
B	48.00	E	459.00	H	72.50	L	49.00	P	79.50	S	12.00	V	32.00
C	144.00	F	48.00	J	67.00	M	34.50	Q	73.00	T	40.00	W	148.00

Allowable Range: C = 200 inches max.; L = 52 ±2 inches; Overall Trailer Length = 600 inches max.; Overall Combination Length = 780 inches max.; Trailer Overhang = 87 inches max.; Ballast Center of Mass Ht = 73 ±2 inches above ground;

MASS ( lb )	CURB	TEST INERTIAL
M <sub>1</sub>	8800	11250
M <sub>2</sub>	4960	18080.00
M <sub>3</sub>	4920	16770
M <sub>4</sub>	5890	17880
M <sub>5</sub>	4180	15300
M <sub>Total</sub>	28750	79280
	Allowable Range 29,000 ±3100 lb	Allowable Range 79,300 ±1100 lb

Height above ground:  
 A: 33 inches  
 B: 32 inches  
 C: 49.5 inches



**Figure E.1. Location of Accelerometers and Rate Transducers.**

**E2 SEQUENTIAL PHOTOGRAPHS**



0.000 s



0.185 s



0.370 s



0.555 s



**Figure E.2. Sequential Photographs for Test No. 609591-03-3 (Overhead and Gut Views).**



0.740 s



0.925 s



1.110 s



1.295 s



**Figure E.2. Sequential Photographs for Test No. 609591-03-3 (Overhead and Gut Views) (Continued).**



0.000 s



0.185 s



0.370 s



0.555 s



0.740 s



0.925 s




1.110 s



1.295 s


**Figure E.3. Sequential Photographs for Test No. 609591-03-3 (Rear View).**



— Roll — Pitch — Yaw


Test Number: 609591-03-3  
 Test Standard Test Number: MASH 5-12  
 Test Article: PennDOT PA Bridge Barrier  
 Test Vehicle: 2008 Freightliner CL120/2002 Utility 53ft  
 Inertial Mass: 79,280 lb  
 Gross Mass: 79,280 lb  
 Impact Speed: 49.9  
 Impact Angle: 14.8°

Axes are vehicle-fixed.  
 Sequence for determining orientation:  
 1. Yaw.  
 2. Pitch.  
 3. Roll.



**Figure E.4. Vehicle Angular Displacements for Test No. 609591-03-3.  
(Accelerometer Located at Fifth Wheel)**






Test Number: 609591-03-3  
Test Standard Test Number: MASH 5-12  
Test Article: PennDOT PA Bridge Barrier  
Test Vehicle: 2008 Freightliner CL120/2002 Utility 53ft  
Inertial Mass: 79,280 lb  
Gross Mass: 79,280 lb  
Impact Speed: 49.9  
Impact Angle: 14.8°


**Figure E.5. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located at Fifth Wheel).**

### Y Acceleration at Fifth Wheel



**Figure E.6. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located at Fifth Wheel).**


### Z Acceleration at Fifth Wheel



— SAE Class 60 Filter    — 50-msec average

Test Number: 609591-03-3  
Test Standard Test Number: MASH 5-12  
Test Article: PennDOT PA Bridge Barrier  
Test Vehicle: 2008 Freightliner CL120/2002 Utility 53ft  
Inertial Mass: 79,280 lb  
Gross Mass: 79,280 lb  
Impact Speed: 49.9  
Impact Angle: 14.8°

**Figure E.7. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-3  
(Accelerometer Located at Fifth Wheel).**




— SAE Class 60 Filter    — 50-msec average

Test Number: 609591-03-3  
 Test Standard Test Number: MASH 5-12  
 Test Article: PennDOT PA Bridge Barrier  
 Test Vehicle: 2008 Freightliner CL120/2002 Utility 53ft  
 Inertial Mass: 79,280 lb  
 Gross Mass: 79,280 lb  
 Impact Speed: 49.9  
 Impact Angle: 14.8°

**Figure E.8. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-3  
(Accelerometer Located Rear of Trailer).**


### Y Acceleration Rear of Trailer




— SAE Class 60 Filter — 50-msec average

Test Number: 609591-03-3  
Test Standard Test Number: MASH 5-12  
Test Article: PennDOT PA Bridge Barrier  
Test Vehicle: 2008 Freightliner CL120/2002 Utility 53ft  
Inertial Mass: 79,280 lb  
Gross Mass: 79,280 lb  
Impact Speed: 49.9  
Impact Angle: 14.8°


Figure E.9. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located Rear of Trailer).



**Figure E.10. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-3  
(Accelerometer Located Rear of Trailer)**




**Figure E.11. Vehicle Longitudinal Accelerometer Trace for Test No. 609591-03-3 (Accelerometer Located at Tractor).**



**Figure E.12. Vehicle Lateral Accelerometer Trace for Test No. 609591-03-3  
(Accelerometer Located at Tractor).**





**Figure E.13. Vehicle Vertical Accelerometer Trace for Test No. 609591-03-3  
(Accelerometer Located at Tractor)**

# SI\* (MODERN METRIC) CONVERSION FACTORS

## APPROXIMATE CONVERSIONS TO SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
<b>LENGTH</b>				
in	inches	25.4	millimeters	mm
ft	feet	0.305	meters	m
yd	yards	0.914	meters	m
mi	miles	1.61	kilometers	km
<b>AREA</b>				
in <sup>2</sup>	square inches	645.2	square millimeters	mm <sup>2</sup>
ft <sup>2</sup>	square feet	0.093	square meters	m <sup>2</sup>
yd <sup>2</sup>	square yards	0.836	square meters	m <sup>2</sup>
ac	acres	0.405	hectares	ha
mi <sup>2</sup>	square miles	2.59	square kilometers	km <sup>2</sup>
<b>VOLUME</b>				
fl oz	fluid ounces	29.57	milliliters	mL
gal	gallons	3.785	liters	L
ft <sup>3</sup>	cubic feet	0.028	cubic meters	m <sup>3</sup>
yd <sup>3</sup>	cubic yards	0.765	cubic meters	m <sup>3</sup>
NOTE: volumes greater than 1000L shall be shown in m <sup>3</sup>				
<b>MASS</b>				
oz	ounces	28.35	grams	g
lb	pounds	0.454	kilograms	kg
T	short tons (2000 lb)	0.907	megagrams (or metric ton")	Mg (or "t")
<b>TEMPERATURE (exact degrees)</b>				
°F	Fahrenheit	5(F-32)/9 or (F-32)/1.8	Celsius	°C
<b>ILLUMINATION</b>				
fc	foot-candles	10.76	lux	lx
fl	foot-Lamberts	3.426	candela/m <sup>2</sup>	cd/m <sup>2</sup>
<b>FORCE and PRESSURE or STRESS</b>				
lbf	poundforce	4.45	newtons	N
lbf/in <sup>2</sup>	poundforce per square inch	6.89	kilopascals	kPa

## APPROXIMATE CONVERSIONS FROM SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
<b>LENGTH</b>				
mm	millimeters	0.039	inches	in
m	meters	3.28	feet	ft
m	meters	1.09	yards	yd
km	kilometers	0.621	miles	mi
<b>AREA</b>				
mm <sup>2</sup>	square millimeters	0.0016	square inches	in <sup>2</sup>
m <sup>2</sup>	square meters	10.764	square feet	ft <sup>2</sup>
m <sup>2</sup>	square meters	1.195	square yards	yd <sup>2</sup>
ha	hectares	2.47	acres	ac
km <sup>2</sup>	Square kilometers	0.386	square miles	mi <sup>2</sup>
<b>VOLUME</b>				
mL	milliliters	0.034	fluid ounces	oz
L	liters	0.264	gallons	gal
m <sup>3</sup>	cubic meters	35.314	cubic feet	ft <sup>3</sup>
m <sup>3</sup>	cubic meters	1.307	cubic yards	yd <sup>3</sup>
<b>MASS</b>				
g	grams	0.035	ounces	oz
kg	kilograms	2.202	pounds	lb
Mg (or "t")	megagrams (or "metric ton")	1.103	short tons (2000lb)	T
<b>TEMPERATURE (exact degrees)</b>				
°C	Celsius	1.8C+32	Fahrenheit	°F
<b>ILLUMINATION</b>				
lx	lux	0.0929	foot-candles	fc
cd/m <sup>2</sup>	candela/m <sup>2</sup>	0.2919	foot-Lamberts	fl
<b>FORCE and PRESSURE or STRESS</b>				
N	newtons	0.225	poundforce	lbf
kPa	kilopascals	0.145	poundforce per square inch	lb/in <sup>2</sup>

\*SI is the symbol for the International System of Units. Appropriate rounding should be made to comply with Section 4 of ASTM E380. (Revised March 2003)